



**DEPARTMENT OF PHILOSOPHY,
LINGUISTICS AND THEORY OF SCIENCE**

EMERGENCE OF REFERRING EXPRESSIONS THROUGH LANGUAGE GAMES

Dominik Künkele

Master's Thesis:	30 credits
Programme:	Master's Programme in Language Technology
Level:	Advanced level
Semester and year:	Spring, 2023
Supervisor:	Simon Dobnik
Examiner:	Asad Sayeed
Keywords:	referring expressions, language games, artificial 3-d dataset

Abstract

There has been a recent focus on how neural agents in language games ground referring expressions in visual 3D-scenes. This thesis explores when referring expressions emerge and if they align with referring expression found in natural languages like English. For this, multiple new artificial datasets based on the CLEVR dataset are generated to control precisely for the bias included in the visual scenes, namely the attributes of the target object and distractors. The datasets and their controlled biases are validated in a series of reference expression generation and comprehension tasks. A sender and a receiver are playing language games in which they need communicate referring expressions to solve the same tasks. For many tasks, they are able to successfully ground referring expressions in their own emerged language. An analysis of the emerged languages shows that the emerged referring expressions are aligned very few with natural language referring expressions. However, they share certain features like an incremental approach in which some attributes are consistently used more often than others.

Contents

1	Introduction	1
1.1	Research Questions	2
1.2	Contribution	2
1.3	Scope	3
2	Background and Related Work	4
2.1	Grounding	4
2.2	Referring expressions	5
2.3	Language Games	8
2.3.1	Setup of language games	9
2.3.2	Properties of the emerged language	10
2.4	Artificial dataset	11
3	Methodology and Frameworks	13
3.1	CLEVR framework	13
3.2	Feature extractors	14
3.3	Image processing	15
3.4	EGG framework	17
3.5	Optimization in language games	18
3.6	Ethical considerations	19
4	Creation of the datasets	21
4.1	CLEVR single	21
4.2	CLEVR color	22
4.3	CLEVR Dale datasets	23
5	Grounding referring expressions	24
5.1	Object identification	25
5.2	Referring expression generation	28
5.3	Reference resolution	37
6	Grounding referring expressions in language games	49
6.1	Object identification	51
6.2	Referring expression generation	57

6.3	Reference resolution	66
7	Analysis of the emerged languages	74
7.1	Object identification	76
7.2	Referring expression generation	79
7.3	Reference resolution	85
8	Discussion	87
9	Conclusion and future work	92
	References	94

1 Introduction

Language is a complex system that enables humans to communicate and convey meaning. However, the mere existence of words and grammatical structures is not enough to guarantee effective communication. Without grounding, language remains detached from the physical world, making it difficult for individuals to comprehend and interpret linguistic expressions accurately. Grounding bridges the gap between abstract linguistic representations and concrete experiences, providing a shared context and reference point for language users (Roy, 2002; Bisk et al., 2020; Bender & Koller, 2020). By linking language to sensory perceptions, physical experiences, and the situational context, grounding enhances comprehension, facilitates communication. However, one challenge lies in how arbitrary symbols in language can be connected to real-world objects and concepts and acquire meaning, described as the symbol grounding problem by Harnad (1990). Artificial agents can be taught grounding in different ways. One approach is to show the agent an image of the scene as visual input together with a textual description of what is to be grounded in this scene. This can be for example a description of the whole scene, certain visible objects or also actions that are happening (Ahrens et al., 2022; Ilinykh et al., 2022; Lu et al., 2017; Mitchell et al., 2013). By doing this, the agents can learn to identify the same descriptions and symbols for similar visual input. In other approaches, the agents can learn to ground language in visual input through interaction and dialogue, either with humans or other agents. Thus, agents might develop certain strategies to ground language efficiently (Dobnik & Storckenfeldt, 2018; Dobnik & Silfversparre, 2021; Zarri   & Schlangen, 2019).

A central part in many of the ways to learn to ground are referring expressions. Referring expressions are used to point out a particular subset of entities from a set of similar entities or the surrounding context. By that, they can take many forms as noun phrases (e.g. 'the large table', 'the second chair from the right'), proper nouns (e.g. 'Francesca', 'the Big Ben') or complete descriptions (e.g. 'the men that are wearing glasses'). When referring to objects, they often include inherent attributes of these objects as their color or shape. Furthermore, spatial terms play a vital role to refer to and disambiguate objects (Regier, 1996; Dobnik & Kelleher, 2013; Dobnik & Silfversparre, 2021; Ghanimifard & Dobnik, 2017; Ramisa et al., 2015).

One problem that arises is the question of ambiguity in language and referring expressions. Natural language is often used in an underspecified way. Interlocutors rely on pragmatic and semantic context to communicate, particular interlocutors share a common ground which is used to disambiguate referring expressions. In case a common ground is not shared, referring expressions might be misunderstood, because of their underspecification.

Furthermore, the real world is characterized by its continuous nature. On the other side, natural language is a set of discrete symbols. In the process of mapping this continuum to the discrete symbols, information is lost, since the whole context of the real world can't be captured by the natural language. By this, symbols get ambiguous and refer to multiple concepts in the world. One example are the shades of color (Zaslavsky et al., 2018). Discrete English terms like 'red', 'green' or 'blue' might refer to an infinite number of colors in the real world.

To deal with this, humans rely on communicative protocols to disambiguate referring expressions. Dale & Reiter (1995), for instance, describe an incremental algorithm how referring expressions are generated. The goal of the algorithm is to construct referring expressions incrementally, taking into account the salience of different properties and abstracting away from differences in lexical choice. It works by gradually building up a referring expression based on the properties of the object being referred to. Hereby, it considers the most salient or distinguishing properties first and then adds additional properties as needed. This helps to create concise, effective and unambiguous referring expressions.

On the other side, humans as well as machines need to be able to comprehend referring expressions. Often

this task is defined as identifying a unique target object from a set of distractors in a visual scene (Mao et al., 2016). Hereby, many different architectures for models are studied that try to solve this task (Qiao et al., 2020). In some approaches the models for example embed both the referring expression and bounding boxes around objects in the visual scene in the same embedding space to align them. In other approaches, models don't rely on bounding boxes, but extract features from the whole visual scene and combine them with the referring expression in one step. An extension of referring expression comprehension are visual question and answering tasks (VQA), in which a model is presented with a question and a visual scene that should be used to answer the question (e.g. (Antol et al., 2015)). In these tasks, the model often needs to extract multiple referring expressions at the same time and ground them in the visual scene.

Meaning of symbols and referring expression emerge through dialogue between interlocutors (Wittgenstein, 1953; Clark & Wilkes-Gibbs, 1986). Moreover, Wittgenstein (1953) introduces the concept of *language games*: small parts of conversation between interlocutors. In these language games, their context defines which meaning emerges for the referring expressions. This reasoning was taken up in training artificial agents to learn to refer to entities. Hereby, agents need to communicate arbitrary symbols to each other in multiple turns to solve a given task. By solving the task, they assign meaning to these symbols and an artificial language emerges. This setup allows to control the architecture of the agents, the information the agents receive, how and what they are able to communicate and which goals they are trained on. By this, their behavior and the emergence of referring expressions can be studied precisely and consistently. In early research, agents and their communication were studied in the context of robotics and rule-based systems (Steels & Loetzsch, 2009; Roy, 2002; Kirby, 2002; Kirby et al., 2008), while in current research, agents are based on deep neural networks (Lazaridou et al., 2017; Baroni, 2020; Baroni et al., 2022; Kottur et al., 2017). Furthermore, a focus lies on the nature of the emerged language. Agents can for instance learn a compositional language that allows them to combine already learned symbols to create new meaning, when presented with a changed environment and unseen situations (Kharitonov & Baroni, 2020; Lazaridou et al., 2018; Gupta et al., 2020). Additionally, emergent languages can be learned to encode meaning in efficient ways (Chaabouni et al., 2019; Zaslavsky et al., 2018).

1.1 Research Questions

In this thesis, a deeper look is taken into how agents can ground their emerged language in visual input. The focus hereby lies on referring expressions and how agents are able to generate and understand them. Multiple experiments are designed in a way that agents need to use referring expressions in their messages that are communicated. These messages are analyzed with respect to the visual input to answer the two following questions:

1. What are the limits of the agents' architectures, the environment, and input representations on learning successfully grounding referring expressions through language games?
2. To what degree do emergent referring expressions align with referring expressions in a natural language such as English and what constraints can be imposed on the environment and the agents themselves that languages align?

1.2 Contribution

This thesis aims to add three contributions to the field of research. First, new artificial visual datasets are created, consisting of images, depicting objects and their attribute and spatial relations. Many existing datasets that are used to study referring expressions use real photos taken by humans. This adds a lot of inherent bias to the dataset, since these photos for instance often focus on similar objects and actions. Additionally, they require external knowledge about the world and the functions of objects which is not

present in the image. Furthermore, information about the objects and their relations in the image are not present in a structured way. The datasets that are created in this thesis aim to reduce this bias and provide all information about the scene and objects in the image. In fact, the artificial creation of the dataset allows controlling precisely for the bias in each scene which can be utilized by agents in a language game.

Secondly, the thesis evaluates these datasets, by training separate models to generate and understand referring expressions, describing objects in the images. By doing this, it is tested if first the models are able to extract useful visual information that doesn't rely on bias and latent patterns in the textual information in the dataset and secondly shows the impact of different levels of ambiguity in the datasets on the performance of generating and understanding of referring expressions.

Lastly, the thesis brings the separate tasks of generating and understanding of referring expressions together into one single task. This process resembles the learning of referring expressions in natural language (Clark & Wilkes-Gibbs, 1986). In language games, one agent needs to extract visual information from an image and generate a referring expression that is sent to the second agent. The second agent on the other hand needs to understand this referring expressions and combine it with its visual input. Only if both of these subtasks succeed, a new artificial language can emerge and the overall task can be solved. The emerging language is then analyzed to understand, how the artificial referring expressions are built up and compare to natural language.

1.3 Scope

The focus of this thesis is the study of referring expressions. Referring expressions can hereby be based on inherent attributes of objects, as well as their spatial relations towards other objects. In the present study, only the relations of the inherent attributes are studied. Spatial relations add another level of complexity and may be studied in future work. Furthermore, the emerged language will be interpreted by comparing it to referring expressions in natural language. This analysis focuses on the emerged meaning of symbols and if they align with natural language. A deeper study of its compositionality or complexity is out of scope.

2 Background and Related Work

2.1 Grounding

Symbols of a symbolic system such as words in a natural language are typically processed and manipulated in a purely formal manner, without direct reference to their real-world concepts. The question arises, how these symbols can acquire meaning and be connected to the real world without any external interpreter, in other words how the symbols can be grounded in the real world. This is known as the symbol grounding problem (Harnad, 1990). Hereby, Harnad (1990) describes that a high-order *symbolic representation* needs to be grounded bottom-up in two non-symbolic representations. *Iconic representations* refer to analogue representations of sensory input like for instance vision in the retina. These representations are mapped to *categorical representations* which are filtered clusters of the iconic representation. These categories are assigned so-called elementary symbols, in which symbolic representation are grounded.

In computational models this problem is tried to be solved in multiple ways. Recent large language models (LLMs) such as BERT (Devlin et al., 2019) or GPT-3 (Brown et al., 2020) are often trained on big amounts of text corpora produce impressive results on many tasks in Natural Language Processing. Meaning of symbols emerges through relating it to its surrounding context of other symbols it appears in. In this way, their only way of learning, how to generate language as well as solve these tasks is to find patterns of how words and sentences are used in these large corpora. This approach is however criticized by many researchers, since the meaning of symbols is still not connected to the real world and only relies on other symbols in an infinite recursion.

In (Bender & Koller, 2020), the authors argue that meaning is bound to a communicative intent. These are the purposes of why humans are using language. The intent is always embedded in a broader context that exists outside the language itself. This context includes the real world, but also the background knowledge of the speaker as well as interlocutors or reason for what the speaker is saying. By grounding the intent in this context, it becomes meaningful. Only with this step, the intent can be interpreted by the listeners. This grounding is missing when models only train on abstract textual representations of the world (Regier, 1996; Landau et al., 1998).

Bisk et al. (2020) argues that a multimodal approach, including for instance perception as well as social context, is needed to learn meaning in a broader context. One added modality to ground language is often visual input. Hereby, the model needs to learn how to associate linguistic concepts in text corpora with features, extracted from visual input. For instance, a model can learn to associate the noun "dog" with an animal seen in an image or associate the action of "jumping over" with the animal being above an object. Roy (2002) for example studies how an artificial agent can ground spatial relations with a visual scene of geometric shapes. Hereby, the agent builds up hierarchical knowledge that is used to produce correct description in a rule-based manner. In more recent research, complete natural language utterances as well as the visual representations are mapped into an embedding space. By aligning both representations, natural language can be connected to a second modality. Other research explores how to ground smaller parts of the utterances, as phrases and words and combine them compositional (Larsson, 2018; Kollar et al., 2010). This might allow artificial machines to learn grounded concepts more general.

Furthermore, artificial agents can learn to ground language through dialogue, either with human tutors or with other artificial agents. Skocaj et al. (2011) for example teach a robot different objects and concepts. By asking questions and participating in the dialogue with a human tutor, the robot builds up and verifies beliefs, and connects them to language and its visual input. Lauria et al. (2001) follow a similar approach where a robot is taught to follow instructions to generate a map of its physical surroundings. By incorporating dialogue and deep-level reasoning questions the learning gains are enhanced. How artificial agents can ground language in dialogue between each other will be studied in this thesis. Section 2.3 gives an insight

in the state of the research.

2.2 Referring expressions

A specific case of grounding linguistic information in visual input are referring expressions. While a general linguistic expression can be grounded in multiple regions of a visual scene, referring expressions are expected to refer to a unique region (Sánchez et al., 2022). Given for example a visual scene with multiple pens lying on a table, the word 'pen' can be grounded in all visible objects. A referring expression like 'the red pen on the left' in contrast would only refer to one specific object. Referring expressions are however not limited to refer to one single entity, but might also refer to a group of objects as for instance with 'the green pens'. Still they refer to a specific subset of entities and concepts.

Hereby, Krahmer & van Deemter (2012) classify referring expressions into four categories: *One-place predicates* refer to one single entity in the visual scene without. By this, the entity is identifiable without using another entity as basis. Often, the referring expressions includes intrinsic attributes of an object or absolute locations in the scene as in 'the red pen on the left'. *Relational* referring expressions refer to entities via other entities in the scene. Accordingly, a relating between the target entity and distractors is described. This includes for example spatial relations like 'the pen behind the cup' or relations based on the entities' properties like 'the largest pen'. Referring expressions can also identify *sets* of entities. Instead of uniquely referring to on single pen, the referring expression 'the green pens' refers to all objects that are pens and that are green. Finally, *gradable* referring expressions involve gradable properties as opposed to absolute values. For example, given the referring expression 'the tall building', 'tall' is a gradable property because it can be measured on a scale. The success of the referring expression depends on how well it captures the intended level of height compared to other buildings. By this, vagueness is introduced and referring expressions depend on context, either present in the visual scene or pragmatic context.

One of the main challenges of referring expressions lies in ambiguity. Ambiguity is introduced in two forms. First, there is an inherent difference in natural language and the real world it is grounded in, also described in the symbol grounding problem. The nature of the world is continuous, while natural language being a formal symbol system uses discrete symbols. In especially, natural language utilizes a very limited set of symbols to represent the world. When trying to map continuous concepts to this limited set of discrete symbols, information necessarily gets lost. Apparent examples are the color systems in human languages. While color grades exist on an infinite spectrum in the real world, languages combine certain color grades into categories (Zaslavsky et al., 2018). The word 'red' for example refers to many different shades of red. Even more, the shades of color it actually refers to depends also on the pragmatic context and the people uttering it (Monroe et al., 2017). The same also applies to spatial references. References like 'near to' or 'left to' might refer to objects that are touching each other, but in other contexts also are kilometers away from each other.

The other form of ambiguity is introduced through under-specification of the speakers (e.g. Dobnik & Silfersparre (2021)). When interlocutors interact in a dialogue, they share some common knowledge. The first interlocutor might presuppose that the second interlocutor knows a certain fact. Based on this, they might utter a referring expression that together with this shared fact uniquely identifies an entity. However, the referring expression on its own is under-specified and might refer to multiple entities. Given for example the following situation: Two people are in a room with their beverages standing on the table and Person A requests his beverage from Person B. A referring expression like 'the beverage close to me' would uniquely identify one of the beverages. Despite that, Person A might more likely use 'the beverage' to refer to theirs. On its own, the referring expression is under-specified and can refer to both of the present beverages. However, both persons share the fact that the targeted beverage belongs to person A, which disambiguates the referring expression in this context. In another context, the shared fact would be that Person A wants to try the beverage of Person B. Again, this fact would disambiguate the referring expression, but now refer

to the second beverage. The referring expression is the same in both contexts, but refers to two different entities. This creates a challenge for computational models, that need to understand and generate referring expressions if they are only presented with the text, but not with the shared context.

The research of referring expressions can be split into two fields: referring expression generation (REG) and referring expression comprehension (REC). In **referring expression generation**, computational models are trained to generate a referring expression that uniquely identifies an entity given some perceptual, often visual input. The research goes back into the 70s, where [Winograd \(1972\)](#) developed an algorithm to generate referring expressions step by step, taking into account the context and the information available at each stage of the generation process. A similar approach is described in [\(Dale & Reiter, 1995\)](#). Their incremental algorithm is based on the salience of the properties of the present target object and distractor objects. The most salient properties are considered first, and added to the referring expression until the referring expression is unambiguous. In other words, the object is described unambiguously using the lowest number of words.




Figure 1: The target object in this scene is the *small turquoise sphere*. Using the incremental GRE-algorithm, the target object can be uniquely referred to as *turquoise sphere*

Given for example the scene in Figure 1. Objects in this scene have three attributes that we consider in the following order of salience: a shape, a color and a size. This order defines, which attributes can be left out, while still identifying the object uniquely. The target object in the given scene is the *small turquoise sphere*. In the first step, the attribute with the highest salience, the shape, is selected from the target object. This produces the referring expression *sphere*. In the next step, it is checked if there are also distractors, described by this referring expression. In our case, both cubes and the cylinder are already disambiguated, but the purple sphere can still be described by the produced referring expression. Therefore, the algorithm also adds the next lower salient attribute, the color to the referring expression, which produces the *turquoise sphere*. With this, also the last remaining distractor is as well disambiguated, and the referring expression describes the target object uniquely. The size, the least salient property is therefore not necessary in the referring expression. This algorithm will be utilized in this thesis and will be referred to as *the incremental GRE-algorithm*.

Additional to generating an efficient disambiguating referring expressions, a challenge also lies in processing the visual input. This especially applies to spatial and geometric positions and relations of objects in a scene, where models struggle to extract geometric information from visual features ([Kelleher & Dobnik, 2017](#)). More complex scenes also involve multiple perspectives, where the models are tasked to produce referring expressions that depend on the spatial perspective of the speaker and the listener ([Ahrens et al., 2022](#); [Lee et al., 2022](#)). In ([Dobnik & Silfversparre, 2021](#)), visual dialogue is analyzed where speakers have different views on cups that are placed on a table. When speakers refer to a certain cup, they need to take the perspective of the listener to disambiguate the referring expression; for instance in the referring expression 'the cup on the left', *left* is dependent on the speaker's and listeners' spatial position in relation to the cup.

Current research focuses hereby on generating relational referring expressions, which add more complexity to the task (Ghanimifard & Dobnik, 2017, 2019; Ramisa et al., 2015; Liu et al., 2023). Models need to first extract visual features of multiple objects from the scene. Of these extracted objects, a meaningful landmark object needs to be found which helps to refer to the target object. Finally, they need to find proper relations between them to describe the target object. Relations can be mostly based on the geometric and spatial relation of two objects (e.g. above/below), while the function of objects play a stronger role in other relations (e.g. over/under) (Coventry et al., 2005; Dobnik & Kelleher, 2013).

Referring generation tasks can be hard to evaluate, since often there are many possible referring expressions that are possible and uniquely identify the target object (Mao et al., 2016). Instead, the task can be turned around: A model needs to identify an object when presented with a referring expression. This is called **referring expressions comprehension**. Many challenges remain similar to the REG task, since the model needs to extract disambiguating visual features from the scenes as well. However, the goal is typically to select the best matching region of a given choice in a visual scene (Qiao et al., 2020). They describe seven different approaches how the challenge is approached in the current research. In *joint embedding* approaches, both visual input and the textual referring expressions are embedded into the same embedding space. By doing this, the model is able to find similarities and combine them. In some cases, an attention mechanism is applied on top. This allows the model to focus on important parts of each representation for the specific task. *Modular models* are split up in multiple submodels that split up the complete task and solve them step by step. This helps to reduce the complexity of a task, as well as making more transparent, where models fail and succeed. *Graph-based models* try to make use of the structure in a visual scene when multiple objects are present and the model is tasked to disambiguate them. In a first step, the visual features of the image are transferred into a graph that captures objects’ properties and their relations. This graph is then combined with the referring expression to extract, which of the nodes is represented by it. To give a bigger focus on syntactic and semantic structure in a referring expression (which might get underrepresented by sentence-level representations of e.g. an LSTM), some models utilize *external parsers*. These make use classical methods as for example dependency parsers, to parse the referring expressions. *Weakly supervised* models are used when there is a lack of large datasets that annotate the relation between a referring expression and the corresponding regions in the image. Instead, they can operate on datasets that only include the visual scene with a matching referring expression. This is done by selecting a matching region in the visual scene and then reproducing the input referring expression from that region. During testing, the model only extracts the region from a given referring expression. While most of the described approaches grounding the referring expression in multiple steps, by first identifying possible regions around objects in the visual scene and then combining each proposal with the representation of the referring expression, *one-stage approaches* combine them into one step. The image is processed as a whole and combined with the embedded referring expression. The model then predicts a bounding box around the referred entity. Finally, *Visual-Language pre-training* tries to jointly learn from visual and textual representations, instead of separate visual and textual processors in the other approaches. Models like ViLBERT (Lu et al., 2019) learn joint representations of language and visual input. These can then be fine-tuned on the specific referring expression comprehension task.

Closely related to the REC task is visual question and answering (VQA) (Ahrens et al., 2022; Antol et al., 2015; Ilinykh et al., 2022; Xu & Saenko, 2016). In these tasks, a model is given a question about a visual scene. The goal is to find an answer in the scene and generate an answer. Central to this is to extract referring expressions from the question and ground them in the visual scene. In (Johnson et al., 2017b), a model is for example shown an image similar to Figure 1 and asked the question ‘Is there a blue cube with the same size as the purple cylinder?’. To answer this, the model needs to understand two referring expressions and try to ground them in the image. In some cases the model can’t ground a referring expression, when no object in the scene matches the referring expression. In the paper, it is solved by using a modular design of the model, where in a first step the question is translated into a sequence of instructions that defines, how the model is supposed to extract information from the image. In the first part, the referring expression is

parsed, while in the second part the model grounds it in the visual input.

2.3 Language Games

In this thesis, referring expression generation and referring expression comprehension are studied at the same time. This is done by using language games between two artificial agents. The term 'language games' was first introduced by [Wittgenstein \(1953\)](#). Following his argumentation, meaning of words and language is not absolute, but is situated in human dialogue. Hereby, two interlocutors converse in language games, that define how the utterances are meant and interpreted. The words' meaning is not just based on the context or surrounding words, but more on the situation, including pragmatic and social context. The rules in each of these situations differ and therefore the meanings and semantics of words and sentences may differ from situation to situation. This is summarized as a language game. These can be any small parts of conversations, for instance between a teacher explaining a new concept to a student, or between two people, discussing a specific topic. An interjection 'Water!' may be a warning, an answer to a question, a request or something else, depending on the context. This applies as well to the ambiguous referring expressions, as in the example about the beverages described in [Section 2.2](#). Which referring expression Person A uses to ask for the beverage, depends on the assumed shared knowledge. With other interlocutors or situations, different referring expressions are uttered.

This reasoning was taken up when trying to train artificial entities to produce a language. One of the original games is the signaling game, proposed by [Lewis \(1969\)](#). These games are composed of a sender and a receiver. The sender has access to the state of the world, while the receiver does not. The sender can choose from a fixed set of signals to communicate information to the receiver. The receiver, upon receiving the signal, must take an action based on that information. The goal of both sender and receiver is for the receiver to take the correct action in every state, as both players have a common interest in achieving the same outcomes. Both sender and receiver are rewarded in the same way if the proposed action was correct. Hence, both agents need to invent a language together, fit to the conditions of the game.

The study of the emergence of an artificial language serves multiple goals. First, the study of the emergence of artificial language can help to shed light into why and how natural languages evolved ([Bartlett & Kazakov, 2005](#); [Kirby, 2002](#); [Kirby et al., 2008](#); [Noukhovitch et al., 2021](#)). This approach allows a deep study of the constraints and restrictions that are necessary so that symbols start to be connected with meaning and get grounded in the real world. Insights in this field might give indications for in which circumstances natural language evolves. On the other hand, research analyzes how the emerged language looks and how the agents represent information in messages and symbols ([Baroni et al., 2022](#); [Lazaridou et al., 2017](#); [Chaabouni et al., 2022](#); [Kottur et al., 2017](#)). Some studies observe different properties of the emerged languages, such as compositionality, complexity or efficiency, and study how the agents can be biased towards producing a language that holds certain properties. Eventually, this can produce languages that agents can use in practical applications instead of relying on the predefined inflexible protocols that are currently used.

In language games it is central that the means of communication are very restricted. Typically, the agents are given a set of arbitrary symbols, a vocabulary, that the agents can use to convey information. These symbols initially don't have any meaning, but by using and interpreting them repeatedly to solve the task the agents learn to use certain of those symbols, to encode specific information. By this, a new artificial language emerges between these agents. The emergence of a language however is highly dependent on the constraints posed on (1) the agents' architectures, (2) the way of communication, (3) the perceptual input for the agents and (4) the task they need to solve ([Baroni et al., 2022](#)).

In ([Steels & Loetzsch, 2009](#)) two robots are trained by using language games. The authors explore how spatial language, more specifically language that focuses on spatial positions and movements, emerges when the agents are situated in the real world and can perceive each other. Two robots equipped with a camera

are moving freely in a space until they see each other as well as the target object of the game. The target object is moved by the researchers, and that movement is registered by both robots. The robots now need to communicate the movement to each other using language games. Hereby, the experiments show that when agents are embodied and have a specific view on the surrounding world the capability of aligning their own perspective with the other’s is central for the success of communication and the emergence of a language.

In more recent work, deep neural models are utilized for the agents. Instead of being embodied, agents only receive visual input, without any perception that the other agent is present. In (Lazaridou et al., 2017), two agents play a discrimination game. The same set of images is shown to both agents. While they are unordered for the receiver, the sender always sees the target image as its first image. The task is now for the sender to communicate the target image in a way that the receiver can discriminate it from the distractors and then point towards it. Hereby, two of the constraints mentioned above are studied at once. First, the way of communication is constrained in the way that the sender can only communicate one symbol per message, which results in the agents clustering images into categories that are described with a symbol. Secondly, two different sender architectures are compared: the ‘agnostic’ sender that encodes each image separately and then produces the message, and the ‘informed’ sender that uses convolutions to combine both images for better discrimination. While both architectures are able to solve the task with an emerged language, the emerged language of the informed sender converges faster and makes use of more symbols than the agnostic sender.

While the previously described examples always study prosocial agents (agents that have a common goal), Cao et al. (2018) examine self-interested agents. Hereby, multiple agents need to distribute a set of items between them. Each item has a utility score for each agent that is only visible to themselves. The goal for each agent is to gain the highest utility score by choosing the correct items. To do that, the agents first negotiate with arbitrary symbols in a ‘linguistic’ channel. At any time, any agent can choose to end the negotiation by proposing how to distribute the items, using predefined symbols in the ‘proposal channel’. These can be accepted or rejected by the other agents. Their experiments show that in this self-interested setup, the agents utilize the proposal channel well to solve the task, but no language emerges in the linguistic channel. However, in a similar setup with prosocial agents, they start to utilize the linguistic channel and create an artificial language.

2.3.1 Setup of language games

In this thesis, the language games are studied with prosocial non-embodied agents that are deep neural networks. They can exchange multiple symbols to communicate after being presented with images. This is done using the *EGG* framework that allows a high configuration of the agents’ architectures, of the ways of communication, and of the technical constraints (Kharitonov et al., 2019).

Using the framework, how the messages of the sender are produced can be controlled. For instance the sender can send single symbols or use different kinds of RNNs to produce a sequence as a message. The same applies to the receiver for parsing the message.

Furthermore, a central problem in language games is how to train the sender. Usually every layer in the receiver model is differentiable and therefore standard backpropagation methods can be used to update the weights in the receiver. However, the sender’s messages are discrete symbols and the loss coming from the receiver can therefore not be simply passed on to the sender. A classic solution to this problem is to use REINFORCE algorithms (Williams, 1992) that can handle discrete symbols. More recently, Gumbel-Softmax relaxation (Jang et al., 2017) is used to turn the discrete categorical distribution into a continuous probability distribution. Doing this, receiver and sender act as a whole deep neural model that can be completely backpropagated with standard methods. The methods are discussed deeper in Section 3.5. When setting up the language game with the *EGG*, both REINFORCE and Gumbel-Softmax relaxation can be

used.

In classical machine learning problems, the models are trained using a train dataset for multiple epochs. To verify the performance, the model is verified on unseen test samples, which allows to test the ability to generalize its learned knowledge. Opposed to that, the main goal of language games is not to solve a specific task, but instead the success of communication with a useful emerged language. Consequently, the agents are trained continuously, and the testing doesn't validate the model on unseen samples, but instead is used to extract the exchanged messages, namely the emerged language. In other words, during training, the agents are shown randomly drawn samples from the dataset for each game. This is done repeatedly for k 'games' so that the agents improve and ground their knowledge in the used symbols. During the testing, the agents are frozen and again randomly drawn samples are shown. The messages that the agents are exchanging now represent the language that emerged after k language games which can be analyzed.

Section 3.4 explains the framework in more detail.

2.3.2 Properties of the emerged language

When agents develop an artificial language, they can learn to use it in different ways. Several studies research the properties of emerged languages, in particular if they share properties with human languages. One important property is the capability of forming new meanings by combining multiple symbols in a message, so-called compositionality (Chaabouni et al., 2020; Gupta et al., 2020; Kharitonov & Baroni, 2020; Lazaridou et al., 2018). Lazaridou et al. (2018) construct a referential game where agents are presented with symbolic input instead of visual input in form of images. More specifically, each of the objects, target object and distractors, are represented as one-hot vectors where each dimension corresponds to an attribute of the object. This setup should bias the agents to rely directly on these given attributes in the messages to communicate the target object, instead of first having to extract every possible attribute, for instance from visual features. Hence, this helps them to develop a compositional language. A compositional language should help the agents to communicate objects with unseen combination of attributes during training. Therefore, to analyze the degree of compositionality in the emerged language, the authors present the agents with new combinations of objects and measure the accuracy. Even if the accuracy drops lower, the fact that it is still above the random baseline shows that the agents are able to generalize to a certain degree. Furthermore, they utilize new combinations of symbols in their messages. However, Kharitonov & Baroni (2020) show that compositionality is not necessarily tied to the ability to generalize. In their experiments, non-compositional languages that emerge are able to generalize better than their compositional counterparts.

One essential property of human languages is *Zip's Law of Abbreviation*, in other words that more frequent words tend to be shorter. In (Chaabouni et al., 2019), the researchers analyze if this law also applies to emerged languages. They find that without any pressure to produce shorter strings the agents produce a language that follows the inverse rule: the most frequent inputs are associated with longer messages. Only when long messages are penalized, a language which follows similar rules as human languages emerges.

Finally, a strong focus in the study of emerged languages lies in interpretability (Dessi et al., 2021; Lazaridou et al., 2017; Chaabouni et al., 2021). While the agents ground the symbols in their input and certain symbols correspond to certain categories, they do not necessarily align with human categories and words. However, agents can be biased to use similar categories, as shown in (Lazaridou et al., 2017). This is done by infusing human labels during training so that the agents ground the visual input not only in their artificial language, but also in human language. More specifically, their experimental setup is a referential game, where the sender needs to describe the target image in a set of distractors to the receiver. Alternating with describing the target image to the receiver, the sender is trained to classify its input with human labels. The results show that this setup doesn't have any negative effect on the communicative success, but instead it only biases the agents to align their vocabulary with human descriptions. This makes the emerged language much easier to

interpret for humans.

2.4 Artificial dataset

Language is heavily influenced by the perception and the environment (Hofstadter & Sander, 2013; Dobnik & Åstbom, 2017; Ji et al., 2022). This is for instance very apparent in color naming systems across different languages (Zaslavsky et al., 2018). Which and how many words are used to refer to a specific color is dependent on the perceptual and social context around the speakers. Different studies show that while all languages tend to share similar basic color categories, some languages' systems are based on different underlying principles. Color names in the language of the Berinmo people from Papua New Guinea for example reference natural objects and hence color categories are different from non-referential English color names (Davidoff, 2001; Steels & Belpaeme, 2005). Further, this fact can be applied to more abstract constructs like metaphors, which often reference perceived events in the world (Lakoff & Johnson, 1980). Perceiving that cats always land on the ground on their feet is for example the origin of the metaphor 'as nimble as a cat'.

This influence on the language by the perception of the world is not only limited to human language learning and evolution, but it as well applies to machines that are trained to produce language. Many models in different disciplines of Natural Language Processing are trained on datasets such as the MS COCO dataset (Lin et al., 2014) or the Flickr30k dataset (Young et al., 2014), which are sourced from uploaded photos in social networks. While these datasets often contain a large amount of samples, they can contain structural biases. The photos usually feature and center on specific objects, people or animals. This is not necessarily a faithful representation of human perception of the world, in which these entities are for instance partially hidden, shown from the back or appear at the edges of the field of view. The datasets might therefore give a euphemized view on the world. Furthermore, the datasets can contain underlying patterns in the semantic information of the photos (Hendricks et al., 2018; Johnson et al., 2017a; Hudson & Manning, 2019). For instance, when dogs are photographed, they usually appear running on a meadow. An image captioning model might learn to predict the caption 'a dog running on a meadow' for all images containing a dog, independently if the dog is actually running on a meadow or sitting in the living room, just because of the higher frequency in the dataset. In other words, the model might utilize these underlying structural biases rather than relying on the extracted visual information from the image.

Different approaches are taken to mitigate this problem. While some research focuses on improving the models (e.g. Hendricks et al. (2018); Lu et al. (2017)), others create artificial datasets. Using artificial datasets, one can control exactly which structural patterns occur. Furthermore, all ground truths as for example spatial positions of objects are known and can be used for training models. Figure 2 shows several examples of different artificial datasets. Real world photos often contain a lot of distracting visual information that poses challenges for models to identify the relevant information. In (Ghanimifard & Dobnik, 2017) and (Ji et al., 2022), the authors for example create abstract visual scenes that only contain specific concepts, like for instance spatial positions. With no distracting concepts present, researchers can focus only on the effects of the concept that is relevant for the respective study. Other datasets consist for example of comic-like scenes (Zitnick et al., 2013; Zhang et al., 2016). These scenes, while still being abstract also contain functional objects. This adds more complexity for predicting spatial relations. More recently, datasets are created using 3D environments (Johnson et al., 2017a; Lee et al., 2022; Ahrens et al., 2022). Scenes created in this way resemble photos taken in the real world and models can more easily transfer the learned knowledge to real world photos. Extending this reasoning, several datasets include embodied perspectives. Images are for example taken from the perspective of a person in the scene (Dobnik et al., 2015) or from the perspective of an embodied robot navigating a 3D environment (Hill et al., 2021).

This thesis utilizes an artificial dataset for two reasons. First, all ground truth information about the scenes can be extracted during their generation. This includes spatial positions of entities placed in the scene,




Figure 2: Example images from different artificial datasets

their properties and relations to other entities. Having all information present, several different tasks for the models can be created using the same generated images. More importantly, the usage of an artificial dataset allows for perfect control over the bias present in the images, in particular which entities are present, and which properties and attributes they have. As detailed before, perceptual input shapes the language that describes and interacts with it. When agents in a language game describe and refer to entities present in a scene, the emerged language is expected to utilize these biases by making use of the controlled attributes in the scenes.

3 Methodology and Frameworks

3.1 CLEVR framework

The basis for my datasets is the Visual Question Answering (VQA) framework CLEVR (Johnson et al., 2017a). This framework provides code to generate configurable VQA datasets that are split in two parts: a collection of images, and a set of questions and answers that refer to and describe each image. Many of the existing VQA datasets come with two problems. First, they include many biases, such as biases in the base images and biases in the linguistic properties of the questions and answers. A relatively high number of images of dogs in a dataset, might for instance bias a classifier model towards classifying dogs most of the time. On the other hand, repeating patterns in the questions and answers might also be exploited by a model, without extracting the needed information from the image. For these reasons the CLEVR framework aims to reduce the biases as much as possible in both images and questions and answers as well as precisely control the remaining biases to explore their limits. Secondly, datasets may come with only a limited amount of annotations and information about the state in an image. The CLEVR dataset uses artificially rendered 3D-scenes. By doing so, all information about for instance the location of objects or their relations to each other can be later used in training models or analyzing their results. Furthermore, it allows making predictions about the effects of varying contexts and information present in the scene.

For this thesis, the CLEVR framework will be extended to have more control over the generation of the images. With this extension, several datasets are created. The extensions are described in Chapter 4. Hereby, only the images and their ground truth properties are interesting for the present study of referring expressions. The questions and answers won't be used. In the following section the image generation of the original CLEVR framework is described. The visual part contains images of 3D-generated scenes depicting different kinds of simple objects. Each of these objects is made up of a different combination of attributes, such as *shape*, *color*, *size* and *material*. The possible values of these attributes are listed in Table 1. Three to ten objects are placed in random locations into the scene and assigned with random attributes. To enhance realism and reduce ambiguity, objects are placed in a way so that they do not intersect and have a certain distance from each other. Furthermore, it is made sure that every object is almost completely visible. The positions of the light and the camera are slightly jittered for each image to add noise and reduce recurring patterns. Since the objects are part of 3D scenes, they may look different in each image, because of different lighting and shadows, distances to the camera and rotations. This noise approximates the real world and natural environment, and makes it harder for models to learn compared to relatively noise-free projections on a 2D plane. Figure 3 shows an example of a generated image in the CLEVR dataset.

shape	color	size	material
cube	gray	small	rubber
sphere	red	large	metal
cylinder	blue		
	green		
	brown		
	purple		
	cyan		
	yellow		

Table 1: Attributes of objects in the CLEVR dataset

Furthermore, the dataset contains information about each scene. This includes all selected attributes for each object as well as the exact position of the centers of all the objects, both 3D-coordinates in the 3D scene and 2D-coordinates in the final rendered image. In addition, simple spatial relations (in front of, behind, left, right) between the objects are calculated and stored. These are simply based on the 3D-coordinates of




Figure 3: Example of a generated image in the CLEVR dataset

the objects in relation to the position of the camera.

3.2 Feature extractors

In computer vision tasks, machines need to analyze images and extract information from them. To do this, machines often rely on feature extractors. Features are important parts or patterns in an image, which can have different levels of abstractions. They can for example be low-level features, as geometric information about lines and edges in an image, or also very abstract information about whole objects. Traditional approaches involve extracting key points and descriptors from an image and using them to represent the image (Harris & Stephens, 1988; Lowe, 1999; Bay et al., 2006). More recently, convolutional neural networks (CNN) became popular due to their ability to learn complex features automatically from raw image data. These are also used in this thesis as a first layer to extract important information from the image. Hereby, there are currently two different architectures.

First, the VGG19 (Simonyan & Zisserman, 2015) is used which is an architecture based on many convolutional layers. Using 16 to 19 convolutional layers with small convolution filters helps the model to solve localization and classification tasks on the training dataset, but also enables it to generalize onto other datasets. After the convolutional layers, the data is passed first through an average pooling layer which outputs $512 \times 7 \times 7$ dimensions. Next follow three linear layers with *ReLU* non-linearities in between. After flattening the input, these classification layers output 4069, 4069 and 1000 dimensions respectively.

The second architecture is ResNet-101 (He et al., 2016). This architecture tries to overcome the degradation of very deep networks, where the accuracy rapidly drops after it gets saturated. This is done using residual blocks. A residual block consists of two or three convolutional layers and a residual connection, also known as a shortcut connection. The residual connection allows the input to be added directly to the output of the block, allowing the network to learn the residual function with respect to the input. This approach enables the network to better preserve information from earlier layers and avoid the problem of information loss that can occur in very deep networks. There are four blocks that output $256 \times 56 \times 56$, $512 \times 28 \times 28$, $1024 \times 14 \times 14$ and $2048 \times 1 \times 1$ dimensions. A following average pooling layer outputs $2048 \times 1 \times 1$ dimensions as well. The final linear layer reduces the flattened data to 1000 dimensions, corresponding to the ImageNet classes.

Both architectures are available pretrained on an image classification task on the ImageNet dataset (Deng et al., 2009). In this thesis, the implementations and weights available for PyTorch are used.^{1,2} In both cases, images that should be passed through the feature extractors need to have the same structure and shape as the images that were used in the pretraining. Hence, all images passed to them in the experiments in this thesis are preprocessed in the following way. As described in (He et al., 2016; Simonyan & Zisserman, 2015), the images are resized to 256 pixels for the shorter side, then cropped around the center to a square of 224×224 pixels. Finally, the RGB channels are normalized, by subtracting the means (0,485; 0,456; 0,406) and dividing the result by the standard deviation (0,229; 0,224; 0,225) for each channel respectively.

Since the task in this research is very different from a classification, it likely learned representations that are not directly transferrable to other tasks. The pretrained knowledge in both models might not be directly transferrable to new tasks as studied by Yosinski et al. (2014). In this thesis, the task differs for multiple reasons. First, the used images for the pretraining and the present study are part of a different domain. Even though images of the CLEVR framework are generated to resemble the real world, they still only include abstract geometric objects while ImageNet contains real photos of persons, animals and objects. Furthermore, the original task for the pretraining is a classification task, whilst this thesis is interested in generating and understanding referring expressions. For this reason, multiple different adaptations of these architectures are usually used. Table 2 lists the different adaptations for both VGG19 and ResNet-101, where later layers are omitted. Preliminary results showed that early layers like *ResNet-1* to *ResNet-3* or *VGG-0* and *VGG-avg* provided better results. This corresponds to the hypothesis that later layers include too much task specific knowledge from pretraining. There was no visible difference between *VGG* and *ResNet*, so *ResNet* is used in all experiments due to its more efficient architecture. However, *ResNet-1* and *ResNet-2* contain a high number of dimensions, that slows the training and raises the amount of needed memory on the GPU. Some experiments couldn't be performed using these layers, so all experiments are run, using *ResNet-3*.

	description	output dimensions
VGG-0	contains only the convolutional layers	$512 \times 7 \times 7$
VGG-avg	contains an additional average pooling layer	$512 \times 7 \times 7$
VGG-cls1	contains an additional one classification layer, including its non-linearity	4069
VGG-cls2	contains another additional classification layer, including its non-linearity	4069
VGG-cls3	the original VGG19 architecture	1000
ResNet-1	contains one residual block	$256 \times 56 \times 56$
ResNet-2	contains two residual blocks	$512 \times 28 \times 28$
ResNet-3	contains three residual blocks	$1024 \times 14 \times 14$
ResNet-4	contains four residual blocks	$2048 \times 1 \times 1$
ResNet-avg	contains an additional average pooling layer	$2048 \times 1 \times 1$
ResNet-cls	the original ResNet-101 architecture	1000

Table 2: Different adaptations of VGG19 and ResNet-101 used in this research

3.3 Image processing

In the experiments different agent architectures are compared. To make these architectures comparable, the agents' models are composed of submodules that solve a specific subtask. Submodules can for example

¹https://pytorch.org/hub/pytorch_vision_resnet/

²https://pytorch.org/hub/pytorch_vision_vgg/

be image encoder modules or text parsing modules. Hereby, different ways of solving the subtask are manifested in multiple exchangeable submodules. For instance, one image encoder module uses CNNs while another image encoder module uses a traditional approach. These can simply be exchanged in an agent’s model without needing to adapt the whole agent. Consequently, the experiments stay comparable, since the differences are only added or removed submodules.

The feature extractors described in Section 3.2 are not enough to be solely used to encode the images used in this thesis. Even though final layers that contain very task and domain specific knowledge can be removed, the previous layers still don’t contain any information about the new domain and task. For this reason they need to be extended with further layers that are not frozen and can learn and store information about the new domain by connecting the pretrained general knowledge with the specific task. These additional layers on top of the feature extractors that make up the *image encoder* submodule, however, are always trained from scratch for each of the experiments and tasks. In this thesis, only this submodule is used to encode images for all the conducted experiments, except otherwise specified.

Johnson et al. (2017b) describe an architecture that was used for training baseline models on the CLEVR dataset. This architecture will be used as the submodule. Hereby, the image is first passed through a frozen feature extractor. Two convolutional networks with subsequent *ReLU* non-linearities condense the important information from the output of the feature extractor. The convolutional layers reduce the channels to 128 channels, using a kernel size of 3 and a stride and padding of 1. Afterwards, a 2-dimensional max pooling is applied with a kernel size and stride of 2. Finally, the resulting matrix is flattened and passed through a linear layer to reduce it to an encoding size. This vector represents the encoded image with its extracted features. Table 3 shows the layers and their output dimensions when using ResNet-3 as the feature extractor and an image embedding size e_i .

	layer	output dimensions
	Input image	$3 \times 224 \times 224$
1	ResNet-3	$1024 \times 14 \times 14$
2	Conv($3 \times 3, \rightarrow 128$)	$128 \times 14 \times 14$
3	ReLU	$128 \times 14 \times 14$
4	Conv($3 \times 3, \rightarrow 128$)	$128 \times 14 \times 14$
5	ReLU	$128 \times 14 \times 14$
6	MaxPool(2×2 , stride 2)	$128 \times 7 \times 7$
7	Flatten	6272
8	Linear Layer($\rightarrow e_i$)	e_i

Table 3: Image encoder with ResNet-3 and an image embedding size e_i

In some experiments, the focus of the model should be pointed to certain regions in the image. This is done by providing the model additionally to the original image of the scene with a masked version of the scene. In particular, the masked version only contains black and white regions. All pixels in the relevant region are white, while all remaining pixels outside this region are black. This is expected to help the model to learn which are the important parts in the original image. However, a challenge lies in combining both original image and masked image. When extracting features from an image using the previously described submodule, the output of the final linear layer doesn’t directly correspond to pixels and regions in the image, but only contains the important extracted features sequentially. In other words it loses the 2D geometrical structure of the image. The model will have problems to align these extracted features with the masked image, still having the 2D geometrical structure.

For that reason, another submodule for masked images is used, the *masked image encoder*. In this submodule, the original image and the masked image are combined at an earlier stage, when both have the same




Figure 4: Combination of the original image and its masked version

structure (see Figure 4). In particular, both images are processed in exactly the same way, by passing it through a feature extractor and then through the above described extending layers until layer 6, the max pool layer. Even though the masked image doesn't contain similar features to the images the feature extractors are pretrained on, this method still provided better results in the experiments. After this, the images are concatenated along the channels, which results in a matrix with the dimensions $256 \times 7 \times 7$ (still including the geometrical structure with 7×7 grids). Finally, this matrix is flattened and reduced to the image embedding size e_i . Doing this, the model can directly align a region in the original image with a region in the masked image.

3.4 EGG framework

The goal of this thesis is to run and compare different setups of language games systematically. To do this, all experiments rely on the *Emergence of lanGuage in Games* (EGG) framework (Kharitonov et al., 2019) which is implemented in PyTorch. This framework allows the implementation of language games in code, where agents are neural models that communicate with each other. It consists of a heavily configurable core that controls the generating and parsing of the message, the calculation of the loss and the rules, for how the weights of all neural models are trained. The configuration includes for example:

- a choice between single symbol and sequence messages with varying RNNs,
- an easy switch between different loss functions,
- or a choice between two optimization functions (Gumbel-Softmax relaxation and REINFORCE algorithms) to learn neural models containing discrete symbols.

Furthermore, runs of games can be saved to analyze the used messages of the agents and how they vary over the duration of the learning.

The EGG framework is set up in three levels, shown in . Part of the lowest level are the *agents* themselves. The agents are neural models that need to be implemented from scratch and define how the agents process their input and in case of the receiver combine it with the message. The second level consists of *wrappers* that take care of generating and parsing the message. The sender wrapper uses the output of the sender agent, to produce a message. The receiver wrapper on the other hand parses the message received by the sender and passes the result as an additional input to the receiver agent. The third level, the *game*, links all described parts together. It provides the agents with the input and passes the message from the sender to the receiver. Furthermore, it uses the output of the receiver and calculates the loss, which is then the basis for the adaption of the weights for both wrappers and agents.

For the language games which are run in this thesis, the sender will always produce a sequence of symbols




Figure 5: The EGG framework is made up of three levels: the game (gray), the wrappers (blue) and the agents (orange)

as a message, which the receiver will parse. Gumbel-Softmax relaxation is applied to produce discrete symbols. This is done in the default method of the EGG framework using two LSTMs, an encoder LSTM in the sender wrapper and a decoder LSTM in the receiver wrapper. The output of the sender agent is used as the initial hidden state for the encoder LSTM. This LSTM is then producing symbols until it generates an end-of-sequence symbol. This sequence is then passed to the receiver wrapper with its decoder LSTM. Its hidden state is initialized randomly. The received message sequence is processed symbol by symbol. After each time, a symbol is processed by the LSTM, the resulting new hidden state is passed to the receiver agent as the parsed message. The receiver agent is combining it with its representation of the image input and is predicting an output. In other words the receiver agent produces as many outputs as symbols are present in the message. The *game* is then calculating a loss for each of these outputs separately. These losses are summed up to a total loss that is used to adapt the weights in both agents as well as in both LSTMs.

3.5 Optimization in language games

Training agents in a language game is not a straight forward task. In this thesis, the agents share a common goal, in particular optimizing the predictions of the receiver. The loss function of the whole game can therefore be defined as the loss of the receiver’s predictions given its input and the sender’s message. By this, the receiver can be trained relatively easily by backpropagating the game’s loss through all layers in the model of the receiver. A problem however arises when passing on the loss to the sender. The generation of the message involves sampling from a categorical distribution and is therefore not differentiable. Consequently, the gradients of the loss function can’t be estimated with standard backpropagation methods for the sender. To solve this problem two dominant methods are currently used: REINFORCE algorithms (Williams, 1992) and Gumbel-Softmax relaxation (Jang et al., 2017).

The traditional approach to solve problems with a discrete channel formulates the problem as a reinforcement learning task and relies on the REINFORCE algorithms. In reinforcement learning, the neural models are trained to optimize their policy given a reward. Given for example the referential game, described in (Lazaridou et al., 2017), where the sender is presented with two images and needs to communicate the target image to the receiver. The receiver is shown the same images and is tasked to point to the correct target image given the sender’s message. The sender model and receiver model are following a policy with parameters θ respectively. The policy of the sender can be defined as $s(\theta_S(i_L, i_R, t)) \in V$ with θ_s being the parameters of the senders neural model, i_L and i_R the presented images, t the target image and V the vocabulary. The receiver’s policy is dependent on the message by the sender and therefore directly

dependent on the sender’s policy and can be defined like this: $r(i_L, i_R, s(\theta_S(i_L, i_R, t))) \in \{L, R\}$. The reward is given if the receiver’s policy successfully produced the target image:

$$R = \begin{cases} 1, & \text{iff } r(i_L, i_R, s(\theta_S(i_L, i_R, t))) = t \\ 0, & \text{otherwise} \end{cases} \quad (1)$$

The task for the agents to learn is to maximize the reward function R across all possible rewards (dependent on receiver’s policy and target image) $\mathbb{E}_{\tilde{r}}[R(\tilde{r})]$. The problem hereby is that not all possible rewards are known. Without training, it can’t be determined if a certain configuration of the agents, the policy, yields the correct target image. The rewards are in fact the outcome of the training. To solve this, Monte Carlo sampling is used to approximate the expected value $\mathbb{E}$. Monte Carlo sampling works on the fact that the mean of all drawn samples from an unknown probability distribution approximates its expected value. The more samples are drawn, the better the approximation. Using the approximation, the function becomes differentiable and can be used to calculate the gradients to update the policies. In this case, the approximation is based on the already determined rewards, in other words on the already played games. Early games are more or less trial and error, because the approximation is very bad. Only when many games are played, the approximation becomes better and the models can be updated properly. This however also means that the training can take very long until the models start to converge, and it suffers from high variance.

For this reason, more recently Gumbel-Softmax relaxation is used to represent the discrete message. Basically, this method is a way to turn a discrete categorical distribution into a continuous distribution that can be differentiated. By doing this, sender and receiver are completely differentiable and act as whole deep neural model where the loss can be backpropagated with standard methods. In particular the problem lies in sampling from the categorical distribution C over $|V|$ symbols, which can’t be differentiated. Therefore, the method applies a reparameterization trick: random samples are instead drawn from the Gumbel distribution G (Equation 2) and summed with the logarithmic probabilities of each symbol (Equation 3).

$$g = -\log(-\log(u)) \quad \text{with } u \sim \text{Uniform}(0, 1) \quad (2)$$

$$s_k = \log(c_k) + g_k \quad \text{for } k = 1, \dots, |V| \quad (3)$$

To determine the symbol to use, usually the *argmax* function would be applied on the resulting vector s . However, this function is again undifferentiable and is therefore approximated using the *softmax* function:

$$y_k = \frac{\exp(s_k/\tau)}{\sum_{i=1}^{|V|} \exp(s_i/\tau)} \quad (4)$$

The temperature τ of the *softmax* function determines how well it approximates the *argmax* function. For $\tau \rightarrow 0$, the samples from the Gumbel-Softmax distribution are identical with the categorical distribution while for $\tau \rightarrow \infty$ the Gumbel-Softmax distribution becomes uniform.

The Gumbel-Softmax method offers stable gradient estimates and can be more efficient than the traditional REINFORCE algorithm, especially when dealing with large action spaces. This also applies to language games, where Havrylov & Titov (2017) demonstrated that Gumbel-Softmax relaxation is more effective. For that reason, the experiments in this thesis utilize Gumbel-Softmax relaxation.

3.6 Ethical considerations

In the field of natural language processing (NLP) ethical issues often play major roles. These can be part of the used datasets, the created models and their training as well as the application of the models. For

datasets, the role data privacy is increasing with the necessity of larger amounts of data (Klymenko et al., 2022). Furthermore, datasets often contain biases, based for instance on the authors of the collected natural language texts. Often they also contain biases such as overrepresentations and underrepresentations. Even though some of these biases are inherent to the data and not necessarily negative, much research is indicating that undetected and unaddressed biases in datasets might lead to negative consequences (Shah et al., 2020; Field et al., 2021; Bender et al., 2021). Training neural models can also lead to environmental issues, as large models need to process huge amounts of data and require a lot of energy (Bender et al., 2021). Finally, the application of trained models can create harm. This applies for example to easy accessible large language model (LLMs) that can be used to create information hazard (Weidinger et al., 2022).

The research in this thesis tries to reduce these risks. Looking at the datasets that are used in this thesis, all data is created artificially and contains therefore no personal information. Even further, the aim of the creation of these datasets is to reduce and study the remaining biases. It doesn't include any social information, but on the other hand consists only of abstract scenes. The choice of which attributes the objects are made up is inherently biased towards human cognition, but doesn't have a social impact. The models and agents are therefore trained, by including as few human biases as possible.

Looking at the environmental issues, the models used in this thesis consist of only few trained layers and the training is therefore short and doesn't require much energy. Larger models as the feature extractors are already pretrained and add no additional consumption.

Finally, the purpose of this thesis is to analyze the results and the emerged language and draw conclusions, how emerged languages can be grounded better in the environment. For that reason, the final models can't be used in any real world applications and produce potential harm. On the other hand, this work can on the long run mitigate harm as it provides a study of models, how they would behave on real data. This therefore contributes towards interpretability of AI.

4 Creation of the datasets

This research investigates how agents use referring expressions to discriminate objects seen in images based on their relations. For that reason, the original CLEVR framework offers too little control over how a new dataset is created. Especially, which objects and in which attributes they share with each other in each image can't be controlled. Following, we extended the framework for generating new datasets.³ By this, the objects in the generated images are controlled to have different human-recognizable attributes, namely the *shape*, *size* and *color*. These attributes also correspond to referring expressions in natural language such as English. The *material* is always the same for all objects in a generated image. There were three main extensions to the framework:

First, objects in the scene were separated into three categories: one *target object*, objects in a *target group* and *distractor* objects. The target object is the main object in the scene and the models are trained to identify and communicate between each other. All other objects and their relations are based on this target object. The target group contains similar objects to the target object. These are objects that the agents need to discriminate the target object from. Finally, the distractors are objects that add noise to the scene and should make it more complex. They are expected to teach the agents more precise descriptions of the target object. The number of the objects in both groups can be controlled.

In a second step, when generating the images it is possible to define the relations between *target object/target group* and *target object/distractors*. The relation is defined as **how many** attributes of the target object are identical with the attributes of a single object in the target group and distractors respectively. For example the target object is a *small red cube*. If two attributes are shared between target object and target group, objects in the target group could include *small blue cube*, *big red cube* or *small red sphere*, but couldn't include another *small red cube* or a *small blue cylinder*. The number of shared attributes can also be set to a range to control how challenging the referring task is.

Lastly, it is also possible to define exactly **which** attributes should be shared between the target object and the groups. For example, it can be defined to have the same size for objects in the target group, but have different, randomly selected shapes and colors. This allows for a very controlled generation of relations between the objects in the scene. Figure 6(d) shows one generated image with this extended source code. Here, the target object is the large purple cylinder. The target group contains four objects that share zero to a maximum of two attributes. It is not controlled, which attributes are shared (they are selected randomly). The large purple cylinder shares the same color and size with the large purple sphere, the same size with both cubes and no attribute with the small turquoise sphere. There are no distractor objects.

For all generated datasets in the following sections, the general constraints and settings are as close as possible to the original CLEVR dataset. The size of the generated images is 480x320 pixels. 10.000 images are created for each of the datasets. Each image contains a maximum of 10 objects, that are not intersecting, have the same minimum distance between objects and are at least partially visible from the camera.

4.1 CLEVR single

The simplest new dataset is called 'CLEVR single'. This is a very simple dataset and has the purpose to simplify the problem the model needs to learn as much as possible. Each scene in the dataset contains only one single object, the target object. There are neither objects in the target nor in the distractor group. All attributes are assigned randomly to the target object. The differences across the whole dataset are the

³https://github.com/DominikKuenkele/MLT_Master-Thesis_clevr-dataset-gen




Figure 6: Example images of each dataset, with the target object specified

locations and rotations of the objects. With this dataset, neural models can focus on only the features, as well as the locations of this single object. There are no objects that distract the model from extracting features from the target object. This helps to understand if the models are actually able to assign features or learn locations of these features in an image. Figure 6(a) shows an example with the only object being the *large yellow sphere*.

4.2 CLEVR color

The second dataset that is created is called 'CLEVR color'. The purpose of this dataset is to create scenes, where the target object is completely unique and as easily identifiable as possible. For this reason, there exist only two groups in the scene, the target object and distractors. The distractor group can contain in between 6 and 9 objects. To make the discrimination as simple as possible the target object and the objects in the target group share exactly two attributes. Furthermore, to simplify the relation between target object and distractors over the whole dataset, it is also controlled which attributes are shared. The distractors have always the same size and shape as the target object, but the color is different. The reason for choosing the color as the only discriminating attribute is that it is assumed that the color is easier to learn for neural models as opposed to for instance abstract shapes.

As seen in Figure 6(b), the *small brown cylinder* is unique. By this, it is possible to refer to the target object using the attributes with four different combinations: the *brown* object, the *brown cylinder*, the *small brown* object and the *small brown cylinder*. All attributes, apart from the color are not discriminating the target object from the distractors. Notice as well that this restriction doesn't apply to the distractors, where multiple objects with the same color are allowed. In other words, the choice of attributes is random for the distractors, and they may overlap.

4.3 CLEVR Dale datasets

The above described dataset is very restrictive in the relation between the objects, where only *one* attribute is used to disambiguate them. The number and the type of shared attributes are controlled exactly. In the real world, objects have overlapping attributes and hence objects can only be identified by an intersection of multiple attributes. In real situations, there is no restriction at all how objects or things relate to each other. Natural language emerged that can refer to distinct attributes of these objects to discriminate them from each other. This emergence of referring attributes and their combination is studied deeper in this work.

For this, we created a dataset that allows almost any relation between a target object and the distractors. However, the creation is inspired by incremental algorithm for the Generation of Referring Expressions (GRE) described in (Dale & Reiter, 1995) who observe that attributes in descriptions occur in certain order and are added incrementally in a certain hierarchy. This algorithm ensures that every scene contains a unique object in respect to its and the distractors' attributes. Using the algorithm, one can refer to an object using its attributes to discriminate it from all other objects as efficiently as possible. In other words, the object is described unambiguously using the lowest number of words. For the dataset that means that zero, one or two attributes can be shared between the target object and distractor objects. This ensures the uniqueness of the target object. On the other side, it is not controlled which attributes are shared. These are assigned randomly. There is again no control over the relations between distractors, which means that distractors can appear multiple times.

Two datasets following these rules are created. The 'Dale-2' dataset contains one target object and one distractor (see Figure 6(c)), while the Dale-5 dataset contains one target object and exactly four distractors. Consider Figure 6(d), with the target object being the *large purple cylinder*. The large purple sphere shares the size and color, the two cubes only share the size, and the small turquoise sphere doesn't share any attribute.

These two datasets allow a more realistic look in how models can acquire knowledge about attributes of objects. More specifically it helps to understand how models learn to discriminate objects from each other, since the model may only need to learn discriminative features of objects and not all features of the whole object.

5 Grounding referring expressions

This chapter serves two purposes. First, the generated dataset from the previous section is validated. For this, models are trained to both generate referring expressions of the target object and understand existing referring expressions. A success of these experiments indicates that the target objects in the datasets are possible to refer to and the datasets can be used in more complex setups in language games.

Secondly, the experiments in this chapter provide the basis for the setup of the agents in the language games. Language games are very complex setups for machine learning models. The models need to solve multiple tasks at the same time in order to solve the overall problem. For instance, in a simple setup of a game two agents are involved. The first agent, the sender, is shown a scene with objects and needs to communicate one target object to the other agent, the receiver. The receiver is shown the same scene and needs to identify the target object with respect to the message of the sender. In this case, the sender first needs to learn to encode the scene, all objects and their attributes, as well as the information about the target object into its own game specific space. In a next step it needs to learn how to translate this encoding into a message that is sent to the receiver. The receiver then needs to learn to decode this message, after which it needs to learn how to combine the decoded message with its own encoding of the scene and objects. And finally it needs to learn how to identify the target object with this information. There are many points of possible failure to train the agents.

For this reason, we decided to divide the main problem and let the models learn simpler subtasks and increase the complexity step by step.⁴ This will give a very detailed overview where the models struggle to learn and in which ways they can be improved. Mainly, the tasks are separated into language games with two agents and classical machine learning tasks without any communication, namely only one 'agent' that solves the task alone. With this division, we can analyze the learning of the encodings of the scenes separately from the learning of producing and decoding messages.

The final objective of this thesis is to find out, how agents can communicate about relations of objects based on their attributes, namely how to generate and understand referring expressions. Because of that, the first experiments focus on extracting information from images and combining them with structured knowledge about the objects. Here, we structured the experiments into three levels. In the first level, the models are trained to learn the position of objects in the image and attend to specific regions of the image, by understanding a referring expression of the target object. In the second level, the models are trained to differentiate objects in the scene from each other, again by understanding referring expressions. In the last level, the models are trained to generate referring expressions, more specifically the models learn to caption and describe objects in the image. These combined experiments should lay the basis for how to build up the agents in the language games.

For all experiments in this section, the batch size is 32 samples and the optimizer is *Adam* (Kingma & Ba, 2015). 8000 randomly selected samples are used for training, the remaining 2000 samples for testing. Other hyperparameters are specified for each experiment.

⁴https://github.com/DominikKuenkele/MLT_Master-Thesis

5.1 Object identification

Setup

In a first task a neural model is trained to discriminate multiple objects from each other. Hereby, the model is shown bounding boxes of all objects in the scene as well as a description of the target object. The model needs to combine all information and then point to the correct bounding box. This task forces the model to extract visual features from the objects in the shown inputs and connect them to a representation of human given attributes. Since the model is shown only bounding boxes around each object rather than the whole scene, geometric information about the objects' locations doesn't play a role for the success in this task.

In a first step, bounding boxes are extracted from each scene. Each bounding box is a square with a side length of 96 pixels around the center coordinates of each object. By doing this large objects in the front of the scene fill the bounding box completely, while smaller objects in the back of the scene contain some space around them. They also might contain noise in the form of parts of adjacent objects. Preliminary experiments indicated however that a more complex method for extracting the bounding boxes, depending on spatial position in the scene to reduce the noise didn't improve the results. Therefore, bounding boxes in this thesis rely on the former simpler approach. Since, each bounding box will be passed through one of the feature extractors, they are preprocessed as described in Section 3.2. The array of bounding boxes is padded with matrix of zeros to the maximum possible number of objects present in a scene across the dataset. For the 'Dale-2' dataset, this corresponds to a maximum of two bounding boxes, 5 bounding boxes for the 'Dale-5' dataset and 10 for the 'CLEVR color' dataset. For each sample in the dataset the bounding boxes are shuffled.

The attributes of the target object are encoded as one-hot encodings. There is a three-dimensional vector encoding the *shape*, an eight-dimensional vector encoding the *color* and a two-dimensional vector encoding the two different *sizes*. The values of each dimension of these vectors can either be zero or one, depending on the attributes of the target object. These three encodings of the attributes are then concatenated to a vector with 13 dimensions.




Figure 7: Simplified architecture of the object identification task

The model, the **object identifier** is split into three submodules, the *bounding box encoder*, the *attribute encoder* and the *identifier*. Each normalized bounding box of the sample is encoded with the *bounding box encoder*. Hereby, they are passed through *ResNet-avg*. The preceding layers *ResNet-1* to *ResNet-4* couldn't be compared due to memory restrictions on the GPU. The resulting vector is flattened and projected to the embedding dimension e via a linear layer. Correspondingly, the one-hot vector of the attributes is projected to the same embedding dimension with another linear layer, using the *attribute encoder*. In the *identifier* submodule, each bounding box is combined with the representation of the attributes. By bringing both vectors to the same embedding size, the dot product between each embedded bounding box and the

embedded attributes can be calculated. A high correlation between the attributes and the object should result in a high dot product, while a low correlation results in a lower dot product. The model can so learn to connect the object representation with the attributes. The dot products are concatenated and form a vector with as many dimensions as objects present. The *softmax* function is applied over the resulting vector, which returns a probability distribution over all objects; the model points to the object with the highest probability.

The experiments are conducted with the following hyperparameters: a learning rate of 2×10^{-4} and 30 epochs. The number of epochs was chosen manually after identifying when the loss as well as the test accuracies didn't improve significantly. The loss is calculated using cross entropy. The following embedding dimension e are compared: 2, 10, 50, 100, 500, 1000.

The object identification task is trained on all datasets that include more than one object in each sample, namely the 'CLEVR color', 'Dale-2' and 'Dale-5' dataset. Random baselines for each dataset would yield accuracies of 10%, 50% and 20% respectively. The 'Dale' datasets are directly comparable to each other for the similar setup of their creation. Especially interesting is the effect of the increasing the number of distractors and the growing number of attributes that are needed to discriminate the objects.

Results

Table 4 lists the accuracies of the models' predictions after 30 epochs for all three different datasets and different embedding sizes e .

	Dale-2	Dale-5	CLEVR Color
e	Accuracy	Accuracy	Accuracy
2	92%	72%	40%
10	100 %	94%	92%
50	99%	95 %	94 %
100	100 %	95 %	93%
500	100 %	95 %	93%
1000	100 %	94%	94 %

Table 4: Accuracy scores of the object identifier after 30 epochs: e are different embedding sizes

The first trend that is visible is that fewer distractor increase the accuracy of the model. The model achieves almost perfect accuracy in all configurations for the 'Dale 2' dataset with only two objects. With five objects in the 'Dale-5' dataset, the accuracy drops to 95% and with a maximum possible number of 10 objects in the 'CLEVR color' dataset the model only achieves 94% in the best configuration. This is not very surprising, since the model has a higher chance of predicting a wrong object, given the random baselines of 50%, 20% and 10%. Furthermore, when more objects are shown to the model, more attributes are needed to discriminate the target object from the distractor, since it is more likely that the distractors share attributes with the target object. The task is getting therefore more challenging.

A second conclusion is that the model needs a certain embedding space, to represent the features of each image. Across all dataset, an embedding space of only 2 dimensions result in a much lower performance compared to the best configuration. Even though the model is still able to achieve an accuracy of 30% to 50% points over the random baseline, this shows that a bigger embedding size is beneficial to extract and represent the features of the objects. Between 50 and 1000 dimensions, the model performs the best and varies only by 1% point, which may be due to different random initialization of the weights in the model.

In conclusion, the model is able to learn to discriminate the objects based on the visual appearance. The

model can generate these high results, even with its relatively simple architecture. In this architecture, the model doesn't compare the objects directly to each other, but each object is only associated with the attribute encodings. A more complex architecture, in which the model is additionally tasked to discriminate the objects directly from each other might even improve the results.

5.2 Referring expression generation

Setup

Opposed to the previous experiment, where the focus lied on extracting visual features, the model is now tasked to generate referring expressions. This is done in two setups. The first setup uses bounding boxes as in the previous section as input, where the model needs to describe the target object of one of the bounding boxes. In the second setup, the model is presented with the complete image and therefore also needs to accommodate to geometric information of the scene.

The bounding boxes are extracted and normalized in the same way as for the object identification task. Since for the second setup, the images will also be passed through the feature extractors, they are normalized as well in like manner. The referring expressions for the target object are generated using the incremental GRE-algorithm, described in Section 2.2. By this, the model needs to describe the target object with respect to the distractor objects. There are some minor additions concerning the padding of the referring expression. As before, the referring expression is padded to a number of three tokens, corresponding to the maximum of three attributes. However, there are three different ways how the padding is applied. First, the referring expression are, as usual in captioning tasks padded at the end with a specified padding token. A problem could arise when the referring expression is not viewed as a natural language sentence, but as slots filled with tokens. More specifically, following the GRE-algorithm, the last token in the referring expression is always the shape. The second last token if existing describes the color, while the third last token if existing describes the size. As soon as this sequence is padded at the end, these slots disappear. A referring expression that only describes the shape, such as *cube* will be padded to *cube <pad> <pad>*, where the third last slot is filled up with the shape instead of the size. Since this task is not focussing on producing natural language with a correct grammar, but focuses instead on extracting attributes, having a slot structure could help the model to express the extracted attributes correctly. For this reason, the second method of padding the referring expression is prepending the referring expression with padding tokens. By this, the positions of the slots are preserved and if not specified just filled with a padding token. Each slot has always the same semantic value, e.g. the last slot always contains the shape of an object. This can be done since the referring expressions are not free text, but instead the structure and the possible content is given by the dataset. This method might help the model to learn the correct referring expressions. The last variation concerns the order of producing each token. When the referring expressions are prepended, the model would need first produce two padding tokens, before it finally can produce a much more meaningful token for the shape. This could be difficult to learn for a model, as the longer a sequence of tokens is, the more information about the beginning of the sequence gets lost. Even though a sequence of just three tokens may not be long enough for this factor to be a problem, we experimented to reverse the referring expression. Instead of producing for instance *<pad> green sphere* as correct in English, the model would now need to produce *sphere green <pad>*. Notice that the padding token is again at the end of the generation, but the order of slots as well as the amount of information in the referring expression are still preserved.

This task inherently involves learning human knowledge and natural language structure. Nonetheless, this helps to understand more detailed if and how the model discriminates objects. Can the model solve the task, or do specific attributes used by humans pose challenges to the model?

In the first setup, the **bounding box RE generator**, the model receives the bounding boxes as input (see Figure 8). The first bounding box is always the target object, while the remaining bounding boxes are shuffled. As in the previous experiment, each bounding box is embedded, using the same *bounding box encoder* submodule: first it is passed through *ResNet-avg* and afterwards projected to an image embedding dimension e with a linear layer. The *RE generator* submodule uses these embedding to produce a referring expression. Hereby, all encoded bounding boxes are concatenated and again compressed to the decoder output dimension $LSTM_o$ using another linear layer. This representation of all objects serves as the initial




Figure 8: Simplified architecture of the bounding box RE generator

hidden state of an LSTM, which generates the referring expression. Tokens used in the LSTM are embedded with embedding dimension $LSTM_e$. During training, teacher forcing is applied by using embeddings of the ground truth tokens as the input sequence for the LSTM, instead of the output of the LSTM. The output of the LSTM is passed through a linear layer at each step to determine logits over the symbols of the vocabulary. During testing, the LSTM is always forced to generate three tokens, with an embedded start-of-sequence token as first input to the LSTM. Each token in the sequence is determined greedily, by selecting the highest logit in the output of each step in the LSTM.

In the second setup two different models are compared against each other. The first model, the **basic RE generator** acts as the baseline and only receives the complete image as the input. The image is encoded, using the *image encoder* submodule, described in Section 3.3, in particular it is passed through *ResNet-3* and subsequently processed by several additional convolution layers. The same *RE generator* submodule as for the bounding boxes is used to produce the referring expression. Hereby, since there is only one input scene, its encoding is directly reduced to the decoder output dimension $LSTM_o$. The LSTM is trained in the same way as above.




Figure 9: Simplified architecture of the masked RE generator

Using this approach, the model doesn't have any information about the target object and is therefore expected to produce referring expressions for a randomly selected object on the scene. Therefore, it is extended in a second step with attention to the target object, the **masked RE generator** (see Figure 9). A masked version of the image is created and passed to the model. For this, a fixed size squared area of 96×96 pixels around the center of the target object is filled in white, while the rest of the image is filled in black. Both original and masked image are processed together with the *masked image encoder* submodule described in Section

3.3. Accordingly, the same *RE generator* submodule is utilized here. This should point the model towards which object to describe and discriminate from the distractors.

For both setups, the same hyperparameters as in the previous experiments are used: a learning rate of 2×10^{-4} and 30 epochs. The loss is calculated using cross entropy. Table 5 shows which variables are compared for each model:

	e [100, 500, 1000]	$LSTM_o$ [100, 500, 1000]	$LSTM_e$ [10, 15, 30]
bounding box RE generator	×	×	×
basic RE generator	-	×	×
masked RE generator	-	×	×

Table 5: Variables for each model where e is the embedding dimension, $LSTM_e$ the embedding dimensions for tokens in the LSTM and $LSTM_o$ the output dimension of the LSTM

As already discussed before, this task can be interpreted as a classification task rather than a natural language generation task. The main reason for this is that the model is tasked to assign specific attributes to the target object instead of producing free text with a large vocabulary. Following, we are interested in the classification mistakes the model makes. For this, the model’s success is validated on accuracy, recall and precision scores. These are calculated in the following ways. The first measure is the **overall accuracy** if the model predicted every word in the referring expression correctly. This gives a hint, how the model fares in general and if it is able to predict any of the attributes. However, a ‘false’ prediction doesn’t give much insight into why the model predicted a wrong referring expression.

It could be the case that the model predicted the correct shape, but wrong color. Even worse, the model could have predicted more attributes than necessary to uniquely identify the target object and didn’t follow the rules of the GRE-algorithm. For instance, consider the scene in Figure 6(d). The correct referring expression is *cylinder*. If the model would predict *purple cylinder*, the accuracy determines it as false as generating the referring expression *large purple cylinder* as well *small green cube*. The first two descriptions identify the target object perfectly, but the model only didn’t learn to exclude unnecessary attributes. To mitigate this, the accuracies for each class are included, as well as the macro average. This can give a better understanding of the errors the model makes. The same is done for **precision** and **recall**.

With the **non-target accuracy**, we identify if the model described another object, which is not the target image. This is basically an inverted accuracy score; the lower the score, the better the model fares. By this, it measures the false negative generated referring expressions. For this, referring generations are generated for all the non-target objects and distractors in the images using the GRE-algorithm. Importantly to notice is that the referring expressions may not uniquely identify a distractor, since multiple distractors with the same shape, color and size are allowed. If the generated description of the model describes an object that is not the target object, it gets assigned 100%. If not, independently of describing the target object, no object, or one of the objects insufficiently, it gets assigned 0%. Using this measure, we can get an overview if the model’s problem lies in extracting and relating attributes or in understanding which of the presented objects is the target object.

The RE generator models are trained on both ‘Dale’ datasets. Again, each of these datasets increases the complexity of the description. While the referring expression for the ‘Dale-2’ datasets are generally shorter, expressions of the ‘Dale-5’ datasets need to be more specific and use more attributes. Additionally, the model needs to attend to many more locations in the image at the same time to find discriminating factors between those. Furthermore, the models are trained on the ‘CLEVR color’ dataset. In this dataset, the focus lies mainly on only one discriminating attribute, the color. This might help the model in its prediction and

will be tested in the experiments.

Results

Table 6 shows the *overall accuracy*, *F1 scores* for each word and the *non-target accuracies* of the **bounding box RE generator** when trained on the 'Dale-2', 'Dale-5' and 'CLEVR color' datasets. As can be seen, the overall accuracies, in other words perfect matches of the generated referring expression depend very much on the dataset. With the 'Dale-2' dataset, the model can achieve perfect matches in 99% of the cases in its best configuration. Also the 'CLEVR color' dataset allows the model to predict the correct referring expression in 93% of the samples. Opposed to that the model can only generate perfect referring expressions in 69% of the samples of the 'Dale-5' dataset. Looking at the *non-target accuracy*, one of the problems can be identified for the 'CLEVR color' dataset. Summing the *non-target accuracy* and the *overall accuracy*, one gets the accuracy that any of the shown object was described independently if it was the target object. For the 'CLEVR color' dataset, this score lies at 96% to 97% in the best configurations, which means that the model described a shown object for almost all the samples. In 3% to 4% of the cases, the model only picked the wrong object to describe. This looks different for the 'Dale-5' dataset. Here, the model describes only in 71% of the cases one of the shown objects, 69% the target object and 2% a distractor. The model therefore struggles more with the correct generation of words than with choosing, which object to describe.

When looking at the different configurations, in especially different values for e , $LSTM_o$ and $LSTM_e$, it can be seen that the results are not very different for the 'Dale-2' and 'CLEVR color' datasets. However, bigger effects can be identified for the 'Dale-5' dataset. Here, a low output dimension of the LSTM $LSTM_o$ tends to give lower scores. This especially enhanced, when also the embedding dimensions of the tokens $LSTM_e$ is low. Again, the image embedding size e doesn't seem to have a big effect, when over 50 dimensions. Indeed, the model achieves an accuracy of 69% with all three tested embedding sizes.

e	$LSTM_o$	$LSTM_e$	Dale-2			Dale-5			CLEVR color		
			Acc.	F1	NT	Acc.	F1	NT	Acc.	F1	NT
100	100	10	97	97,67	1	65	88,17	2	92	94,95	3
100	100	15	97	97,77	0	62	86,51	2	92	94,45	4
100	100	30	98	97,81	1	65	87,97	2	92	94,47	4
100	500	10	98	98,16	0	67	88,13	2	93	95,18	4
100	500	30	99	98,57	0	69	89,53	2	93	95,17	3
100	1000	10	98	98,28	0	68	88,23	2	93	95,41	3
500	1000	30	99	98,85	0	69	89,15	2	93	95,05	4
500	500	10	99	98,71	0	67	88,99	2	93	95,4	3
1000	100	10	97	97,72	0	59	85,43	2	93	95,04	4
1000	100	30	98	98,16	0	61	86,77	2	92	94,68	4
1000	1000	10	99	98,95	0	69	89,21	2	93	95,15	4
1000	1000	15	99	98,67	0	68	88,98	2	93	95,01	4

Table 6: Overall accuracies (Acc.), F1-Score (F1) and non-target accuracies (NT) in % of the bounding box RE generator after 30 epochs: e are different embedding sizes, $LSTM_o$ are different LSTM output sizes and $LSTM_e$ are different embedding sizes for the tokens in the LSTM.

Tables 7 and 8 give a more detailed insight in the results and especially what mistakes the model is making for both the 'Dale-5' and 'CLEVR color' datasets. They list *precision* and *recall* metrics for each token for the best configuration of the model with $e = 100$, $LSTM_o = 500$ and $LSTM_e = 30$. The tokens are grouped by attribute and also show the metrics averaged over each of the attributes. Since the overall results for the 'Dale-2' dataset are already close to perfect, the focus for this analysis lies on the remaining two datasets. The metrics of the $\langle pad \rangle$ token indicate if the model produced the correct length of the referring expression,

in other words if it was able to determine which attributes are necessary to discriminate the target object from the distractors. For the 'CLEVR color' dataset, the scores are perfect. This is not surprising, because all referring expressions for the 'CLEVR color' dataset consist of exactly two attributes, shape and color, and the first generated token will always be the only $\langle pad \rangle$ token in the referring expression (corresponding to the unspecified size). The $\langle pad \rangle$ token is therefore easy to learn. For the 'Dale-5' dataset, the model struggles more to predict the correct length of the referring expression.

When looking at the tokens for the shape, it can be seen that the model is able to identify it very well across all datasets. The model predicts the correct shape for all samples using the 'CLEVR color' dataset, while both *precision* and *recall* lie around 98,3% when using the 'Dale-5' dataset. Even though the score is almost perfect, the slight difference might stem from the fact that all distractors have the same shape in the first case, while distractors can be different in the second case. Consequently, the model is only exposed to one shape at a time for each sample, which might simplify its identification.

For the color attribute, the metrics drop significantly for both 'Dale-5' and 'CLEVR color' to an average of around 93%. Hereby, no meaningful difference can be seen across the datasets, but there are differences between the colors. Some colors are predicted with *precision* and *recall* around 95% to 96%, while others are only around 90%. However, these differences are not reproducible across multiple runs and configurations. The best and worst predicted colors vary and no conclusions can be drawn which colors are easier to predict for the model.

Finally, the size is the most difficult attribute to predict for the model. Apart from the 'CLEVR color' dataset, where a size never needs to be predicted and also is never predicted, the metrics for the prediction of size tokens are the lowest across all tokens. They are the only mistakes, the model makes, when exposed to the 'Dale-2' dataset and the average *precision* lies around 23% below the average of predictions of the color for the 'Dale-5' dataset, while the average *recall* lies around 28,82% below. The reason why the *precision* is higher than the *recall* is the $\langle pad \rangle$ token, which is predicted very often instead of a token specifying the size. In fact, the opposite relationship is visible for the *precision* and *recall* for said token. The much higher absolute number of $\langle pad \rangle$ tokens leads to a smaller relative difference of %-points shown in the table. Again, no conclusion can be drawn if larger or smaller objects are easier to predict, since the results vary across runs and configurations.

		small	large	size	cube	cylinder	sphere	shape	$\langle pad \rangle$
Dale-2	Precision	99,17	98,29	98,73	99,86	99,71	99,67	99,75	99,64
	Recall	97,54	94,26	95,9	100	99,56	99,67	99,74	99,77
Dale-5	Precision	69,65	69,21	69,43	98,19	98,32	98,39	98,3	82,22
	Recall	62,11	66,15	64,13	98,79	97,87	98,25	98,3	84,59
CLEVR color	Precision	-	-	-	100	100	100	100	100
	Recall	-	-	-	100	100	100	100	100

Table 7: Precision and Recall in % for $\langle pad \rangle$, size and shape tokens with $e = 100$, $LSTM_o = 500$ and $LSTM_e = 30$. The columns **shape** and **size** show the average across all tokens of the respective attribute.

The approach, how the padding is produced and in which order the attributes are concatenated didn't have an effect on the described metrics. When the order was reversed and the padding appended, the model was converging slightly faster and reached the limit around two to three epochs earlier. The final peak stayed exactly the same and the effects were therefore not studied deeper.

In conclusion, it can be said that the model is able to extract discriminative features from the shown bounding boxes and produce referring expressions. However, the result highly depends on the amount of distractors

		blue	brown	cyan	gray	green	purple	red	yellow	color
Dale-2	Precision	94,51	98,77	97,59	98,68	98,89	98,8	97,47	100	98,09
	Recall	97,73	100	98,78	97,4	96,74	98,8	100	98,8	98,53
Dale-5	Precision	92,12	93,82	89,13	89,12	92,63	91,12	97,24	94,36	92,44
	Recall	92,12	89,78	94,91	94,51	95,71	92,42	89,34	94,85	92,95
CLEVR color	Precision	93,46	92,37	94,47	93,86	92,04	91,13	90,07	94,7	92,76
	Recall	92,75	92	95,98	89,92	94,12	91,13	94,23	91,91	92,76

Table 8: Precision and Recall in % for color tokens with $e = 100$, $LSTM_o = 500$ and $LSTM_e = 30$. The column **color** shows the average across all colors.

and the resulting need of more discriminative features to describe the target object. While the shape is easily identified, the model has bigger problems to identify the color and especially the size of the target object.

In the following paragraphs, the results of the **basic RE generator** as well as the **masked RE generator** are evaluated. Compared to the *bounding box RE generator*, the task differs substantially. Instead of bounding boxes, the model is shown the image of the whole scene. In addition to extracting features of the target object and distractors separately, the model is now tasked to extract these at once for all objects. Furthermore, it needs to learn which of the objects is the target object by combining the image with the masked image. The *basic RE generator* acts hereby as a baseline. Since there is no information about the target object present, the model is expected to extract the features of all objects, but not to be able to focus on the target object. Masking should help the model, to also solve the second task.

		Dale-2			Dale-5			CLEVR color		
$LSTM_o$	$LSTM_e$	Acc.	F1	NT	Acc.	F1	NT	Acc.	F1	NT
100	30	38	41,16	40	14	48,91	34	15	36,98	34
1500	15	45	62,66	45	17	51,89	38	13	35,85	33
2000	10	45	60,72	44	16	50,77	37	13	34,96	36

Table 9: Overall accuracies (Acc.), F1-Score (F1) and non-target accuracies (NT) in % of the basic RE generator after 30 epochs for selected configurations: $LSTM_o$ are different LSTM output sizes and $LSTM_e$ are different embedding sizes for the tokens in the LSTM.

Table 9 shows some selected results for the *basic RE generator* after 30 epochs. The sum of the *overall accuracy* and *non-target accuracy* represents in how many cases any of the shown objects were described, independently if it is a distractor or the target object. As can be seen, the sum is always relatively high independently of the dataset. This shows verifies that the model is able to extract information about the objects in the image. However, it can't decide which object to describe. Most clearly, this is shown with the 'Dale-2' dataset where the sum lies around 90%. In almost all samples, the model describes an object perfectly, but in 45% of the cases it is the target object, in 45% the distractor. Which object, the model chooses is pure chance. The same pattern is visible for the other datasets. Since there are more distractors in the scenes, the model is more likely to describe one of those, when deciding randomly, and the *non-target accuracy* is higher than the *overall accuracy*. However, another fact plays a role here. The incremental GRE-algorithm can only generate unique referring expressions, when the referred to object is unique in the scene. This applies to all target objects, but there is no such restriction on the distractors. One scene can include for instance multiple *large red spheres* as distractors. The algorithm then generates two identical referring expressions which can affect the *non-target accuracy*. Indeed, while the average number of distractors per scene in the 'CLEVR color' dataset is 7,5, the average number of unique distractors lies at 2,7. As seen later, the model learns to correctly never predict a *size* and always predict the correct *shape*. Given this

fact, a random guess of a color would predict in $\frac{1}{8} * 2, 7 = 33, 9\%$ of the cases a unique distractor while in $\frac{1}{8} = 12, 5\%$ of the cases it would predict the target object. This corresponds the *non-target accuracies* and *overall accuracies* the 'CLEVR color' dataset. The high *non-target accuracy* is therefore misleading and doesn't represent that the model identified other objects in the scene.

$LSTM_o$	$LSTM_e$	Dale-2			Dale-5			CLEVR color		
		Acc.	F1	NT	Acc.	F1	NT	Acc.	F1	NT
100	10	81	76,16	9	21	57,07	23	16	43,69	31
100	15	78	72,06	11	17	53,29	25	26	50,87	30
100	30	83	78,76	7	19	54,91	24	29	53,37	26
500	10	83	79,78	6	27	62,05	16	17	44,93	32
500	15	83	79,75	7	28	63,78	16	21	47,08	31
500	30	84	83,03	5	30	64,36	17	21	40	31
1000	10	84	82,2	5	31	65,58	13	12	37,67	34
1000	15	85	82,62	5	31	64,28	16	16	43,27	32
1000	30	85	83,13	4	31	64,06	17	13	41,79	34
1500	10	84	81,27	4	33	67,5	14	12	39,04	34
1500	15	85	84,11	4	35	69,05	12	17	44,98	31
1500	30	84	80,93	4	36	68,97	15	14	42,99	33
2000	10	83	82,69	4	36	69,11	13	13	41,85	34
2000	15	84	81,95	4	34	66,94	14	14	38,79	33
2000	30	85	82,8	4	32	65,52	16	18	45,41	32
3000	10	82	79,83	4	34	67,61	12	12	38	34
3000	15	85	81,8	4	32	65,64	15	13	38,52	35
3000	30	83	80,6	3	30	63,5	16	12	38,45	34

Table 10: Overall accuracies (Acc.), F1-Score (F1) and non-target accuracies (NT) in % of the masked RE generator after 30 epochs: $LSTM_o$ are different LSTM output sizes and $LSTM_e$ are different embedding sizes for the tokens in the LSTM.

Table 10 shows the results for the *masked RE generator* after 30 epochs. A first look at the sum of the *overall accuracy* and the *non-target accuracy* shows the model is able to extract the attributes from the shown objects. For the 'Dale-2' dataset, this number lies at 90% for the best configuration, at 51% for the 'Dale-5' dataset and at 55% for the 'CLEVR color' dataset. Those sums correspond more or less to the sums of the model without masking shown in Table 9. In other words, the masking doesn't hinder the model to extract and describe attributes in the image. However, the balance in between the two accuracy scores shifts towards the *overall accuracy*, meaning that the model is now able to identify the correct target object more often. While the model still achieves 85% *overall accuracy* in its best configuration, for the 'Dale-2' dataset, the model only reaches 36% for the 'Dale-5' dataset and 29% for the 'CLEVR color' dataset. The scores for all datasets are all well above the *basic RE generator* baselines of 45%, 16% and 15% respectively, while in all cases the *non-target accuracies* drop lower. In other words, the masked image helps the model to focus on the correct object.

Comparing it to the less complex *bounding box RE generator*, the results are much less accurate. This applies to all datasets, even though it is most apparent for the 'CLEVR color' dataset. Given the highly increased complexity of the task, the model fares well in comparison on the *Dale* datasets.

Moreover, the referring expression generated for the 'Dale-2' dataset are also efficient in the sense that they follow the incremental GRE-algorithm and only use necessary discriminative attributes. Features of both target object and distractor are therefore extracted and associated with the vocabulary. Striking in these results is also the *non-target accuracy*, which is much higher than for the *bounding box RE generator*. For

the 'Dale-2' dataset, it arrives at 11% in one configuration, for the 'Dale-5' dataset, the model describes for at least 12% of the samples a distractor, for one configuration even in over 25% of the cases. The *non-target accuracy* of the 'CLEVR color' is misleading, and is therefore not considered. This shows that the model still struggles to learn which of the objects in the scene is the target object, even though masking is applied.

Looking at the effects of the LSTM output size $LSTM_o$ and the LSTM embedding size $LSTM_e$, a difference between the *Dale* datasets and the 'CLEVR color' dataset can be identified. A higher $LSTM_o$ tends to increase the performance of the model, when presented with the *Dale* datasets until a size of 1500 to 2000 dimensions. When it is further increased the model starts to perform worse. Furthermore, with a low $LSTM_o$, the model is more likely to identify and describe a distractor, while a higher $LSTM_o$ helps the model to focus on the target object. The $LSTM_e$ however doesn't seem to have a big consistent effect on the results. With an $LSTM_o$ of around 1500 to 2000, the model seems to fare slightly better with higher $LSTM_e$ of 15 or 30 dimensions. For the 'CLEVR color' dataset, the results look different. Opposed to the former datasets, a lower $LSTM_o$ helps the model to describe the correct target object. On the other side, the *non-target accuracy* stays relatively constant independently of the variables at the same level as for the *basic RE generator*. This indicates that the model uses random guesses of the color when it is not able to extract the color of the target object. To confirm this, the model's performance on different tokens and attributes are analyzed.

		small	large	size	cube	cylinder	sphere	shape	<pad>
Dale-2	Precision	68,63	76	72,31	98,41	98,18	98,92	98,5	94,77
	Recall	30,17	34,55	32,36	98,7	98,33	98,47	98,5	98,64
Dale-5	Precision	49,47	57,3	53,38	87,09	83,26	84,78	85,04	64,99
	Recall	24,67	26,7	25,69	83,66	85,28	86,03	84,99	77,87
CLEVR color	Precision	-	-	-	100	100	99,7	99,9	100
	Recall	-	-	-	99,85	99,85	100	99,9	100

Table 11: Precision and Recall in % of <pad>, size and shape tokens in the best configuration for each dataset (marked in bold in Table 10). The columns **shape** and **size** show the average across all tokens of the respective attribute.

		blue	brown	cyan	gray	green	purple	red	yellow	color
Dale-2	Precision	88,89	85,9	81,82	85,53	79,76	84,52	87,76	87,36	85,19
	Recall	89,89	83,75	87,8	79,27	93,06	76,34	90,53	81,72	85,3
Dale-5	Precision	69,51	72,73	73,48	66,27	63,23	64,32	67,98	70,76	68,53
	Recall	72,43	71,29	73,48	60,77	74,6	74,87	71,13	73,57	71,52
CLEVR color	Precision	37,63	39,23	22,09	20,23	33,33	22,97	24,9	43,96	30,54
	Recall	29,44	42,68	27,48	22,22	25,44	26,53	26,23	37,14	29,64

Table 12: Precision and Recall in % of color tokens in the best configuration for each dataset (marked in bold in Table 10). The column **color** shows the average across all colors.

Tables 11 and 12 shows the precision and recall for each token. The metrics on the <pad> token show that the model always predicts the correct length of the referring expression when presented with the 'CLEVR color' dataset. For the 'Dale-2' dataset, the model is able to do this in almost all the cases, while the model struggles the most with the 'Dale-5' dataset. While this was similar to the *bounding box RE generator*, the effect here is amplified. Furthermore, the easiest attribute to predict is the shape. Again, the metrics for the 'Dale-2' and 'CLEVR color' dataset are almost the same, but the model is much less able to predict the correct shape for images from the 'Dale-5' dataset with only around 85%. Hereby, the precision is the

highest for predicting *cubes* and lowest for predicting *cylinders*, but this varies across runs.

The prediction of the color drops very much in comparison. While the metrics all lied above 90% for the *bounding box RE generator*, now none of datasets passes this limit. With the 'Dale-2' dataset, the precision and recall lie around 85%, with the 'Dale-5' dataset around 70% and around 30% with the 'CLEVR color' dataset. The drop for the 'Dale' datasets is expected, because of the higher complexity of the task, but the model's performance on the 'CLEVR color' dataset is much worse. Only every third prediction is correct. Hereby, a difference across the colors is visible. Some colors reach both precision and recall of around 40%, while others only of only around 20%. Again, which color is captured better differs from run to run. Interesting is also the margin between the precision and recall for the colors 'blue', 'cyan', 'green', 'purple' and 'yellow'. A low precision and high recall indicates that the model predicts the specific color more often than needed while the opposite indicates that it predicts the color less often than needed. In particular, 'blue', 'green' and 'yellow' are predicted too often and 'cyan' and 'purple' are predicted too few.

Finally, the size is again the most difficult attribute to predict. As the *bounding box RE generator*, the *masked RE generator* learns correctly to never predict a size for the 'CLEVR color' dataset. Interestingly is the fact that the recall is low which shows that the model likely predicts a *<pad>* token instead. This might be due to the fact that the *<pad>* token is very frequent in the size slot across all referring expressions and the model amplified this fact. Between both sizes, 'large' objects are easier to predict for the model than 'small' objects. The difference lies for both *Dale* datasets at around 8%. However, the precision is still far above a random guess, when used on the 'Dale-2' dataset. Using the 'Dale-5' dataset, the precision only lies at around 50% to 57%.

In conclusion, when the model doesn't need to extract the objects from the scene it performs very well. In this case, it is able to achieve almost perfect results on the 'Dale-2' dataset and very good results on the remaining two datasets. However, using complete scenes impairs the performance highly. The *overall accuracies* decrease and the *non-target accuracies* increase; the model has more difficulties to focus on the correct object. The most difficulties the model has with the 'CLEVR color' dataset where only the color is a discriminative attribute. Looking at the attributes, the last slot (shape) is always the easiest to predict, while the first slot (size for the *Dale* dataset and color for the 'CLEVR color' dataset) is the most difficult. This effect is again amplified when the model needs to extract the objects itself instead of being presented with bounding boxes.

There are two main explanations for these results. First, as already seen in the previous experiments, a bigger number of distractors confuses the model more where to focus on. In the 'Dale-2' dataset, there are only two possibilities, while the four distractors in the 'Dale-5' dataset and up to nine distractors in the 'CLEVR color' give the model a bigger choice. Moreover, having only one attribute to discriminate the target object, poses the model with more difficulties. The second explanation lies in the incremental GRE-algorithm. For instance using the 'Dale-2' dataset, when only two random objects are placed in a scene, a second (or third) attribute to discriminate the objects is only needed, when the shape is the same. Otherwise, the shape is enough, and the RE is only one word long. The probability for this lies at 66,6%. For shape and color being enough, the probability lies at 29,2% and that all three attributes are necessary is 4,1%. Opposed to that the probabilities with four distractors as in the 'Dale-5' dataset are 19,8%, 47% and 33,2% respectively. With four distractors the algorithm is much more likely to produce longer referring expressions. These are harder to learn and generate for the model since it needs to take more extracted attributes into account to discriminate the target object from the distractors. This is verified by the lower precisions and recalls of the size and color tokens. Furthermore, the low recall of the size tokens shows that the model produces too short referring expressions too often.

5.3 Reference resolution

Setup

With the reference resolution task, the model is trained to understand referring expressions, by pointing towards the target object in the scene. Compared to the object identification task in Section 5.1, this task is more complex since it also includes identifying locations instead of choosing from given objects. This level should help to analyze, how the final task of the language game should look like, in especially what the receiver is tasked to predict. As described before, the sender should communicate an object in the image and the receiver needs to identify it. The challenge lies in how the receiver refers to the identified object. There are multiple possibilities, how it can be done. One of them could be to describe the target object with human language, using the attributes. The main goal however is to let the language of the agents emerge as natural as possible. Including human referring expressions into the task would bias also the emerged language towards attributes and words, used in natural language. For this reason, the final task of the receiver will be to 'point' to the target object. In this section, this is done in two ways. First, the models are tasked to predict the center coordinates of the target object (*coordinate reference resolver*). This requires a very high precision of the model in extracting spatial information. However, the exact location is not necessarily important to highlight, which object the model predicts to be the target object, and might challenge the model too much. Therefore, in a second approach, the model is tasked to predict a region around the target object (*attention reference resolver*). This reduces the necessary amount of spatial information and might be easier to learn for the models. With both approaches, the models receive few natural language information, but are still able to rely on all information present in the image to discriminate the objects.

In the simplest setup, the **coordinate reference resolver**, the model receives only the image as an input and produces two numbers as an output, the predicted x- and y-coordinate of the target object. Again, the image is encoded, using the *image encoder* submodule, described in Section 3.3. The *coordinate predictor* submodule takes the encoder image to predict x- and y-coordinates of the target image, Hereby, the encoded image is flattened and passed through two linear layers with a *ReLU* non-linearity in between. These reduce the dimensions first to the coordinate predictor dimension c and finally to 2.

To determine the loss, the euclidean distance between the resulting predicted point on the image and the ground truth point are calculated. This distance is learned to be minimized. By doing that, the model learns to focus and attend on a specific part in the image, in a perfect model the center of the target objects.

With this simple setup, the model is theoretically able to very precisely focus on an object in the image. The problem arises as soon as multiple objects are present in the image. There is no information available for the model to understand which one of these objects is the actual target object, except for the final calculation of the loss. Since there is not necessarily a pattern for which object in the image is the correct target object over the whole dataset, the models will likely fail to generalize. Therefore, the models need to receive more information. Here, four different ways to encode and refer to the target object are tested.

In the first method, the target objects' attributes are encoded as **one-hot encodings**, as described in Section 5.1. In an extension to this method, also the **center coordinates of all objects** in the image are included. The center coordinates of all objects are simply extracted. Since there is no direct way of ordering objects, distributed in 2 dimensions into a list, these are shuffled, to just provide the model with all possible targets to choose from. Since there are varying numbers of objects in the image, this vector of variable length is padded to the maximum number of objects in the dataset. The padded locations consist of two zeros for both coordinates. In both methods, the encodings of the target object are concatenated with the encoded image and then passed to the coordinate predictor.

The third method encodes the attributes of the target object with human language using the **incremental**




Figure 10: Simplified architectures of the *coordinate reference resolvers*

GRE-algorithm. This opposes the idea described before, to share as few natural language information as possible with the model. Still, this approach can help to understand and analyze if the model was able to extract information about the objects and more specifically their attributes from the image. If the model is able to match parts of the image with human words it would show that the model learned this attribute. If the model in a next step can learn this for the whole dataset, this would mean that it could generalize over these attributes and assign them to certain regions in an image. This insight would help for succeeding models that make use of these learnings without human language.

For the experiments, each image is captioned with a referring expression of the target object using the described algorithm. To include it in the model, the referring expressions need to be padded to an equal length. In this case they are padded to a length of 3, which is the maximum number of attributes that can be used. For this, as standard practice in captioning tasks, the referring expressions are padded at the end with a specified padding token.

In the model, the referring expression is encoded, using the *GRE parser* submodule. Here, the learned embeddings of each token are parsed by the LSTM and its final hidden state is then used as a summary of the complete referring expression. Tokens are embedded with embedding dimensions $LSTM_e$ and the output of the LSTM has the size if $LSTM_o$. The vocabulary that is used for the descriptions is based on 14 symbols, including the padding token. Both the processed image and the final hidden state of the LSTM are flattened and concatenated, which is then passed through the coordinate predictor.

The fourth method, to encode the target object utilizes **masking** of the image. The image is masked in the same way as in Section 5.2. While even the one-hot encodings contain human language knowledge by translating human referring descriptions into a vector, the masking method will only point the model towards the target object without giving more information. It therefore can only rely on its own extracted visual features and the inherent human bias in the image when looking at masked images. Both original and masked image are processed as described in 3.3 and afterwards passed through the coordinate predictor.

For all setups, the same hyperparameters as in the previous experiments are used: a learning rate of 1×10^{-4} and 30 epochs. The loss is calculated using cross entropy. Table 13 shows the variables that are changed during the experiments for each of the models.

	e_i [50, 100, 300, 500]	c [512, 1024, 2048]	$LSTM_e$ [15, 30]	$LSTM_o$ [1000, 1500]
coordinate reference resolver	×	×	-	-
+ one-hot	×	×	-	-
+ one-hot + locations	×	×	-	-
+ incremental RE	×	×	×	×
+ masking	×	×	-	-

Table 13: Variables for each model where e_i is the image embedding dimension, c the dimensions of the coordinate predictor, $LSTM_e$ the embedding dimensions for tokens in the LSTM and $LSTM_o$ the output dimension of the LSTM

The test dataset is again evaluated on the euclidean distance of the predicted coordinates to the ground truth coordinates. This distance needs to be minimized. The mean of all calculated distances is calculated across the whole epoch, which results in a mean distance score per epoch. Since this score only takes the average of all predictions into account it doesn't show how every prediction fared individually. If for instance the prediction of one object is getting more precise with growing number of epochs, but the precision of another object gets worse, the mean distance will stay the same. It doesn't reflect this change. For that reason, we also introduced an accuracy score. For that we defined a fixed size circle with a radius of 20 pixels around the center of each object. If the model's prediction lies in this circle, it will be counted as a correct prediction, if it lies outside, it is a false prediction. These scores are averaged for the epoch and result in an accuracy score, where 100% means that all predictions were very close to the center coordinates and 0% means that no predictions were close to the center coordinates. This of course doesn't give a perfect representation since the size of the objects varies, but it will still show, how precise each individual prediction is. A high accuracy may indicate that the model could identify this specific object better.

In the second approach, the **attention reference resolver** predicts a region around the center of the target object. For this, the image is divided into 14×14 regions. The target area is located around the center of the target object, consisting of 3×3 regions. Hereby, the center of the target object is located in the central region. The model is then tasked to predict the matrix $A = (a_{ij})$, where:

$$a_{ij} = \begin{cases} 1, & \text{if region } i, j \text{ in target area} \\ 0, & \text{otherwise} \end{cases}$$

To do this, the model combines a representation of the image and a representation of the target object. More specifically, the image is encoded using the *image encoder* submodule, omitting the last *max pool* layer. By this, the resulting matrix has $128 \times 14 \times 14$ dimension, corresponding to the 14×14 regions. For the target object, the incremental RE is passed through an LSTM as described before. Both encodings are passed through two linear layers separately to project them to the projection dimension p , followed by the *tanh* function. Following, the dot product is calculated between the projected image and the projected attributes which results in a 14×14 matrix. This emphasizes the correlation between the attributes and each region. A high dot product for a region indicates a high correlation between the attributes and the specific region, while a low dot product indicates the opposite. Training a model like this should therefore highlight the regions in the image that are described by the referring expression, namely the region around the target object. To calculate the loss, the *softmax* function is applied over the prediction and compared to the ground truth matrix A using the *binary cross entropy*. Figure 11 shows the architecture. Hereby, the models converged faster and were trained for 20 epochs with a learning rate of 2×10^{-4} . An $LSTM_e = 15$ and $LSTM_o = 1500$ showed the best results. Projection sizes $p = \{50, 100, 300, 500, 1000\}$ are compared.




Figure 11: Simplified architecture of the attention predictor

The *attention reference resolver* is evaluated on the summed predicted probability for the regions in the target area. In particular, the predicted matrix, consisting of probabilities for each region is multiplied with the ground truth matrix A , consisting of only ones and zeros. The result is summed and returns the probability mass for the target area. If the model predicts the target area perfectly, the probabilities in the target area sum to 1. If the model for instance focuses on the wrong object, the probability mass in the target area is lower.

The reference resolution models are trained on the 'CLEVR single' as well as on both 'Dale' datasets. The 'CLEVR single' dataset should test the model if it can actually learn locations of an object. Since the model relies on the extracted features of ResNet, locational information of the objects in the image might not be present anymore. This is due the fact that CNNs compress information of the image summarizing small regions (convolutions) several times. While this extracts the key features of objects in an image and might capture relational position between these objects, absolute locations might get lost as shown by [Kelleher & Dobnik \(2017\)](#). Training on this dataset should make sure that the model can converge towards the correct pixels, utilizing these features. In a next step, the 'Dale' datasets provide the actual problem of discriminating objects from each other and afterwards pointing to the correct one. Here, the models should make use of the additional given referring expressions about the scene, as one-hot encodings of the attributes, descriptions using the incremental GRE-algorithm or the encoded locations. 'Dale-2' and 'Dale-5' provide two different difficulties for the model, where it needs to discriminate a target object from one or four distractors and then point towards it. Latter task is assumed to be significantly harder.

Results

Tables 14 to 18 show the results of the five adaptations of the reference resolver. Across the first three models (basic reference resolver, +one-hot, +one-hot+locations), the same patterns can be seen.

The **basic reference resolver** acts as a baseline for the other models. Since this model doesn't have any information about the target object, it shouldn't be able to point towards the correct target object. However, this model should learn underlying structures in the images that it can use to make better predictions. Indeed, the model converges on all datasets to a certain limit. Random guesses of the coordinates correspond to a mean distance of 95 pixels, given the image size of 224×224 pixels, which the model can beat for all datasets.

Table 14 shows the results. When trained on the 'CLEVR single' dataset, the model can minimize the

e_i	c	CLEVR single		Dale-2		Dale-5		CLEVR color	
		loss	Acc.	loss	Acc.	loss	Acc.	loss	Acc.
100	512	2,45	96%	38,16	35%	46,44	18%	51,8	12%
100	1024	2,18	94%	37,23	38%	47,38	18%	52,04	13%
100	2048	3,44	99%	36,8	40%	46,77	18%	51,29	13%
500	512	2,71	96%	37,1	37%	47,28	18%	51,01	14%
500	1024	2,61	97%	36,2	39%	48,6	17%	52,73	12%
500	2048	5,18	99%	36,09	40%	44,81	18%	51,8	13%

Table 14: Mean loss and accuracy of the basic reference resolver for different configurations of the model after 40 epochs: e_i is the image embedding dimension and c the coordinate predictor dimension

mean loss consistently across all variations of the variables to a few pixels. In effect, this means, that the model is able to almost always predict the correct location of the center of the target object. Since no distractor is present, the model also doesn't need any description of the target object and only needs to discriminate the object from the background. This shows that the model is in general able to derive geometrical information from abstract feature, extracted by a feature extractor. Geometrical information therefore doesn't get completely lost during this abstraction, but the model is able to point to a specific object, as long as only one object is part of the image.

However, the model has more difficulties when distractors are present in the image. For the 'Dale-2' dataset, the mean loss converges towards 35 to 39 pixels. The model was able to extract some structural information from the image, but the predictions are not consistently on the target object. Looking at the accuracy, the best variations of the models are only able to point in 41% to 42% of the samples towards the correct object, which lies just below a random guess of 50%. Using the 'Dale-5' and the 'CLEVR color' datasets, the results are similar. While the mean loss stays consistently around 46 to 48 pixels and 50 to 53 pixels respectively, they are still far below the random baseline. Also the accuracies, lie a bit below the random guesses of 20% and 15% respectively. However, it is visible that more present distractors in the scene challenge the model more.

Looking at the image embedding size e_i and the coordinate predictor dimension c , it seems, they don't have any significant effect on the results. The results staying the same across all variations indicates that the increase compared to the random baseline is just due to learning an underlying structural pattern of how scenes are set up. This hypothesis will be discussed further below with examples from the predictions.

Interestingly, providing the model with the target object encoded as a **one-hot vector** and the **locations** of

e_i	c	CLEVR single		Dale-2		Dale-5		CLEVR color	
		loss	Acc.	loss	Acc.	loss	Acc.	loss	Acc.
100	512	2,95	98%	37,27	34%	47,05	18%	51,25	12%
100	1024	3,64	98%	37,19	37%	46,39	19%	50,25	14%
100	2048	6,15	99%	37,04	39%	45,77	18%	50,55	14%
500	512	3,29	98%	38,58	34%	47,25	18%	50,56	14%
500	1024	2,15	93%	37,18	40%	47,57	18%	51,75	14%
500	2048	2,86	98%	35,71	41%	46,62	18%	52,67	11%

Table 15: Mean loss and accuracy of the *reference resolver + one-hot* for different configurations of the model after 40 epochs: e_i is the image embedding dimension and c the coordinate predictor dimension

e_i	c	CLEVR single		Dale-2		Dale-5		CLEVR color	
		loss	Acc.	loss	Acc.	loss	Acc.	loss	Acc.
100	512	3,02	97%	36,88	37%	47,04	16%	51,36	12%
100	1024	2,48	95%	38,24	33%	46,91	15%	52,67	12%
100	2048	3,8	100%	37,89	32%	45,33	13%	49,12	11%
500	512	3,6	98%	35,56	42%	47,41	16%	51,86	12%
500	1024	2,51	98%	36,56	39%	45,88	17%	51,73	12%
500	2048	2,37	97%	37,33	35%	48,04	16%	53,68	11%

Table 16: Mean loss and accuracy of the *reference resolver + one-hot + locations* for different configurations of the model after 40 epochs: e_i is the image embedding dimension and c the coordinate predictor dimension

all objects doesn't improve the results. Tables 15 and 16 show the same results as for the *basic reference resolver*. It seems that the model is not able to combine the image representation with the representation of that target object or the locations of all objects and another representation is needed.

e_i	c	$LSTM_o$	$LSTM_e$	Dale-2		Dale-5		CLEVR color	
				loss	Acc.	loss	Acc.	loss	Acc.
50	1024	1000	15	22,64	63,55%	48,23	14,95%	52,62	11%
50	2048	1500	15	21,35	65,9%	46,95	16,75%	52,2	11,35%
100	1024	1000	15	16,08	75,5%	47,62	16,5%	50,65	12,8%
100	1024	1000	30	20,69	69,5%	46,9	16,45%	51,23	12,2%
100	1024	1500	15	21,24	66,3%	48,78	15,55%	52,21	12,25%
100	2048	1000	15	19,46	70,1%	46,79	16,9%	50,24	13,3%
100	2048	1500	15	21,19	66,65%	46,79	16,65%	50,55	11,3%
300	1024	1000	15	20,63	68%	46,91	17,4%	50,39	11,75%
300	1024	1500	15	21,38	66,15%	46,36	15,55%	51,29	12,25%
300	2048	1000	15	21,12	66,95%	46,98	16,65%	51,4	12,85%
300	2048	1500	15	14,01	79,45%	47,41	16,9%	51,32	12,6%
300	2048	1500	30	22,09	64,75%	46,77	17,65%	49,75	13,4%
500	1024	1000	15	35,14	41,25%	46,41	16,6%	50,63	12,8%
500	2048	1500	15	36,52	41,95%	44,9	18,65%	50,02	13,4%

Table 17: Mean loss and accuracy of the *reference resolver + incremental RE* for different configurations of the model after 40 epochs: e_i is the image embedding dimension, c the coordinate predictor dimension, $LSTM_o$ the output dimension of the LSTM and $LSTM_e$ the embedding dimensions for tokens in the LSTM

Encoding the attributes of the target object with the **incremental GRE-algorithm** finally improves the model's performance. Table 17 shows the results of selected configurations. Using the 'Dale-2' dataset, the model is able to predict the center coordinates of the target object for most of the images. The results, hereby, are dependent on the different variables. The best results are achieved with $e_i = 300$, $c = 2048$, $LSTM_o = 1500$ and $LSTM_e = 15$ and this configuration will be used in the succeeding analysis and the remaining language games experiments. With this configuration the mean distance of the model's predictions is around 14 pixels, and they lie in around 79,45% of the cases on the target object. This is far below the random guess of the center coordinates as well as better than a random choice between the objects. Comparing it to the other configurations, it becomes apparent that an image embedding size e_i between 100 and 300 dimensions provides the model with enough information from the image. Contrary to this, a relatively high decoder size of the LSTM $LSTM_o$ that decodes the referring expression is necessary. However, it seems to

be dependent on e_i . A larger e_i requires a larger $LSTM_o$. Preliminary experiments have shown that lower sizes didn't provide any good results. Furthermore, lower embedding dimensions of the tokens $LSTM_e$ tend to give better results. An $LSTM_e$ around the vocabulary size of 14 gave the best results while for instance more dimensions with 30 always worsened the model.

Using the 'Dale-5' and 'CLEVR color' datasets, providing the incremental referring expression to the model didn't help. The results are similar to the baseline with no information about the target object.

Finally, Table 18 shows the results, when the model is additionally provided with the **masked image**. Hereby, the model is able to predict correct locations using all datasets. All configurations achieve mean distances of a few pixels and accuracies of almost 100%. This shows that the model can make use of the masked image. However, this is also not surprising since the model doesn't need to use the original image, but can completely rely on the mask. Since the mask only includes the target object but no distractors, it corresponds to the 'CLEVR single' dataset which as already seen in the results before is an easy task to learn for the model.

e_i	c	Dale-2		Dale-5		CLEVR color	
		loss	Acc.	loss	Acc.	loss	Acc.
100	512	8,01	98%	6,77	100%	6,05	95%
100	1024	8,77	99%	3,61	98%	5,29	93%
100	2048	8,71	99%	4,28	96%	3,24	93%
500	512	14,27	99%	9,97	99%	5,9	94%
500	1024	8,6	99%	2,07	94%	13,03	95%
500	2048	2,67	95%	10,57	96%	4,24	98%

Table 18: Mean loss and accuracy of the *reference resolver + masking* for different configurations of the model after 40 epochs: e_i is the image embedding dimension and c the coordinate predictor dimension




Figure 12: Mean loss of training and testing data with all datasets, using attributes encoded with the incremental GRE algorithm. The following variables are used for all models: $e_i = 300$, $c = 2048$, $LSTM_o = 1500$, $LSTM_e = 15$


Figure 12 gives more insight in why the models don't converge to a lower mean loss. It shows how the

mean loss changes during the training after each epoch. Hereby, the figure shows the graph for the best performing configuration of the model that is presented with the incremental referring expression, using $e_i = 300$, $c = 2048$, $LSTM_o = 1500$ and $LSTM_e = 15$. The different colors correspond to the different datasets. Two lines are shown for each dataset. The solid line represents the loss when trained on the training data. The dotted line shows the mean distance to the target object of the model’s predictions when presented with the unseen test data. In particular, after each epoch, the model is frozen and tested on the test split. After this, the weights are unfrozen again and the training is continued. As can be seen, the training loss of the model always converges towards a low value. Unsurprisingly, the datasets with fewer distractors are faster to learn than ones with more. For both successful datasets, ‘CLEVR single’ and ‘Dale-2’, also the training loss converges towards the same value. However, the testing curves for the remaining two datasets don’t match their corresponding training curve. Indeed, both curves stay at the same value until around epoch 9. Then the loss of the training starts to drop while the loss in the testing starts to rise. That indicates that until epoch 9, the model learns to general structural patterns in the images that apply to the complete dataset, both training and testing split. After this, the model begins to memorize the training samples. This knowledge is not transferrable to the test split and indeed even harms the test performance slightly. That behavior can be observed for all models and configurations that don’t outperform the baseline. Preliminary experiments showed that applying dropout to help the model to generalize didn’t increase the performance which shows that the architecture is not able to extract the necessary features from the images and the referring expression and combine them.


An interesting pattern appears when doing a qualitative analysis of the models’ predictions. Here, the predicted coordinates compared to the ground truth coordinates are visualized (Figure 13), using the best performing model with $e_i = 300$, $c = 2048$, $LSTM_o = 1500$ and $LSTM_e = 15$. Figure 13(a) shows random examples of predictions for images in the train dataset of ‘Dale-2’. The green circle shows the ground truth center coordinates of the target object, while the red circle shows the prediction of the model. As can be seen, the predictions are very precise. Figure 14 combines the predictions and ground truths across all images in the train dataset. This shows general patterns of the models predictions over the complete dataset. Here, all predicted coordinates are placed as red circles into the image, while all ground truth coordinates are placed as green circles. For the predictions on the ‘Dale-2’ dataset, the resulting shape is a rhombus, which reflects that all objects are placed usually central into the scene (see Figure 14(a)). As expected the green and red rhombus align mostly in the same area for the train split of the ‘Dale-2’ dataset. Figures 13(c) and 14(c) show the same patterns for the ‘Dale-5’ dataset, while Figures 13(e) and 14(e) show it for the ‘CLEVR color’ dataset.

The results look very different when using the predictions for the test split. As discussed in the paragraphs above, the model performs well on the ‘Dale-2’ dataset which is also reflected in the qualitative analysis. The visualization of the test split resembles the train split very much. However, the other two datasets show differences. As can be seen in Figures 13(d) and 13(f), the three randomly selected predictions don’t align with the ground truth coordinates. While for some images they lie on a distractor, on some images, the prediction is on the background. However, they tend to be in an area towards the target object, but are still quite imprecise. These findings align with the mean distance scores, described in the paragraphs before. However, it seems that the model’s predictions are all towards the center of the image. This can be seen clearer in Figures 14(d) and 14(f). Again, the green circles form the shape of rhombus. In contrast, the predictions in red almost all cluster in the center of the image. They form roughly the shape of a smaller rhombus.


These results allow three conclusions. First, the underlying structure in all images is the placement of objects in the center of the scene. The models, learn to use the structure and are biased to predict coordinates towards the center. The reason for this is likely that the model can produce a relatively low loss, without relying on many extracted features of the objects. Since all objects are always located in the center of the image and never in its corners, a prediction of any coordinate in the center is on average closer to the target




(a) 'Dale-2', train split




(b) 'Dale-2', test split




(c) 'Dale-5', train split



(d) 'Dale-5', test split



(e) 'CLEVR color', train split



(f) 'CLEVR color', test split

Figure 13: Examples of the models' predictions on the 'Dale' and 'CLEVR color' datasets. The green circle represents the target object, the red object the model's prediction. Notice that the images are shown in the original size while the model processes them normalized. Hence, the distances don't correspond to the axes.




Figure 14: The images show all the model’s predictions (red dots) and the ground truths (green dots) combined for the ‘Dale’ and ‘CLEVR color’ datasets

object than any random prediction or predictions of coordinates at the borders of the image. The model therefore learns only, where *any* object is likely located and can minimize the mean distance to a certain extent with this strategy.

Secondly, even though the models are biased towards the center of the image, the predictions are still often leaning towards the location where many objects lie. This can be seen for the ‘CLEVR color’ dataset, especially in left and central image in Figure 13(f). Again, by this strategy, the model can minimize the mean distance, since the probability is high that the target object lies in this cluster of objects.

Thirdly, when few distractors are present in the scene, the model is able to combine the encoding of the referring expression with the encoding of the image. In particular, it is able to learn which of the objects in the image is described by the referring expression. As soon as more objects are present, the task gets to

difficult and the model only relies on the general patterns in the dataset. Concluding, the model is able to extract, where objects are located in the image, but can't consistently make use of the referring expressions, to decide which of these objects is the target object.

A central problem in the models' predictions is therefore the focussing on precise locations in the image and connecting them to the referring expression. The **attention reference resolver** is meant to solve this problem in two ways. First, the predictions must not be as precise, as only regions in a 14×14 grid need to be identified. Second, the referring expressions are naturally combined with each region in the image. While the *coordinate reference resolver* only combines the complete feature map with the encoded referring expression, the *attention reference resolver* calculates the similarity of each region with the referring expression separately. This should connect both encodings easier. As Table 19 shows, this hypothesis seems to be confirmed. Across all datasets, the model is able focus on the correct region in the image with high precision. On the 'Dale-2' dataset, the model is able to make 96,57% of its predictions in the correct regions around the target object with a projection size of $p = 500$. The worst result with $p = 300$ still only lies around 3% points below and therefore identifies the target object almost always correctly. These results still hold, when more distractors and more complex referring expressions are introduced. On the 'Dale-5' dataset, the model can achieve similar performances, with a probability mass of 93,61% with $p = 300$, while three of the remaining configurations stay above 92%. When the *color* is the only discriminating attribute, the model achieves again similar results to the 'Dale-2' dataset, despite the higher number of distractors of up to 10. The best performance of 95,33% is achieved with $p = 100$, but all configurations beat are almost reach 94%. In conclusion, the models are able to easily understand the referring expression and to ground them in the target object in the image. While more complex referring expressions challenge the model slightly more, it still can focus on the correct object.

	Dale-2	Dale-5	CLEVR color
p	Probability mass	Probability mass	Probability mass
50	94,47%	89,69%	94,36%
100	95,16%	92,19%	95,33%
300	93,65%	93,61%	94,15%
500	96,57%	92,29%	94,15%
1000	95,93%	92,93%	93,82%

Table 19: Probability masses of the *attention reference resolver* for different projection sizes p of the model after 20 epochs with $LSTM_e = 15$ and $LSTM_o = 1500$

This conclusion gets even more clear, when having a look at the image, where the model identified the wrong regions. Figure 15 shows three images for each dataset, where the model's predicted probability mass was lower than 60%. The errors of the models can be classified into three categories. Most of the errors are based on non-visible target objects. Either the target object is located outside the preprocessed cropped image, or it is partially hidden behind another object. Unsurprisingly, the model has difficulties to focus on these regions. However, in several cases, the models can still make use of small hints of the target object. In the left image of Figure 15(a), a corner of the target object is visible, which the model uses to 31,9% of its attention on. In the central image of the same figure, only the shadow of the target image is visible. Still, the model 44,8% of its attention onto the correct region, while the remaining probabilities are on adjacent regions. This indicates that the model can base its decision on excluding a distractor if it doesn't match the referring expression. This behavior is mainly visible on the 'Dale-2' dataset with only one distractor. On the 'Dale-5' dataset, the model often focuses one on of the remaining distractors. Hereby, the model still focuses on distractors that have attributes mentioned in the referring expressions, as the *sphere* in the left image of Figure 15(b) or the *cyan* and *cylinder* distractors in the central image.

The second category of errors includes errors in which the model confuses a distractor with the target object.

Most of the time, the model still focuses partially on target object, but the main focus lies somewhere else. Again, in these cases, the distractor usually shares an attribute with the target object. This is for instance shown in the right image of Figure 15(b), where the model focuses on the *blue* and *small cube* distractors.

Finally, errors also happen when the target region is not completely placed on the target object. In several cases the automatic calculation of the target region around the center point doesn't include the parts of the object. The model then doesn't actually make an error and focuses on the correct object, but attends only to adjacent regions. These predictions are then evaluated as wrong, even though the model was attending correctly. This can be for example seen in the left and central images of Figure 15(c).




Figure 15: Examples of the *attention reference resolvers*' predictions with a probability mass lower than 60% on the 'Dale' and 'CLEVR color' datasets. The black rectangle shows the cropped section, the model is actually seeing after the image is preprocessed. The green rectangle surrounds the target region that needs to be predicted while the red regions show the actual predictions of the model. The more intense the red, the higher is the probability that the model assigned to this region.

6 Grounding referring expressions in language games

The experiments that are executed using language games have a similar structure as the experiments in the previous chapters, since those provided the basis for the language games. However, every task is solved by two neural networks that communicate through a discrete bottleneck.

The language games in this research have an asymmetric setup. One agent, the sender, is shown some information and needs to generate a message. This message is received by the second agent, the receiver. The receiver needs to parse this message and combine it with the same information that the sender was presented with. The receiver then makes a prediction, which is compared to the ground truth. The game is set up prosocial, which means that both agents receive the same loss based on the receiver’s prediction. All weights of the agents are adapted in the same way.

The vocabulary that the sender can draw from to produce a message is made up of initially arbitrary symbols. The meaning of these symbols is created as soon as the sender uses them in one of the message, and the receiver is able to use it to solve the task successfully. Over time, specific meanings are reinforced and a language emerges. Hereby, the production of the messages is constrained in two ways. First, the size of the vocabulary is varied. A smaller size forces the agents to compress their information more which is a prerequisite for the emergence of a language. With more different words, they can express more information, but it is harder to learn. Different sizes are compared to analyze its effect on the emerged language. Secondly, the maximum possible length of a message is constrained. Again, a shorter message requires more compression, while the longer message allows for more information exchange.

As the experiments before, three different tasks are set up. For the *object identification* task, the agents play discrimination games similar to the setup in (Lazaridou et al., 2017). For the *RE generation* task, the receiver needs to generate a human language referring expression based on the emerged language referring expression by the sender. Since it is possible that the agents simply learn to align these two languages, the agents are tasked to point towards the center coordinates of the target object in the final task, the *reference resolution* task. For all three setups, the sender uses the same setup and only the receiver is switched. By this, differences in the produced referring expression in the message by the sender are only dependent on the receiver’s ability to solve the different tasks. In particular, the impact of the task on the emerged language can be analyzed in more detail.

As discussed in Section 2.3.1, language games are evaluated on the success of communication and the emergence of a language. The testing phase is not necessarily used to test the generalization capabilities of the agents, but rather to extract a sample of the emerged language. It is therefore not as important that the samples in the testing phase are unseen samples. Hence, for both training and testing a certain number of samples are randomly drawn from the complete dataset. In these experiments, the dataset consists of 10.000 scenes in total. To train the agents, 128.000 games are played (using 128.000 randomly drawn samples from the dataset) with a batch size of 32 samples. To retrieve the samples of the emerged language, after the agents are trained, they are frozen and play 2.048 games with randomly drawn samples from the dataset. This yields 2.048 interactions that are used to analyze the emerged language.

Across all experiments, the same restrictions on the vocabulary and the produced messages are compared. First, five different vocabulary sizes $|V|$ are tested: 2, 10, 16, 50 and 100 symbols. Notice that these vocabularies include the *<eos>* token which signals the end of the message. A vocabulary of two symbols therefore consists effectively of only one token that can be learned by the agents. The center of attention lies on the vocabularies with 16 and 50 symbols. The vocabulary with 16 symbols corresponds to the 13 attributes the objects can have and it aligns with human language referring expressions. However, a smaller vocabulary size increases the pressure to converge on meaning, which is why also 10 and 2 symbols are tested. On the other side, the agents might learn to assign one symbol with every combination of attributes

instead of a compositional language. This results in $2 * 3 * 8 = 42$ unique combinations, which corresponds to the vocabulary with 50 symbols. Furthermore, a vocabulary of 100 symbols is used to test the effect of a much bigger bottleneck.

Secondly, also different maximum message lengths are compared: 1, 2, 3, 4 and 6 symbols. Notice that this applies only to the maximum possible length; the agents can choose to use shorter messages. Again, the corresponding length to human referring expressions in English is 3 for the three attributes. However, the agents can be pressured to condense the information more precisely with shorter messages or given less restrictions with longer messages. Vocabulary size and message length play hereby an opposing role in the pressure on condensing information.

All agents are trained using the *Adam* optimizer (Kingma & Ba, 2015). LSTMs are used to produce and parse the message between the agents. Gumbel-Softmax relaxation is applied to train the agents with those discrete messages. Hereby, a temperature of $\tau = 1$ is used which showed the best results in preliminary experiments. All setups are additionally compared to a baseline. In the baseline the sender is "blinded", meaning that the sender is not shown any input but produces random messages. Effectively, the receiver needs to solve the task on their own, by exploiting underlying structures in the shown data and the target data. If a non-baseline model doesn't achieve a better performance than the baseline, the sender didn't communicate any meaningful messages and no language emerged.

6.1 Object identification

Setup

The object identification game is set up as a discrimination game. In a discrimination game, the agents are presented with two or more images, one of these being the target image. The sender needs to communicate this target image to the receiver by discriminating it from the other distractor images. The receiver then needs to decide, based on the message, which of the images is the target image.

The discrimination games in this research have a very similar setup as described in (Lazaridou et al., 2017). The agents in this research resemble their *agnostic sender* as well as their *receiver*. One central difference is the production of the message. The main goal of their language games was the identification of the concept that the shown image was related to. Therefore, the sender communicated only single-symbol messages to the receiver which should describe the concept of the target image. Opposed to that, in this research, the agents are tasked to discriminate objects from each other based on their attributes. It is therefore assumed that the sender communicates these discriminative attributes. For that reason, the sender is allowed to generate sequences as a message where, for instance, each symbol in the sequence might correspond to one attribute.

The data is prepared in the same way as for the single model object identification task in Section 5.1. Bounding boxes of all objects in the scene are extracted and preprocessed to be used for the feature extractors. For datasets with a variable number of objects, the list of bounding boxes is padded with a matrix of zeros to the maximum possible number of objects present in a scene across the dataset. Opposed to the experiments with one neural model, no additional information about the target object’s attributes is provided. Instead, the sender agent is presented with the target object always as the first object, while the distractors are shuffled. The receiver is presented with completely shuffled bounding boxes.

Accordingly, also the models from the single model tasks serve as basis for the object identification task. The sender uses the architecture of the model described in Section 5.2 apart from the final LSTM. Instead, it uses the LSTM with a hidden size h_s included in the *EGG* framework to produce a message. Based on the results from the single model object identifiers, the image embedding size e_s is fixed to 100.

The receiver instead uses the architecture of the single model object identifier, described in Section 5.1. Similarly to the sender, the LSTM of the *EGG* framework with the hidden size h_e is used to encode the sender’s message instead of the one-hot encoded attributes in the single model. The hidden state of the LSTM is projected to the embedding size $e_r = 500$ with a linear layer, based on the results in the previous experiments. As before, the dot product between the embedded message and the encoded image is calculated to let the model point towards the bounding box that is described best by the message. Figure 16 shows how the sender and the receiver of the discriminator are built up.

The experiments are conducted with a learning rate of 2×10^{-4} , the loss is calculated using cross entropy. The following values for the variables are compared:

- h_s : 100, 500, 1000
- h_r : 100, 500, 1000
- $|V|$: 2, 10, 16, 50, 100
- n : 1, 2, 3, 4, 6

The language game is run on the ‘Dale-2’, ‘Dale-5’ and ‘CLEVR color’ datasets. A random guess corresponds




Figure 16: Sender and receiver architectures in the discrimination game


to 50% in the 'Dale-2' dataset, 20% in the 'Dale-5' dataset and 13% in the 'CLEVR color' dataset.

Results


When looking at the results of the experiments, it can be seen that the agents are successfully discriminating the objects across all datasets. Figure 17 gives an overview of the learning process of the agents. Each graph shows the learning curve of a configuration. In the left column, every color stands for configurations with a certain vocabulary size while in the right column a color corresponds to a message length. The rows show the three datasets. First of all, it can be seen that there are many configurations that outperform the baseline across all datasets and the agents are able to solve the task together. However, there are differences in the speed, the performance and the influence of vocabulary size and message length.

The agents can solve the task on 'Dale-2' dataset very fast. Most of the configurations reach accuracies close to the final accuracy already after 2000 to 7000 games. If the agents learn to discriminate the object, they do so during these first games. After they reach these high accuracies, the learning is relatively unstable, and it can drop several times for up to 20% points. However, the agents can recover to the original performance after several thousand games. The more games are played, the more stable the learning gets. The influence of the vocabulary size and message length is not as clear, but smaller vocabulary sizes tend to help the agents to learn faster. On the 'Dale-5' dataset, there is already a wider spread in performances and the learning is slower than on the 'Dale-2' dataset. The agents learn quickly up to an accuracy of around 50%, but for most configurations it then slows down, and the accuracy improves until the cutoff after 128.000 games. When the agents are given a vocabulary size of $|V| = 2$, for several runs, the learning even stops after they reach around 50% accuracy, or it progresses only very slowly. With a vocabulary size of $|V| = 100$, the agents reach the 50% several thousand games after the remaining vocabulary sizes, but the learning goes on afterwards. While there is no visible influence of the message length on the learning speed, all configurations that stay at an accuracy between 45% and 65% have a message length of $n = 1$. Interestingly, there is also one configuration that diverges from the baseline very late, after almost 80.000 games. Finally, on the 'CLEVR color' dataset, a difference in learning speed is again more apparent. Agents tend to learn the fastest with a vocabulary size of $|V| = 2$, the accuracy however almost stagnates after the initial boost to around 40%. When agents are given a vocabulary of size $|V| \in \{10, 16\}$, the initial learning takes place several thousand games later, but therefore it reaches higher final accuracies. As seen already for the 'Dale-5' dataset, most of the configurations converge in the first 20.000 games, but there are several converging much later. An influence of the message length on the speed is again not visible.


Tables 20 to 22 give an overview over the final accuracy scores after 128.000 games of selected configura-




(a) 'Dale-2' dataset with different $|V|$ highlighted




(b) 'Dale-2' dataset with different n highlighted




(c) 'Dale-5' dataset with different $|V|$ highlighted



(d) 'Dale-5' dataset with different n highlighted



(e) 'CLEVR color' dataset with different $|V|$ highlighted



(f) 'CLEVR color' dataset with different n highlighted

Figure 17: Learning curves of all object identification games on each dataset. In the left column, the colors correspond to different vocabulary sizes $|V|$ while in the right column, the colors correspond to different message lengths n . The baseline is marked in black.

tions. For each dataset there are many configurations that outperform the baseline models by a high margin. However, there are still clear differences between the accuracy scores of each dataset.

				Dale-2
h_r	h_s	n	$ V $	Accuracy
100	100	2	10	99,96%
100	1000	2	10	99,96%
1000	100	3	10	99,87%
500	100	3	100	99,83%
100	100	6	50	99,83%
100	500	3	16	99,7%
1000	100	6	16	99,61%
100	100	6	100	99,57%
100	500	1	100	99,52%
100	100	1	50	99,35%
500	100	1	2	99,26%
100	500	1	50	99,26%
500	500	1	100	99,26%
100	500	3	100	99,83%
500	1000	1	16	98%
100	500	1	10	96,61%
100	1000	1	100	99,44%
500	500	6	2	95,92%
100	1000	4	2	94,88%
100	1000	6	10	63,15%
1000	500	2	2	62,98%
baseline				62,72%
100	1000	3	2	61,2%

Table 20: Selected results of the object identification games on the 'Dale-2' dataset with $e_s = 100$ and $e_r = 500$ after 128.000 games

When the agents are tasked to discriminate between the two objects of the 'Dale-2' dataset, they succeed in almost all configurations with an accuracy of over 94%. Selected results are listed in Table 20. In many configurations the accuracy lies above 99%, while just 4 configurations have an accuracy of only 61% to 64%. An antecedent for a low accuracy seems to be a low vocabulary size $|V|$. All experiments with a vocabulary size of only two symbols (including the $\langle \text{eos} \rangle$ symbol) tend to give worse results. Three out of the four results that don't surpass the baseline use a vocabulary size of 2. On the other side, only few configurations with $|V| = 2$ are among the overall best results. When the vocabulary size is increased, the results become better. Especially configurations with $|V| = 10$, $|V| = 16$, $|V| = 50$ and $|V| = 100$ consistently achieve high accuracies. While there are some few exceptions, the results show that the agents tend to perform better, when they can exchange messages with more than one symbol. Hereby, even games with an $n = 6$ perform as well as games with $n = 2$ as seen for example for $|V| = 10$. However, when only one symbol is allowed in the exchange, the accuracy still surpasses the baseline by a big margin and configurations with a high vocabulary of $|V| = 50$ and $|V| = 100$ tend to achieve higher accuracies. Finally, looking at the hidden sizes, no direct effect can be identified and the differences in the results seem to be explained by vocabulary size and message length.

When the agents are presented with the 'Dale-5' dataset, the results are less clear (see Table 21). Again, two groups can be identified: One group of configurations doesn't surpass the baseline of 35% accuracy, while the other group achieves accuracies in between 62% and 94%. For this dataset, the group of successful communication has a wider range of results compared to the 'Dale-2' dataset. Only 16 configurations surpass

				Dale-5
h_r	h_s	n	$ V $	Accuracy
1000	500	3	50	91,75%
100	100	6	10	91,02%
100	100	3	10	90,76%
100	100	4	16	89,76%
100	100	2	10	88,85%
500	1000	1	100	87,11%
1000	1000	6	50	85,07%
500	1000	1	10	84,46%
500	500	1	50	83,29%
100	100	1	10	80,86%
500	100	1	100	76,74%
500	500	4	2	77,78%
1000	1000	3	2	75,78%
100	100	3	2	74%
500	500	1	2	63,41%
baseline				35,07%
500	1000	2	100	34,98%
500	500	3	16	34,77%
500	500	6	2	34,38%
1000	1000	4	2	35,33%
1000	1000	6	100	35,24%

Table 21: Selected results of the object identification games on the 'Dale-5' dataset with $e_s = 100$ and $e_r = 500$ after 128.000 games

90% accuracy, while the majority lies between 80% and 90%. As before, for the hidden sizes, no pattern is visible. However, there is now a clearer influence of the message length n and the vocabulary size $|V|$. First, 15 of the 16 configurations above 90% accuracy are allowed messages with more than 3 symbols. Eight of these configurations even have a message length $n = 6$. Although there are a few configurations with $n = 1$ that perform well, most of them have an accuracy of below 85%. Overall, a longer message tends to help the agents to communicate the correct object. Concerning the vocabulary size, a different pattern can be seen. A vocabulary size of $|V| = \{10, 16, 50\}$ gives the best results. All the configurations with results above 90% use these vocabulary sizes. While a large vocabulary size of $|V| = 100$ can still give good results, the accuracy stays around 80% to 84% most of the time. When given a vocabulary size of only two symbols, the agents still perform far above the baseline. However, compared to the other sizes, the accuracy scores are at the lower end, mainly between 62% and 80%. As expected, when the message length is allowed to be longer, these configurations perform the best.

Finally, the results for the 'CLEVR color' dataset show a similar structure (see Table 22). Two main groups can be identified: Configurations that perform as the baseline with an accuracy of around 23% and configurations that successfully communicate with accuracies of 40% to 73%. Compared to the 'Dale-5' dataset, the highest accuracy is much lower. Furthermore, almost 70% of the configurations are unsuccessful, which is much higher proportion compared to the 'Dale-5' dataset. Still, similar conclusions can be drawn. Different hidden sizes don't seem to have an influence. For this dataset, medium message lengths of $n \in \{2, 3, 4\}$ provide the best results for the agents. However, the agents can still communicate successfully with $n = 1$ and $n = 6$, but the accuracy reaches maximum 64%, and it mainly stays around 50%. As before, the agents can utilize a vocabulary size of $|V| = 10$ and $|V| = 16$ best. Some configurations with $|V| = 2$ and

h_r	h_s	n	$ V $	CLEVR color
				Accuracy
100	1000	3	10	73,65%
100	1000	3	16	73,57%
500	500	4	10	73,57%
100	500	3	16	70,75%
100	1000	4	50	69,31%
1000	500	1	16	62,85%
100	500	1	10	57,12%
1000	500	6	16	54,69%
100	100	4	2	52,95%
1000	500	1	100	52,82%
100	1000	1	100	52,34%
100	500	3	2	51,48%
500	1000	3	16	24,61%
100	1000	3	50	24,48%
1000	1000	4	100	24%
500	1000	1	2	23,96%
1000	100	6	10	23,87%
500	1000	6	50	23,87%
baseline				23,74%
500	500	2	2	22,35%

Table 22: Selected results of the object identification games on the 'CLEVR color' dataset with $e_s = 100$ and $e_r = 500$ after 128.000 games

$|V| = 100$ achieve accuracies of up to 50%, but most lead to an unsuccessful communication. Interesting hereby is that a vocabulary size of $|V| = 2$ requires n to be bigger for better results, while the opposite is true for $|V| = 100$.

Overall these results show that across all datasets successful communication between the agents emerge. The sender is able to encode a description of the target object into the message which the receiver is able to decode. Unsurprisingly, this works the best for simplest dataset 'Dale-2' with only one distractor. With an increasing number of distractors, fewer games are successful, and successful games perform worse. Interestingly, with all vocabulary sizes a language can emerge between the agents. While the vocabulary size $|V| = 2$ usually requires longer messages to succeed, there are some games that also achieve high accuracies with short messages. This fact suggests that the agents don't necessarily rely on the attributes shape, color or size, since they would require more symbols to be encoded. Instead, the agents likely utilize other patterns that are not used in human referring expressions. This will be further analyzed in Section 7.

6.2 Referring expression generation

Setup

In the next step, it is tested if the agents can learn to extract features of the objects together. For this, the same sender as in the previous section is used. Based on the results, h_s is fixed to 500 and e_s to 100. However, the task and by that the receiver’s architecture is adapted in two different ways. In the first setup, the **referring expression generator**, the receiver is tasked to describe the target object with natural language following the *incremental GRE-algorithm* based on the sender’s message (see Figure 18). This follows the approach of the *RE generators* described in Section 5.2. The whole scene is encoded using the *image encoder* submodule, projecting it to the image encoding dimension $e_{ri} = 100$. The sender’s message is decoded with the hidden size $h_r = 500$ and $e_r = 100$, and concatenated with the encoded image. This is then reduced to $LSTM_o = 1500$ dimensions based on the results of the previous experiments, and it is used as the initial state of the captioning LSTM. Tokens are embedded with $LSTM_e = 15$ dimensions. Since the position of the padding as well as the order of the words in the target didn’t have an effect on the results, the usual approach in natural generation task is used: padding tokens are appended and the referring expression is not reversed. During training, the ground truth caption is used as the input to the LSTM using teacher forcing. When presented with test data, the LSTM always produces three tokens, by using its own predicted words as the input for the next step. The loss is calculated using cross entropy.




Figure 18: Simplified architecture of the referring expression generator game

However, this setup could lead to two problems: first, the task is quite complex for both agents to learn, since two language generation steps are involved. This might stop the agents from converging towards a useful language. Secondly, in case a language emerges, it could be aligned with the natural language of the target referring expressions. In other words, the sender might just learn to effectively repeat the target referring expressions without extracting the necessary features themselves. For that reason, in the second setup, the **attribute generator**, the receiver is tasked to predict only the attributes of the target object in the shape of a multi-hot vector (shown in Figure 19). By this, no natural language including its salience order is involved and the complexity of the complete game is reduced. The receiver uses the same way to encode and combine the complete scene and the sender’s message with $e_{ri} = 100$, $h_r = 500$ and $e_r = 100$. This is then passed to a linear layer that produces a vector with 13 dimensions, corresponding to the 2 sizes, 3 shapes, and 8 colors. The loss is then calculated using binary cross entropy.

The experiments for both setups are conducted with a learning rate of 2×10^{-4} . As in the previous section, the following values for the variables are compared:

- $|V|$: 2, 10, 16, 50, 100




Figure 19: Simplified architecture of the attribute generator game

- n : 1, 2, 3, 4, 6

Since the agents are trained to describe the target object discriminatively based on the described GRE-algorithm, they are trained on the 'Dale-2', 'Dale-5' and 'CLEVR color' dataset. The 'Dale-5' and the 'CLEVR color' should be again much harder to learn, since there are more objects that the agents need to discriminate the target object from. The same metrics as in the Section 5.2 are used to evaluate the results for the first setup. When predicting multi-hot vectors, an overall **accuracy** is reported that reflects if all attributes were predicted correctly. Additionally, the accuracy for each attribute is calculated separately to show which attributes give bigger challenges for the models.

Results

As in the previous section, Figure 20 shows the learning curves of all configurations of the **referring expression generator**. The baselines are shown in black. Hereby, the sender is sending random messages, so that the receiver needs to solve the task on their own. In all configurations that don't pass this baseline, no meaningful messages are exchanged, and no language emerged. If configurations perform better on the other hand, it means that the agents learned to encode some meaning in their messages. While for both 'Dale' datasets several configuration diverge from the baseline, in other words, learning takes place, all learning curves align with the baseline for the 'CLEVR color' dataset and are therefore left out. Looking at the learning curves for the 'Dale-2' dataset, most of the configurations can decrease the loss compared to the baseline faster on to a bigger extend. Fast learning takes place in the first 10.000 to 15.000 games, and it decelerates afterwards. Also on this task, there are several configurations that converge much later than the initial fast decrease of the loss. Most of these configurations diverge from the baseline between 15.000 to 35.000 games, but some even need up to 70.000 games. While the vocabulary size now seems to have a lower impact on the learning speed, configurations that converge later tend to have a message length of $n = 6$. For the 'Dale-2' dataset a clear distinction between configurations that align with the baseline and configurations that diverge from the baseline is visible. For the 'Dale-5' dataset, however, all learning curves are closer together and success of learning is not instantly apparent. Nonetheless, several configurations (with low- to medium-sized vocabularies) start to converge earlier than the baseline. Configurations with $|V| = 2$ start to do so already after 5.000 games, with $|V| \in \{10, 16\}$ after around 7.000 games and with $|V| = 50$ after around 12.000 games. With $|V| = 100$, almost no configuration diverges from the baseline. The message length doesn't seem to have an impact. Interestingly, there are several configurations that perform worse than the baseline, and communication between the agents seems to hinder the learning. This happens across all vocabulary sizes and message lengths.




Figure 20: Learning curves of all referring expression generation games on the 'Dale' datasets. On the 'CLEVR color' dataset, the learning curves don't diverge from the baseline and are therefore left out. In the left column, the colors correspond to different vocabulary sizes $|V|$ while in the right column, the colors correspond to different message lengths n . The baseline is marked in black.

Table 23 shows the *overall accuracies*, *F1-scores* and *non-target accuracies* across all datasets for different message lengths n and vocabulary sizes $|V|$. When first having a look at the results of the 'Dale-2' dataset, it can be seen that the baseline already identifies correct referring expressions in 41,8% of the samples. However, almost all other configurations perform much better. This shows that the agents consistently learn languages to solve the tasks. Still, differences in how well the agents perform can be identified. While a small vocabulary with $|V| = 2$ mostly beats the baseline, the emerged language only lets the agents generate the correct referring expression in a maximum of around 72% of the samples. The similar result is visible for a bigger vocabulary size of $|V| = 50$ which has the highest accuracy at around 74%. A vocabulary size of $|V| = 100$ performs consistently slightly better, with accuracies of around 73% to 75%. Interestingly, when the agents are allowed to exchange messages with a message length of $n = 6$, the accuracy peaks at almost 81%. Additionally, also the *F1-score* almost reaches 70% whereas it usually stayed around 50% to 60% in the previously discussed configuration. The *F1-score* evaluates each word in the referring expression separately instead of the binary *overall accuracy* for the complete referring expression. A small increase of the accuracy accompanied by a large increase of the F1-score indicates that the agents learned to encode an additional attribute, with the larger vocabulary and longer messages. Finally, vocabulary sizes of $|V| = 10$

n	$ V $	Dale-2			Dale-5			CLEVR color		
		Acc.	F1	NT	Acc.	F1	NT	Acc.	F1	NT
baseline		41,8	42,36	37,11	62,66	81,16	18,36	13,52	33,08	34,53
1	2	70,49	54,73	7,29	70,16	85,06	13,06	11,68	32,25	34,03
1	10	78,26	63,33	3,56	68,97	85,01	10,85	12,72	32,77	33,85
1	16	74,18	52,21	5,38	71,57	86,87	10,72	13,19	33,64	33,33
1	50	70,83	43,56	4,21	65,23	83,11	12,54	11,81	33,14	34,72
1	100	73,18	52,14	3,86	60,94	80,85	20,36	13,67	33,71	33,64
2	2	72,31	50,42	5,52	66,2	83,39	14,42	13,32	33,62	32,73
2	10	75,22	58,4	3,99	73,22	87,68	9,03	12,37	33,3	34,11
2	16	81,64	73,66	2,86	73,44	88,21	8,85	12,98	33,94	34,24
2	50	74,39	48,53	3,17	75,35	88,77	8,07	14,19	33,04	33,46
2	100	74,09	54,88	3,65	54,56	76,95	22,57	13,28	32,8	33,38
3	2	71,03	50,76	4,62	65,18	82,68	14,23	12,76	33,58	33,64
3	10	76,91	59,42	2,6	71,66	87,14	9,9	12,54	32,75	33,85
3	16	79,95	67,55	3,17	50,13	73,24	24,22	12,93	33,79	34,46
3	50	62,93	48,03	16,58	76,09	88,5	9,2	13,67	33,73	34,29
3	100	75,74	57,51	2,43	69,7	86,14	9,38	13,02	33,64	34,2
4	2	41,23	42,53	35,33	63,93	82,34	15,3	12,2	33,25	33,64
4	10	78,99	66,4	2,08	73,22	88,01	10,85	12,5	33,55	33,16
4	16	80,08	70,48	3,47	69,4	86,09	10,63	11,72	33,1	34,03
4	50	75,48	54,44	3,34	71,35	86,61	10,68	11,81	33,18	34,33
4	100	74,78	57,09	3,86	59,2	80,14	20,57	12,67	32,3	34,55
6	2	72,87	51,44	2,78	60,82	80,42	17,07	13,45	33,73	33,64
6	10	73,61	48,73	2,82	32,64	58,42	33,12	11,89	33,15	35,03
6	16	73,52	49,67	2,43	49,39	73,19	23,78	13,06	32,31	34,64
6	50	44,31	45,07	33,29	78,82	90,22	7,29	12,72	33,29	32,99
6	100	80,95	69,88	3,34	62,2	80,62	19,88	14,24	32,36	32,94

Table 23: Overall accuracies (Acc.), F1-score (F1) and non-target accuracies (NT) in % of the RE generator after 128.000 games: n are different maximum message lengths and $|V|$ are different vocabulary sizes.

and $|V| = 16$ consistently perform the best with accuracies of 74% to 81%. However, a difference in the *F1-score* is visible: configurations with $|V| = 16$ reach 67,55% to 73,66% with message lengths $n \in [2, 4]$, where $|V| = 10$ only reaches an F1-score of 66,4% with $n = 4$ and otherwise performs worse. This indicates as before that the agents were able to encode more attributes with the larger vocabulary.

The results look different when the agents are trained to generate referring expressions for the 'Dale-5' dataset. First, the baseline, in other words the receiver on their own, performs much better. It already produces the whole correct referring expressions in 62,66% of the samples, and it achieves an *F1-score* of 81,36%. However, the *non-target accuracy* is quite high with producing correct referring expressions for a distractor in 18,36% of the cases. This allows two conclusions: on the one side, the baseline can pretty successfully extract a bias from the images. Since there are multiple distractors in the image, the probability that they share attributes that are relevant for discriminating the target is higher. The model therefore can learn to generate *shapes* and *colors* that appear more often correctly, which leads to a higher *F1-score*. On the other side, the larger number of distractors makes it possible for the model to single out the target from the image alone, as it needs to be uniquely identifiable. If there are for instance two large red cubes, two blue spheres, but only one green sphere, the target needs to be the green sphere, and no additional textual information is needed. The model can exploit this bias in the dataset, which leads to a higher accuracy.

However, distractors might also be unique in the scene, so the model won't be able to consistently single out the correct unique object, which leads to a higher *non-target accuracy*. Messages by a sender would need to solve these problems.

Interestingly, many configurations with a sender perform as the baseline or even worse. Only 16 out of 30 configurations beat the baseline, some only by a few percent points. The best configuration however, has an accuracy of 78,82%, an *F1-score* of 90,22% and a *non-target accuracy* of 7,29% which is 16% points, 9% points and 11% points better than the baseline respectively. The models tend to perform better with a message length of $n > 1$ and $n < 6$, and consistently the best across all vocabulary sizes with $n = 2$. However, there are good results for all n , with the best configuration utilizing $n = 6$. Looking at the vocabulary sizes, configurations with $|V| = 2$ beat the baseline only slightly, except with $n = 1$. When the agents use a vocabulary with $|V| = 10$, they beat the baseline consistently and push the *non-target accuracy* close to and below 10%. However, when longer messages are allowed with $n = 6$, the accuracy drops to only 32,64%. The reason might be that the agents learned to exchange messages about patterns that are only present in the training samples and that were not transferrable to unseen samples. The learned language was therefore not general enough. A similar result is visible for $|V| = 16$, but the model additionally performs badly with $n = 3$. Using a vocabulary with $|V| = 50$, the models can generate the best referring expressions. Almost all configurations have an accuracy of above 70%, three of them even above 75%. Having more symbols to describe the objects apparently helps the agents to learn a useful language. However, when the bottleneck is too big, the agents are not able to encode useful messages as seen with $|V| = 100$. The agents are only able to beat the baseline with $n = 3$; all other configurations perform equal or worse.

Finally, the results of the experiments with the 'CLEVR color' dataset show that the agents are not able to learn a language to describe the target objects. The baseline corresponds to a random guess of the color while the other attributes are identified correctly (since they are identical for target and distractor in the complete scene). No configuration beats this baseline which shows that no meaningful language emerges independently of vocabulary size $|V|$ and message length n .

		small	large	size	cube	cylinder	sphere	shape	<pad>
Dale-2	Precision	45,15	37,96	41,56	99,25	99,65	99,21	99,37	94,58
	Recall	16,69	6,23	11,46	99,59	98,55	99,84	99,33	99,3
Dale-5	Precision	80,9	89,63	85,27	97,67	97,7	95,21	96,86	88,1
	Recall	76,99	69,14	73,07	96,58	97,22	96,72	96,84	96,1
CLEVR color	Precision	-	-	-	100	100	100	100	100
	Recall	-	-	-	100	100	100	100	100

Table 24: Precision and Recall in % for <pad>, size and shape tokens for the configurations with the highest accuracy in Table 23. The columns **shape** and **size** show the average across all tokens of the respective attribute.

Tables 24 and 25 show the precision and recall divided by attributes and tokens. The results have a similar general pattern to the single model experiments in Section 5.2. For the 'Dale' dataset, the *shape* is identified well while the agents struggle more with the *color* and the most with the *size*. The agents identify the *shape* and the *size* perfectly on the 'CLEVR color' dataset, but they only predict few *colors*.

Looking at the *shape*, the agents perform almost perfectly with the 'Dale-2' dataset. The precision and recall are slightly lower with the 'Dale-5' dataset, and the agents predict the *sphere* too often, while predicting the *cube* too few. The difference however lies only around 1%.

Interestingly, the agents can predict the *color* the best, when presented with the 'Dale-5' dataset. The preci-

		blue	brown	cyan	gray	green	purple	red	yellow	color
Dale-2	Precision	66	79,35	71,14	86,11	70,48	70,74	67,95	76,26	73,5
	Recall	88,96	63,43	91,9	46,02	69,29	65,99	75,35	79,54	72,56
Dale-5	Precision	92,61	93,3	94,73	91,12	93,66	88,71	88,04	89,79	91,5
	Recall	89,09	86,31	91,08	89,08	83,23	92,16	93,05	88,77	89,1
CLEVR color	Precision	0	0	0	0	12,91	13,9	0	0	3,35
	Recall	0	0	0	0	36,25	69,85	0	0	13,26


Table 25: Precision and Recall in % for color tokens for the configurations with the highest accuracy in Table 23. The column **color** shows the average across all colors.

sion and recall lie around 90%, while for the 'Dale-2' dataset they lie only around 73%. However, there is a bigger difference across the colors. Some colors are predicted more often (e.g. purple and red for 'Dale-5', and yellow red, cyan and blue for 'Dale-2') than others (e.g. brown and green for 'Dale-5', and purple, gray and brown for 'Dale-2'). As can be seen, the colors are not consistent and "difficult" or "easy" colors can't be identified. Additionally, these colors also differ across several runs of the same configurations and datasets. The differences between the two 'Dale' datasets might be explainable by the number of scenes in which the color is part of the referring expression. As seen in Table 23, the *overall accuracy* is higher for the 'Dale-2' dataset, even though the prediction of the *color* attribute is worse. The reason for this is that many referring expressions in the 'Dale-2' dataset only rely on the *shape* and no *color* is needed. The agents therefore can perform well even though predictions of the *color* are wrong. On the other side, the *color* is a central part of almost all referring expressions in the 'Dale-5' dataset and the agents are pushed to learn this attribute more intensely.


Since the single model in Section 5.2 already struggled with predicting the *color* on the 'CLEVR color' dataset, it is no surprise that it performs badly in the more complex setup of language games. Hereby, the agents are not able to communicate anything and the receiver only generates two colors (green and purple) for all shown samples. This results in a random guess of one out of the eight *colors*, explaining the *overall accuracy* of $\frac{1}{8} = 12,5\%$.

The final attribute is the *size*. While the agents easily learn that the *size* is never part of the referring expression for the 'CLEVR color' dataset, they struggle with the 'Dale' datasets. As in Section 5.2, the agents again struggle to predict the correct length of the referring expression. Especially, the agents predict too short referring expressions as the precision of the *<pad>* token is lower than its recall. This is mostly due to the *size* attribute, since a large difference of the precision and recall is visible. As for the *color*, the agents perform better on the 'Dale-5' dataset. The reason might be the same. The *size* attribute is more often needed to discriminate the target object and appears therefore in more samples. Therefore, it is more central in the referring expressions. Similarly to the *color* attribute, there are differences between the single tokens. However, these are not constant across configurations, datasets and runs, and no "difficult" token can be identified.


Finally, Figure 21 shows the learning curves for the **attribute generator**. The measure of learning is hereby the accuracy of the *shape*. The reason for this is that the *size* is not learned at all, while also the *color* diverges only very slightly from baseline. Communication is therefore impacting mostly the *shape*, and the influence of the vocabulary size and message length is shown in the figures. On the 'Dale-2' dataset, configuration that learn the *shape* quickly tend to use smaller vocabularies. However, there are configurations with $|V| \in \{16, 10\}$ that need 15.000 to 20.000 games, but they outperform the configurations which learned faster. A similar result is visible for the message length where shorter messages help the agents to learn faster while longer messages need more games. Looking at the 'Dale-5' dataset, more configurations




(a) 'Dale-2' dataset with different $|V|$ highlighted



(b) 'Dale-2' dataset with different n highlighted



(c) 'Dale-5' dataset with different $|V|$ highlighted



(d) 'Dale-5' dataset with different n highlighted

Figure 21: Learning curves of all attribute-predictor games on the 'Dale' datasets. The graphs show the accuracy of the *shape*, since it highlights the learning effect best. In the left column, the colors correspond to different vocabulary sizes $|V|$ while in the right column, the colors correspond to different message lengths n . The baseline is marked in black.

are able to learn the *shape*. Most of the configurations again outperform the baseline already after 5.000 to 10.000 games, but the learning decelerates shortly after. Interestingly, most of the configurations reach a final accuracy of the *shape* after 128.000 games of 85% to 97%. However, the learning progress is different across the configurations. Several configurations progress quickly only to around 65% with a following relatively steep learning over the remaining 120.000 games. A second group of configurations has an initial learning to around 80% and then progresses slower. One configuration even reaches over 95% after 15.000 games, but then stagnates until the cutoff. Looking at the vocabulary size and message length, no consistent influence is visible. However, agents seem to learn slower with $|V| \in \{50, 100\}$, while $|V| \in \{2, 16\}$ tends to increase the speed. Opposed, a short message length tends to decrease the speed.

Table 26 shows the results for the games in which the receiver predicts a multi-hot vector of the attributes. In the results for the baseline, it can be seen that the receiver can already predict the *shape* and *color* very well: 88,91% and 92% respectively on the 'Dale-2' dataset, 80,78% and 89,38% respectively on the 'Dale-5' dataset, and 100% and 90,78% respectively on the 'CLEVR color' dataset. The *size* however corresponds to a random guess on the 'Dale' dataset and only achieves 76,72% on the 'CLEVR color' dataset. This shows that the receiver can already identify attributes of the target object on their own and discriminate it from

n	$ V $	Dale-2			Dale-5			CLEVR color		
		A _{shape}	A _{color}	A _{size}	A _{shape}	A _{color}	A _{size}	A _{shape}	A _{color}	A _{size}
baseline		88,91	92,03	50,55	80,78	89,38	49,92	100	90,78	76,72
1	2	89,69	93,68	52,04	88,09	90,12	49,74	100	87,37	76,56
1	10	96,31	94,21	52,78	90,6	90,15	49,74	100	91,32	76,52
1	16	94,97	92,8	52,78	91,97	93,45	49,74	100	91,03	76,52
1	50	90,1	91,58	52,78	94,66	93,39	49,74	100	89,41	76,52
1	100	90,41	92,66	52,78	83,03	90,23	49,74	100	86,72	76,52
2	2	92,45	92,45	52,04	88,72	94,38	49,74	100	88,89	76,56
2	10	96,09	94,44	52,78	91,54	90,71	49,74	100	89,54	76,52
2	16	90,58	92,66	52,78	97,18	94,14	49,74	100	86,98	76,52
2	50	89,28	92,45	52,78	92,01	93,01	49,74	100	86,5	76,52
2	100	98,91	92,97	52,78	92,66	92,49	49,74	100	86,68	76,52
3	2	90,97	93,32	52,04	87,88	92,53	49,74	100	90,58	76,56
3	10	97,01	94,79	52,78	94,4	92,8	49,74	100	91,17	76,52
3	16	95,36	93,1	52,78	86,72	91,88	49,74	100	88,06	76,52
3	50	90,93	90,84	52,78	94,92	94,18	49,74	100	88,59	76,52
3	100	89,37	90,76	52,78	94,1	92,8	49,74	100	91,84	76,52
4	2	94,86	92,11	52,04	88,56	93,86	49,74	100	87,11	76,56
4	10	90,58	92,75	52,78	95,05	93,71	49,74	100	89,89	76,52
4	16	98,57	94,14	52,78	96,14	95,23	49,74	100	88,06	76,52
4	50	95,66	93,32	52,78	91,01	90,45	49,74	100	88,85	76,52
4	100	89,41	93,58	52,78	94,66	93,19	49,74	100	86,98	76,52
6	2	93,39	92,94	52,04	82,18	92,16	49,74	100	90,05	76,56
6	10	98,78	94,23	52,78	96,79	92,75	49,74	100	87,67	76,52
6	16	96,96	91,32	52,78	95,57	93,75	49,74	100	89,37	76,52
6	50	88,28	91,45	52,78	91,71	86,24	49,74	100	88,32	76,52
6	100	94,92	92,45	52,78	95,3	93,62	49,74	100	89,19	76,52

Table 26: Accuracies for each attribute in % of the attribute predictor after 128.000 games: n are different maximum message lengths and $|V|$ are different vocabulary sizes.

the distractors. However, the size still seems to be an attribute which is difficult to extract from the visual scene. The increase in performance compared to the generation of referring expression can be explained by two reasons: first, the complexity of the receiver is greatly reduced. When only predicting multi-hot vectors, much fewer layers and weights that need to be trained are involved, and hence the models can learn the given task. Secondly, the complexity of the task is reduced as well. The generation of referring expressions not only includes the learning of the tokens (and their embeddings), but also their order in the referring expression and their salience for the incremental algorithm. Using multi-hot vectors, both order and salience are irrelevant and only the attributes themselves are needed to be learned. The goal of these experiments is now to see if the information of the sender improves the predictions of the receiver.

As can be seen in the table, the improvement is dependent on the attributes. When the agents are trained on the 'Dale-2' dataset, almost all configurations improve the prediction of the shape. While 11 out of 30 configurations only improve by a maximum of 2% points, most can predict the *shape* much better, with an accuracy of up to 98,91%. A pattern based on the vocabulary size $|V|$ and message length n is however difficult to identify. A smaller vocabulary size of $|V| = 10$ generally fares well, but also a large vocabulary size of $|V| = 100$ can help to predict the shape both with short messages ($n = 2$) and long messages ($n = 6$). Opposed to the *shape*, the prediction of the *color* can only be improved by a small margin of a

maximum of 2,7% points. Most of the configurations produce the same or slightly worse results than the baseline. Again, a vocabulary of $|V| = 10$ seems to help the most. Interestingly, when the agents can only use one token to encode their message ($|V| = 2$), an improvement of predictions of the *shape* comes at the expense of the accuracy of the *color* and vice versa. This indicates that the sender doesn't have enough space to communicate both attributes to the receiver. Looking at the *size*, a constant improvement of 2% points across all configurations can be seen. The final accuracy however still lies slightly above a random guess.

The results are similar when the agents need to describe the 'Dale-5' dataset. The baseline accuracies of the *shape* and *color* are lower, but they can be improved to similar peaks as for the 'Dale-2' dataset. The highest accuracy for the *shape* lies at 97,18%, while it lies at 95,23% for the *color*. This indicates that the larger number of distractors makes it difficult to focus on the correct object, and instead it describes distractors when the receiver is on their own. But when the sender can communicate the correct object, the receiver describes the attributes as well as it does with fewer distractors. As before, the predictions of the *size* correspond to a random guess.

Using the 'CLEVR color' dataset, almost no improvements can be seen. The predictions of the *shape* stay at 100% accuracy, while the predictions of the *color* get slightly worse for most configurations and if they improve they only improve by maximum 1% point. The predictions of the *size* stay the same. The fact that the sender has a smaller influence on the 'CLEVR color' dataset than on the 'Dale' dataset is surprising since the sender would need to communicate only the *color* instead of additionally the *shape* (and *size*). A reason why this happens might be the larger number of distractors. This number might hinder the receiver to converge and understand the task, by connecting the multi-hot vector to the colors of the target object. While for the 'Dale' datasets the receiver has a choice between only 2 to 5 objects, they need to decide between up to 10 objects on the 'CLEVR color' dataset. That might confuse the model about where to focus on and subsequently how to connect it to the one-hot vector. Future experiments with a similar dataset including fewer distractors would be needed to verify this hypothesis.

Concluding, these experiments show that the models are able to extract and communicate information about the *shape* and *color* from the images when few objects are present. When the agents are forced to generate referring expressions which are more complex in their structure, they produce perfect results less frequently. However, the communication is successful very often as it helps the receiver to identify the correct attributes and referring expression.

6.3 Reference resolution

Setup

In the final experiments, the agents are tasked to produce and understand referring expressions only based on the implicit human knowledge present in the scenes, as for example the attributes of the objects. Opposed to the previous experiments, explicit human language information as human referring expressions or one-hot encoded attributes are avoided. By this, the agents can't just reuse these human referring expressions, but they need to learn to generate them themselves during the language games only based on the visual input. This is done similarly to the single model reference resolution task, described in Section 5.3. As before, the sender has the same architecture as in the previous language games, encoding the bounding boxes of all objects.

The receiver is tasked to solve two tasks. First, in the **coordinate reference resolver**, the agents are tasked to predict the center coordinates of the target object (see Figure 22). The receiver is the same in both setups and is based on the *reference resolver* + referring expressions, described in Section 5.3. Again, instead of the included LSTM, the receiver uses the *EGG* LSTM with the hidden size $h_r = 500$ and $e_r = 100$ to encode the message. The dimensions of the coordinate predictor are fixed to $c = 2048$, based on the previous results. The euclidean distance between the resulting prediction of the center point and the true center of the target object is calculated and the weights of both agents are adapted accordingly.




Figure 22: Simplified architecture of the coordinate predictor game

Secondly, in the **attention reference resolver**, the agents learn to point towards regions in the image, which is based on the *attention reference resolver* described in Section 5.3. As before, the LSTM is replaced with the *EGG* LSTM to parse the sender's message with the hidden size $h_r = 500$ and $e_r = 100$. The dot product is calculated between each encoded region of the image and the encoded message, and the *softmax* function is applied subsequently. Figure 23 shows the architecture. The loss is calculated using *binary cross entropy* between the predictions and ground truth regions.

The experiments are conducted with the following hyperparameters: a learning rate of 2×10^{-4} , a temperature for the Gumbel-Softmax relaxation of 1 and *Adam* (Kingma & Ba, 2015) as optimizer. The following values for the variables are compared:

- $|V|$: 2, 10, 16, 50, 100




Figure 23: Simplified architecture of the attention predictor game


- n : 1, 2, 3, 4, 6

As in Section 5.3, the agents are trained on the 'Dale-2', 'Dale-5' and 'CLEVR color' datasets to test if the agents are able to first communicate a target object and secondly describe the target object discriminatively with a small vocabulary. The same metrics are used to evaluate the results as described in 5.3.


Results

Figure 24 shows the learning curves for the **coordinate reference resolver**. As visible, all configurations perform exactly as the baselines across all datasets. The baselines show the predictions of the receiver without information from the sender, and they correspond to the structural bias in the dataset. This shows that the agents don't communicate successfully in any of the configurations to solve the task by predicting correct coordinates. Table 27 shows the final results after 128.000 games on different datasets. When looking at how the agents fare with each dataset, not much general improvement can be seen. Most of the configurations don't beat the baseline, independently of the shown dataset. If they do, they can improve the mean distance of the predicted coordinates to the center of the target object only by 2 to 4 pixels. In other words, the guesses are still not consistently precise on the target objects and the agents instead learn to point towards the center of the scene, as the single models in Section 5.2. However, an influence on the accuracy can be identified. The accuracy evaluates how many of the predictions are on the target object. An increase in the accuracy with a stable mean distance shows a behavior where the agents make more correct predictions on the target objects, while the wrong predictions are further away from the target object. As a conclusion, this can mean that the agents' predictions, both correct and incorrect are more confident. This seems to happen on the 'Dale-2' dataset. The mean distance is not improved, but the accuracy reaches in some configurations up to 46,27%. This is an increase of around 13% compared to the baseline. While this value is still lower than a random guess between the objects in the scene, it shows, that some information is exchanged between the agents. The meaning of the messages however doesn't seem to correspond to any attribute or object to consistently solve the task.


Looking at the results on the 'Dale-5' dataset, no improvements for the mean distance nor the accuracy can be seen when a sender is involved. However, while the loss stays again constant, the accuracy drops lower in many configurations, up to 7% points to an accuracy of 23,26%. Again, this is an indicator that messages



(a) 'Dale-2' dataset



(b) 'Dale-5' dataset



(c) 'CLEVR color' dataset

Figure 24: Learning curves of all coordinate reference resolving games on each dataset. As almost no games beat the baseline, $|V|$ and n are not highlighted separately. The baseline is marked in black.

are transferred and interpreted by the receiver. The receiver seems to use this information to focus more on the objects. Since there are more distractors present in the 'Dale-5' dataset, the receiver more likely chooses one of those, as again no discriminating information about the target object seems to be transferred.

Lastly, the similar pattern on the mean distance is also visible for the 'CLEVR color' dataset. The accuracy of the baseline is already lower to begin with, and a sender can lift this score in almost all configurations. But as for the other datasets, the final accuracy is still low, and it reaches a maximum of only 25%. The greater number of distractors seems to raise the complexity of the task even more.


These numbers align with the results of the single model, discussed in Section 5.2. Hereby, the single model was only able to predict correct coordinates for the 'Dale-2' dataset with one distractor. The higher complexity for the agents that includes more layers in the model as well as the discrete bottleneck raises the bar of the task too high to be solved in this configuration. The second setup in this section, the **attention reference resolver**, tries to reduce the complexity, by not predicting precise geometric locations, but instead attending to larger areas. The learning curves are shown in Figure 25.

As expected, the task is solved better by the agents, and they communicate successfully across all datasets.


n	$ V $	Dale-2		Dale-5		CLEVR color	
		loss	Acc.	loss	Acc.	loss	Acc.
baseline		34,49	34,3%	38,13	30,31%	42,72	18,28%
1	2	34,91	34,81%	40,61	25,48%	39,13	25%
1	10	35,31	40,15%	38,73	28,12%	44,19	20,53%
1	16	35,4	42,93%	39,58	26,17%	39,64	24,18%
1	50	32,64	42,01%	38,99	28,52%	42,61	20,79%
1	100	36,73	31,21%	40,25	24,91%	41,5	21,44%
2	2	33,76	40,67%	35,86	31,73%	41,79	22,14%
2	10	31,37	43,27%	37,23	30,34%	42,53	19,75%
2	16	31,19	46,27%	39,38	28,21%	41,74	22,7%
2	50	33,66	39,28%	39,62	25,35%	45,63	17,93%
2	100	35,1	34,81%	39,86	27,3%	45,45	19,05%
3	2	32,99	41,15%	37,76	30,99%	46,45	20,92%
3	10	33,74	38,89%	40,71	26,48%	44,53	19,01%
3	16	34,18	38,98%	38,52	30,03%	41,22	21,53%
3	50	34,38	38,93%	39,52	26,74%	38,4	24,87%
3	100	33,16	40,19%	39,75	27,78%	41,29	21,83%
4	2	33,48	40,36%	38,28	30,9%	42,53	22,4%
4	10	35,01	39,97%	40,88	26,39%	42,33	20,44%
4	16	35,59	35,59%	37,91	31,86%	41,9	20,27%
4	50	34,99	36,68%	40,89	23,26%	43,77	18,36%
4	100	35,46	37,46%	38,53	29,08%	40,6	21,22%
6	2	34,97	37,28%	39,52	29,69%	40,53	24,7%
6	10	32,39	43,53%	38,61	28,26%	40,84	21,74%
6	16	34,87	34,38%	39,03	26,82%	40,34	23,31%
6	50	33,85	37,07%	39,39	27,17%	40,8	22,09%
6	100	34,62	40,02%	39,46	25,48%	42,53	18,4%

Table 27: Mean distance (loss) in pixels and accuracy in % of the coordinate reference resolver after 128.000 games: n are different maximum message lengths and $|V|$ are different vocabulary sizes.


Compared to the experiments in the previous sections, the learning is still generally slower, and the configurations diverge from the baseline overall later. However, when the agents start to learn to communicate, the probability is boosted instantly to a higher level, where it again learns at a slower speed parallel to the baseline. On the 'Dale-2' dataset, the boost is around 40% points. Most of the learning takes place in the first 40.000 games, but there are also two configurations that increase the performance very late after 70.000 and 105.000 games respectively. Hereby, agents tend to learn faster the smaller their vocabulary size is. The same applies as well to the message length. Using the 'Dale-5' dataset, the probability masses are boosted around 30% points when the agents start to communicate successfully. Compared to the 'Dale-2' dataset, fewer configurations start to converge, while most achieve performances close to the baseline. The smaller number of learning curves makes the analysis more difficult, but the same trend about the vocabulary size and the message length is still visible. Interestingly, only one configuration with $|V| = 2$ beats the baseline, but behaves relatively unstable over the remaining training. On the other hand no configuration with $|V| = 100$ is successful. This indicates that one symbol is too few to encode all meaning, but too many symbols are too difficult to learn. This hypothesis is amplified by the results on the 'CLEVR color' dataset. Only two configurations beat the baseline, both with a medium-sized vocabulary size and message length. In both cases, the learning takes place relatively late, after 15.000 and 30.000 games respectively.




(a) 'Dale-2' dataset with different $|V|$ highlighted




(b) 'Dale-2' dataset with different n highlighted




(c) 'Dale-5' dataset with different $|V|$ highlighted



(d) 'Dale-5' dataset with different n highlighted



(e) 'CLEVR color' dataset with different $|V|$ highlighted



(f) 'CLEVR color' dataset with different n highlighted

Figure 25: Learning curves of all attention reference resolver games on each dataset. In the left column, the colors correspond to different vocabulary sizes $|V|$ while in the right column, the colors correspond to different message lengths n . The baseline is marked in black.

The final probability masses after 128.000 games are summed up in Table 28. Opposed to the *coordinate reference resolver*, the baseline can already find and attend to the correct regions in many cases. The proba-

n	$ V $	Dale-2	Dale-5	CLEVR color
		Probability mass	Probability mass	Probability mass
baseline		62,16%	49,61%	41,68%
1	2	93,3%	65,36%	39,22%
1	10	93,85%	46,97%	40,1%
1	16	92,06%	76,68%	36,43%
1	50	94%	76,43%	39,97%
1	100	94,03%	54,14%	40,27%
2	2	92,27%	52,15%	33,64%
2	10	96,16%	80,26%	36,53%
2	16	95,84%	84,03%	39,65%
2	50	93,78%	52,24%	39,56%
2	100	92,43%	53,23%	37,68%
3	2	94,52%	51,97%	37,09%
3	10	94,9%	53,47%	38,24%
3	16	94,59%	81,46%	67,88%
3	50	93,88%	79,65%	40,36%
3	100	95,25%	48,52%	42,55%
4	2	89,15%	51,98%	39,68%
4	10	96,08%	48,03%	64,31%
4	16	94,14%	49,81%	40,84%
4	50	96,24%	48,79%	43,61%
4	100	95,55%	49,65%	42,85%
6	2	59,68%	53,57%	38,43%
6	10	63,46%	82,12%	40,11%
6	16	95,86%	50,71%	40,61%
6	50	91,27%	52,55%	40,21%
6	100	60,27%	46,92%	41,98%

Table 28: Probability masses of the attention reference resolver after 128.000 games: n are different maximum message lengths and $|V|$ are different vocabulary sizes.

bility mass, that is the sum of the predicted probabilities of all regions of the target object, is higher than a uniform distribution ($\approx 4,6\%$) and a random guess of an object. It reaches 62,16% on the 'Dale-2' dataset, 49,61% on the 'Dale-5' dataset and 41,68% on the 'CLEVR color' dataset. Interestingly, including a sender in the setup can improve the result for all dataset. Looking at the 'Dale-2' dataset, almost all configurations beat the baseline and achieve performances of over 90%, the best configurations reach even 96%. Only three configurations stay on the level of the baseline. When comparing the results, mostly the message length n seems to have an influence on the performance. While configurations with $n = 6$ can perform well, this is not constant. All three configurations that don't pass the baseline are allowed to produce message with $n = 6$. $n \in \{3, 4\}$ seem to help the agents the most to perform consistently well, but the difference to configurations with $n \in \{1, 2\}$ is very small. In both cases, the target object is unambiguously identified. The small number of experiments doesn't allow definite conclusions on the influence of the vocabulary size $|V|$, though $|V| = 2$ performs slightly worse than the remaining vocabulary sizes. A correlation between n and $|V|$ is not identifiable.

On the 'Dale-5' dataset, the agents already have bigger problems to beat the baseline. Only 8 out of 30 configuration perform better and reach probability masses around 76% to 84%. However, the increase compared to the baseline is as high as on the 'Dale-2' dataset, with around 30% points. Smaller message

lengths ($n \in \{1, 2, 3\}$) as well as a medium-sized vocabulary ($|V| \in \{10, 16, 50\}$) tend to help the agents more, to solve the task successfully. As before, no correlation is visible with the few successful games. That the agents struggle more with the 'Dale-5' dataset is not surprising. First, the larger number of distractors makes it more difficult for the receiver to focus, as can be seen already in the baseline performances. Additionally, in case the sender communicates the attributes of the target object to the receiver, more information needs to be encoded to uniquely describe the target object. This is naturally more complex to learn for the agents. Finally, since more objects are present, they are more likely clustered closer together, which can result in the identification of adjacent regions to the target regions.

The agents struggle the most on the 'CLEVR color' dataset. Hereby, only two configurations perform better than the baseline and reach a probability mass of around 64% to 67%. Both utilize a medium message length of $n \in \{3, 4\}$ and a medium-sized vocabulary of $|V| \in \{10, 16\}$. Interestingly, several configurations with short message lengths of $n \in \{1, 2\}$ perform worse than the baseline. This indicates that there is communication between the agents, but it rather distracts the receiver from the target object towards the distractors. The same argument for a more difficult task when more objects are involved can be made for the 'CLEVR color' dataset. This dataset includes even up to 10 objects present in the scene which increases the likelihood that the receiver focuses on a wrong object.




Figure 26: Examples of the *attention reference resolvers*' predictions in games with successful communication with a probability mass lower than 50% on the 'Dale' and 'CLEVR color' datasets. The black rectangle shows the cropped section the model is actually seeing after the image is preprocessed. The green rectangle surrounds the target region that needs to be predicted while the red regions show the actual predictions of the model. The more intense the red, the higher is the probability that the model assigned to this region.

Figure 26 shows examples of the wrongly identified regions on each dataset. These are predictions by configurations in which the agents were successfully communicating. In other words the sender was not able to transfer information to the receiver, even though a language had already emerged. As can be seen on the 'Dale-2' dataset in Figure 26(a), similar problems about non-visible objects occur as for the single

models described in Section 5.3. These are in fact the main errors on this dataset. However, in several cases (as in the central image), all objects are visible, and the agents still don't attend solely on the target object. Rather than choosing one of the distractors, the agents usually attend to both objects relatively equally. This indicates that the receiver is uncertain which object the sender is describing. Similar errors also occur on both remaining datasets. In contrast, the share of errors of the latter type is drastically higher. Looking at the results on the 'Dale-5' dataset (see Figure 26(b)), the model usually focuses on several objects at once. While a general pattern is difficult to identify, the receiver tends to confuse the target object with distractors that share multiple attributes with each other. In the central and right image, the wrongly identified distractors share both *size* and *shape* with the target object. Finally, on the 'CLEVR color' dataset, no overall reason for the errors can be identified in the qualitative analysis.

7 Analysis of the emerged languages

The languages that emerge are analyzed quantitatively using a probing approach. Probing can be used to analyze and interpret the hidden representations in neural networks (Conneau et al., 2018). Hereby, a second neural model is trained to classify selected linguistic features on the basis of the hidden representations. The model is expected to be able to easily fit the linguistic features it classifies for. This is considered evidence that these features are expressed in the underlying hidden representations of the main model. In the case of the emerged language, a simple encoder-decoder model is trained to translate the world of the agents, expressed by their messages, into English referring expressions, based on the GRE algorithm by Dale & Reiter (1995). Recall that this incremental algorithm is based on an order in salience for the attributes. In English, Dale & Reiter (1995) propose the order of *shape* > *color* > *size*. However, there is no policy for the agents that enforces specifically this order or indeed any salience order. For this reason, the emerged languages are compared to all six possible salience orders, given the three attributes *shape*, *color* and *size*. This will show if first, the languages follow any salience order and secondly, which attributes are more important for the agents to communicate.

The probing model consists of an encoder LSTM, one linear layer and a decoder LSTM. The encoder LSTM encodes the messages of the emerged language. Its final hidden state is used as a representation of the meaning of the complete message and passed through the linear layer, which learns an abstract representation of the message. The dimension of the linear layer is kept small to prevent memorizing the dataset and to force the model to find abstract connections between the input and the target. The resulting vector is used as the initial state of the decoder LSTM. The decoder LSTM is then trained to produce the English referring expression. Both LSTMs have an embedding dimension of $LSTM_e = 10$ and a hidden size of $LSTM_{out} = 10$, while the linear layer has a size of $l = 10$. The success of the model is validated calculating cross entropy between the models predictions and the target English referring expression. Since the probing task only focuses on how well the given messages of the agents can be related to English referring expressions, no dropout is applied, and the model is trained and validated on the complete dataset; no test or validation split is used. The models are trained for 200 epochs with a learning rate of $lr = 0,004$ and a batch size of 32 samples per batch.

The translation model can learn two characteristics with this setup. First, it can learn to find alignments between the emerged language and the English referring expressions, which is the goal of the probing. But secondly, it can as well learn underlying patterns in the English referring expressions that are independent of the emerged language. For instance, it can learn that the referring expressions are likely to be two symbols long, or that for instance 'cube' is the most common shape. This second characteristic leads to a low loss during training, even though there are no connections to the emerged language. In this test, only the first characteristic is interesting and shows the alignment between the emerged language and English referring expressions. For that reason, two reference baselines are calculated for each salience order of the attributes, so to eliminate the influence of the second characteristic. The first baseline $L_{baseline}$ uses a non-informative input for the encoder LSTM, more specifically it always receives a vector of zeros and therefore can't learn any meaningful representation in the linear layer; the input for the decoder LSTM is the same for every sample. By this, the model is trained to learn the structural patterns in the English referring expressions. The resulting loss is the highest possible loss the model can achieve, independent of the input. Resulting, if the emergent language is connected to English, the loss will be lower than this baseline. If not, the loss will be as high as this baseline. On the other side, the lowest possible loss $L_{English}$ is calculated, by using the English referring expressions as both input and target. This verifies that the model is able to learn an abstract representation from the input and the resulting loss should be close to zero (since the input is perfectly aligned with the target). These two references are used to normalize the results of the actual emergent languages L_{em} , using the formula $L_{norm} = \frac{L_{em} - L_{English}}{L_{baseline} - L_{English}}$. A loss close to $L_{baseline}$ will lead to 100%, while a loss as $L_{English}$ will lead to 0%. By doing this, all configurations can be compared directly to each other. The lower L_{norm} , the higher the alignment between the emerged language and English referring expressions.

Tables 29 to 39 show the normalized losses L_{norm} of the probing for the different tasks on all three datasets. In the following paragraphs, languages will be referred to by their message length n and their vocabulary size $|V|$ as $Lang_{n,|V|}$.

7.1 Object identification

n	$ V $	C > Sh > Si	C > Si > Sh	Sh > C > Si	Sh > Si > C	Si > C > Sh	Si > Sh > C
1	2	95,5%	97,57%	86,98%	81,43%	91,67%	86,45%
1	10	96,11%	96,9%	89,61%	85%	89,4%	84,49%
1	16	95,19%	96,56%	87,25%	81,22%	89,34%	83,13%
1	50	96,61%	97,07%	91,26%	85,75%	87,14%	82,61%
1	100	95,91%	96,73%	90,63%	86,01%	88,95%	84,17%
2	2	99,67%	99,91%	97,02%	95,37%	96,97%	94,64%
2	10	96,36%	96,34%	91,32%	86,75%	87,69%	82,87%
2	16	95,63%	97,12%	88,11%	83,21%	89,86%	85,35%
2	50	95,34%	97,3%	85,48%	80,89%	92,22%	86,18%
2	100	94,88%	96,32%	87,37%	81,17%	88,35%	82,61%
3	2	94,03%	96,96%	79,59%	74,54%	92,32%	85,63%
3	10	96,1%	95,97%	90,45%	84,84%	85,98%	80,5%
3	16	95,71%	95,1%	90,97%	85,33%	81%	75,56%
3	50	96,32%	94,55%	92,5%	86,81%	80,48%	75,73%
3	100	95,33%	97,82%	86,05%	81,33%	93,91%	88,54%
4	2	96,81%	95,12%	93,03%	87,41%	80,73%	75,47%
4	10	95,31%	97,26%	86,9%	82,67%	92,39%	86,98%
4	16	95,63%	94,65%	91,99%	86,65%	79,23%	74,54%
4	50	94,76%	96,69%	86,8%	81,33%	89,65%	83,92%
4	100	96,16%	97,94%	89,57%	85,18%	92,56%	87,74%
6	2	95,73%	96,99%	87,77%	83,27%	91,77%	86,34%
6	10	94,59%	99,89%	86,24%	81,46%	91,42%	86,43%
6	16	95,51%	96,3%	88,89%	83,24%	87,61%	82,71%
6	50	94,66%	97,43%	84,93%	78,61%	91,48%	83,66%
6	100	95,37%	97,77%	83,75%	80,84%	93,96%	89,02%

Table 29: Normalized losses L_{norm} of the probing model on emerged languages of the *discrimination games* on the ‘Dale-2’ dataset. The emerged languages are probed with different salience orders where ‘C’ corresponds to the *color*, ‘Sh’ to the *shape* and ‘Si’ to the *size*. The table only includes languages with which the agents could successfully solve the task. A lower loss indicates a higher alignment. Results with a low alignment are colored in red, while the best three configurations are marked in bold.

Looking at the results for the discriminator, one can see that the results are very different for each dataset. On the ‘Dale-2’ dataset L_{norm} is relatively high for all salience orders (see Table 29). Yet, the alignment with English referring expressions with the *color* as most important attribute is the lowest. When the *color* attribute is in the second position, the alignment gets better, but the best alignment is achieved when the *color* has the least importance. This shows that the agents don’t seem to use the *color* in the communication, but rather rely on *shape* and *size*. The order of importance of these attributes however is not as clear. For some combinations of the message length n and vocabulary size $|V|$, the *size* seems to be the dominant attribute, while for others the *shape* seems more important in the communication. Interestingly, one can see that for many languages only one salience order has a low L_{norm} , while the L_{norm} for the remaining salience orders with a different attribute in the first position is higher. This applies for example to $Lang_{3,2}$, where the loss for ‘Sh > Si > C’ is 74,54% while the second lowest is only at 85,63% for ‘Si > Sh > C’. The same can be seen for instance for $Lang_{3,16}$ in the other direction. This difference indicates that the agents are relying mostly on the most important attribute of this salience order to discriminate the target object. If the L_{norm} for instance were similar for the salience orders ‘Sh > Si > C’ and ‘Si > Sh > C’, this would mean that the emerged language could be connected to both salience orders in the same way. As a consequence, the agents would use the *shape* as often as the *size* to discriminate the objects. This is however only the case

on the 'Dale-2' dataset when the loss is higher (for instance languages $Lang_{2,16}$, $Lang_{2,100}$ or $Lang_{6,16}$). Since the lowest L_{norm} with 74,54% is still very high compared to a complete alignment (0%), the agents seem to encode additionally other information in their messages.

Looking at the influence of n and $|V|$, one can see that there is at least some alignment with one salience order across almost all values. The alignment seems to be best with $n \in \{3, 4\}$, where the loss can reach down 74,54%. Hereby, the most important attribute in the messages seems to be the *size*. For the remaining message lengths n , the loss stays mostly between 80% and 85%. For $n \in \{2, 6\}$ the *shape* seems to be the most dominant attribute, while for $n = 1$ the *size* and the *shape* seem to have a similar importance. The influence of the vocabulary size $|V|$ is not as clear. Small to medium-sized vocabularies seem to promote better alignments with English referring expressions, but also languages with $|V| = 100$ can reach losses of around 80%.

n	$ V $	C > Sh > Si	C > Si > Sh	Sh > C > Si	Sh > Si > C	Si > C > Sh	Si > Sh > C
1	2	94,96%	91,27%	94,51%	90,99%	88,52%	88,17%
1	10	84,34%	84,03%	80,91%	73,23%	79,95%	72,34%
1	16	86,27%	84,96%	82,76%	75,35%	80,72%	74,04%
1	50	85,95%	84,4%	82,96%	74,97%	80,2%	73,54%
1	100	86,31%	85,58%	82,9%	76,03%	81,64%	74,62%
2	10	82,66%	83,23%	78,51%	71,01%	78,89%	70,61%
2	16	89,78%	85,53%	87,68%	80,64%	81,06%	77,24%
2	50	84,4%	82,65%	80,62%	71,42%	77,53%	69,46%
2	100	89,65%	85,3%	87,26%	79,91%	80,88%	77,1%
3	2	87,19%	86,93%	83,99%	78,18%	83,65%	77,08%
3	10	87,15%	84,67%	84,01%	76,24%	80,41%	74,11%
3	50	82,98%	82,25%	78,85%	70,62%	77,42%	69,27%
3	100	83,78%	83,07%	80,23%	72,15%	78,94%	71,1%
4	2	89,23%	87,43%	87,09%	81,45%	83,83%	79,11%
4	10	88,66%	84,83%	85,9%	78,98%	80,2%	75,64%
4	16	83,14%	81,51%	78,15%	70,21%	77,32%	68,48%
4	50	87,62%	84,38%	85,25%	77,29%	79,94%	74,03%
4	100	90,17%	85,76%	87,68%	80,71%	81,37%	78,1%
6	10	82,03%	80,51%	77,46%	68,63%	75,71%	67,15%
6	16	84,73%	81,12%	80,99%	70,5%	76,06%	69,12%
6	50	86,95%	85,13%	84,06%	76,95%	80,11%	74,51%
6	100	86,15%	82,19%	83,56%	75,56%	77,76%	72,47%

Table 30: Normalized losses L_{norm} of the probing model on emerged languages of the *discrimination games* on the 'Dale-5' dataset. The emerged languages are probed with different salience orders where 'C' corresponds to the *color*, 'Sh' to the *shape* and 'Si' to the *size*. The table only includes languages with which the agents could successfully solve the task.

The emerged languages on the 'Dale-5' dataset have generally a better alignment to English referring expressions (see Table 30). For almost all salience orders and emerged languages, the loss is lower than 90%. In the best cases, it even reaches down to 67,15%. Again, the *size* and the *shape* are mostly communicated between the agents, but the *color* now plays a bigger role in the messages. The agents seem to need to rely on more attributes to discriminate the target object. This aligns also with English referring expressions, where the average length of the referring expressions across the whole 'Dale-5' dataset is longer than for the 'Dale-2' dataset. However, opposed to the 'Dale-2' dataset, there are almost no languages where there is one dominant attribute. More often the loss is similar for two salience orders with different primary attributes. For instance the salience orders 'Sh > Si > C' and 'Si > Sh > C' both provide losses around 70%

for $Lang_{6,16}$. Only the languages $Lang_{2,16}$, $Lang_{4,10}$, $Lang_{4,50}$ and $Lang_{6,100}$ have differences of more than 3% points for these salience orders. This indicates that the agents make use of both *shape* and *size* similarly often, while the *color* is used for much fewer images.

When the agents are able to produce longer messages, their languages seem to have more similarities with possible English languages. With $n > 1$ the agents produce languages that can have losses lower than 70% for the salience order 'Si > Sh > C'. Yet, languages with $n = 1$ are not far off and have mostly losses between 72% and 75%. Looking at the vocabulary size, languages with $|V| = 2$ are less likely to emerge and if they emerge they have a worse alignment with English. The best results are produced with $|V| \in \{10, 16\}$ for longer messages (for instance $Lang_{4,16}$, $Lang_{6,10}$ and $Lang_{6,16}$), while shorter messages fare generally better with a larger vocabulary of $|V| \in \{50, 100\}$ ($Lang_{2,50}$, $Lang_{3,50}$ and $Lang_{3,100}$).

n	$ V $	C > Sh > Si	C > Si > Sh	Sh > C > Si	Sh > Si > C	Si > C > Sh	Si > Sh > C
1	2	91,62%	91,57%	94,31%	95,13%	93,11%	94,92%
1	10	79,08%	79,08%	85,04%	86,86%	82,37%	86,38%
1	16	84,02%	83,96%	88,67%	89,65%	86,36%	89,36%
1	50	93,88%	93,74%	95,03%	95,49%	94,64%	95,35%
2	10	88,67%	88,36%	89,59%	90,77%	90,01%	89,81%
2	16	81,13%	81,02%	86,16%	87,97%	83,85%	87,56%
3	2	83,38%	83,46%	88,21%	89,71%	86,05%	89,37%
3	10	77%	76,77%	83,54%	85,57%	79,97%	84,9%
3	16	93,52%	93,6%	94,16%	94,14%	93,75%	93,55%
4	10	68,04%	66,51%	76,33%	78,56%	71,42%	78,56%
4	16	75,1%	74,93%	81,2%	83,35%	77,6%	82,76%
6	2	84,21%	84,02%	88,41%	89,77%	86,61%	89,35%

Table 31: Normalized losses L_{norm} of the probing model on emerged languages of the *discrimination games* on the 'CLEVR color' dataset. The emerged languages are probed with different salience orders where 'C' corresponds to the *color*, 'Sh' to the *shape* and 'Si' to the *size*. The table only includes languages with which the agents could successfully solve the task.

Finally, on the 'CLEVR color' dataset, much fewer languages emerge (see Table 31). Those languages that emerge have very different levels of alignment with English. While three languages stay above 90% for all salience orders, most of them stay between 80% and 90%. Four languages even get below 80% for the salience orders where the *color* is the most important attribute. One of those even reaches 66,51%, the best alignment across all emerged languages on the discrimination task. Unsurprisingly, the *color* is now the most important attribute. The loss with the remaining salience orders is still relatively low, but this is likely due to the fact that the color occurs in any referring expression as it is the only discriminating attribute. The probing model can therefore easily connect this pattern to the emerged language. As expected, the losses for 'Sh > Si > C' and 'Si > Sh > C' are almost the same, which indicates that the agents make (no) use of both *shape* and *size* in the same way.

Even though only one attribute would need to be communicated, languages with $n \in \{3, 4\}$ tend to be closer to English referring expressions. Hereby, vocabulary sizes of $|V| \in \{10, 16\}$ produce the most aligned languages, while languages with only 2 symbols have relatively high losses. The agents were not able to communicate with vocabulary sizes larger than 16.

7.2 Referring expression generation

n	$ V $	C > Sh > Si	C > Si > Sh	Sh > C > Si	Sh > Si > C	Si > C > Sh	Si > Sh > C
1	2	95,07%	98,06%	86,63%	85,3%	96,26%	93,32%
1	10	90,8%	96,4%	71,88%	69,29%	94,05%	85,13%
1	16	91,47%	96,96%	71,2%	66,82%	93,83%	83,35%
1	50	93,26%	96,63%	77,53%	71,94%	93,56%	84,62%
1	100	93,5%	97,86%	77,42%	71,93%	94,68%	85,77%
2	2	93,57%	97,72%	80,89%	79,8%	96,08%	90,71%
2	10	84,86%	92,07%	58,8%	52,09%	88,36%	77,01%
2	16	87,29%	92,88%	68,52%	71,5%	92,56%	83,9%
2	50	89,15%	95%	68,19%	68,93%	93,11%	83,95%
2	100	91,06%	96,14%	71,98%	67,23%	92,81%	82,71%
3	2	93,05%	97,15%	82,41%	77,36%	94,43%	88,8%
3	10	88,52%	95,41%	66,61%	63,63%	92,25%	81,46%
3	16	85,71%	92,88%	56,44%	49,22%	88,87%	74,54%
3	50	90,78%	96,28%	68,17%	64,84%	94,16%	83,5%
3	100	86,54%	93,54%	65,9%	66,03%	92,49%	83,28%
4	10	87,61%	94,63%	66,83%	64,85%	92,24%	82,85%
4	16	85,7%	93,56%	56,9%	52,1%	88,98%	76,15%
4	50	87,55%	94,24%	61,03%	55,82%	91,73%	76,52%
4	100	88,84%	94,84%	68,68%	66,73%	92,57%	81,79%
6	2	93,48%	98,14%	81,36%	79,08%	96,09%	90,95%
6	10	85%	92,44%	57,21%	55,07%	89,39%	77,44%
6	16	88,02%	94,22%	71,42%	66,35%	90,86%	84,12%
6	50	98,57%	99,45%	95,57%	95,06%	99,16%	96,64%
6	100	86,44%	92,76%	65,59%	65,93%	92,42%	82,16%

Table 32: Normalized losses L_{norm} of the probing model on emerged languages of the *referring expression generation games* on the 'Dale-2' dataset. The emerged languages are probed with different salience orders where 'C' corresponds to the *color*, 'Sh' to the *shape* and 'Si' to the *size*. The table only includes languages with which the agents could successfully solve the task.

Tables 32 and 33 show the results of the probing on the emerged languages of the *referring expression generation games*. This is the only task where the final task for the agents is to generate English referring expressions with the salience order 'Sh > C > Si'. English referring expressions are therefore explicitly passed to the agents as correct labels during training. One can then expect the agents to align their own language with the target referring expressions, and a high alignment with the salience order 'Sh > C > Si' is expected. Looking at the results, this is partially confirmed for the 'Dale-2' dataset. Some emerged languages reach one of the highest alignments to English referring expressions with a normalized loss of 49,22% across all emerged languages in this thesis. However, the salience order with the highest alignment is 'Sh > Si > C', and it values the *size* more than the *color*, instead of the reversed way as in the training data of the agents. The *color* seems, as in the previous task, not as important to communicate as the other attributes. While the *size* plays a bigger role, the *shape* is the central attribute in the communication. This fact is interesting for two reasons: first, the *shape* being the most important attribute in the messages aligns with the receiver's generated referring expressions where the *shape* was predicted almost perfectly. The receiver therefore seems to make use of the sender's ability to extract the *shape* from the images and it reproduces what the sender communicated. However, without a deeper analysis, it can't be ruled out that the receiver extracts the *shape* themselves from the image, and it uses the sender's message only to determine the correct target object in the scene. Secondly, this does not apply directly to the *size* and the *color*. The *size* seems to be communicated often by the sender to discriminate the target object. On the other hand, as the target referring

expression uses the salience order 'Sh > C > Si', the shape is only needed to be generated in $\frac{1}{3} * \frac{1}{8} \approx 4, 2\%$ of the samples. The opposite applies to the *color*. The *color* is not important in the agents' communication, but the receiver however needs to produce colors in the generated referring expression in $\frac{1}{3} \approx 33, 3\%$ of the samples. This shows that the agents actually don't align their own language with the target referring expression. The communication of the target object between the agents seems to be a separate step from the receiver's generation of the referring expression.

Looking at the influence of the message length, one can see that the language is the least aligned to the salience order 'Sh > Si > C' with $n = 1$. Still, even with these short messages, the loss can go down to 66,82%. With $n > 1$, almost all languages have a loss of below 70%, while at least one configuration is even lower than 60%. Hereby, languages with $n \in \{3, 4\}$ have the highest alignment to English. Languages with the highest alignment also mostly make use of a medium-sized vocabulary of $|V| \in \{10, 16\}$ as for example *Lang*_{2,10}, *Lang*_{3,16}, *Lang*_{4,16} and *Lang*_{6,10}. While larger vocabularies can still align relatively much with English referring expressions, languages with $|V| = 2$ are much less similar.

n	$ V $	C > Sh > Si	C > Si > Sh	Sh > C > Si	Sh > Si > C	Si > C > Sh	Si > Sh > C
1	2	92,86%	96,4%	90,06%	89,5%	95,73%	90,93%
1	10	83,9%	90,9%	78,63%	74,74%	89,6%	78,99%
1	16	84,68%	91,65%	80,11%	77,03%	90,16%	81,05%
1	50	84,85%	91,67%	79,95%	77,11%	90,32%	81,04%
2	2	90,51%	95,36%	87,5%	86,43%	94,77%	88,35%
2	10	82,44%	90,32%	77,65%	73,73%	88,89%	78,41%
2	16	81,85%	89,4%	76,07%	71,66%	87,9%	75,91%
2	50	83,58%	91,12%	78,67%	75,03%	89,94%	79,06%
3	2	92,51%	95,96%	89,96%	88,7%	95,18%	90,43%
3	10	82,11%	89,54%	75,9%	71,78%	88,18%	76,72%
3	50	83,12%	90,82%	77,62%	74,08%	88,88%	78,74%
3	100	83,74%	89,59%	79,29%	74,48%	87,46%	78,05%
4	2	88,86%	94%	84,8%	83,19%	93,37%	85,92%
4	10	79,93%	89,29%	74,1%	69,5%	87,19%	74,79%
4	16	81,26%	89,68%	75,73%	71,96%	88,4%	76,93%
4	50	81,55%	89,42%	75,9%	71,68%	88,17%	76,55%
6	2	91,09%	95,26%	87,86%	86,81%	94,78%	88,82%
6	50	80,39%	87,85%	75,01%	68,71%	84,54%	72,93%

Table 33: Normalized losses L_{norm} of the probing model on emerged languages of the *referring expression generation games* on the 'Dale-5' dataset. The emerged languages are probed with different salience orders where 'C' corresponds to the *color*, 'Sh' to the *shape* and 'Si' to the *size*. The table only includes languages with which the agents could successfully solve the task.

On the 'Dale-5' dataset, the emerged languages again resemble the English referring expressions less. While the dominant salience order is 'Sh > Si > C' as on the 'Dale-2' dataset, the *color* plays a bigger role. This effect is the same as for the discrimination games, and can be explained by the higher number of distractors. While the loss for the salience order 'Sh > Si > C' is lower than 70% for two languages, it stays between 70% and 80% for most languages. Interesting now is that all attributes are communicated by the sender, while the receiver is also generating the correct attributes in the referring expression. Opposed to the 'Dale-2' dataset, the need for *size* and *color* is much bigger to discriminate the target object in any salience order, due to the larger number of distractors.

*Lang*_{6,50} is the emerged language with which the agents can achieve the best results on the task. While the receiver achieves high precision and recall scores on each attribute (recall Tables 24 and 25), each

attribute also plays a bigger role in the message by the sender. Indeed, one can see an alignment between the predictions of the receiver and the usage of attributes in emerged language. A more frequent usage of an attribute in the emerged language leads to a more accurate generation of this attribute in the final referring expression.

As for the previous analyses, a vocabulary size of $|V| = 2$ seems to be too small for the agents to use similar referring expressions as in English. Additionally to $|V| \in \{10, 16\}$, also a vocabulary size of $|V| = 50$ now helps the agents to create more resembling languages. Only the language $L_{3,100}$ emerges, that utilizes a vocabulary of $|V| = 100$, and it aligns similarly to English as $L_{3,50}$ and slightly worse than $L_{3,10}$.

Looking at the message length, a larger n brings the emerged languages close to English referring expressions. With $n = 1$ the normalized loss remains above 74,74%. With growing n , the loss decreases, and even gets lower than 70% for $n \in \{4, 6\}$. However, while $Lang_{6,50}$ is the language with the highest alignment, it is one of only two languages that emerged with $n = 6$. This indicates that agents struggle with so few constraints, but if they do converge to a language, it makes use of similar structures as English.

n	$ V $	C > Sh > Si	C > Si > Sh	Sh > C > Si	Sh > Si > C	Si > C > Sh	Si > Sh > C
1	2	95,73%	94,23%	92,96%	90,59%	81,59%	78,21%
1	10	91,77%	91,19%	73,14%	63,99%	67,45%	57,55%
1	16	91,74%	90,87%	73,07%	63,78%	66,16%	55,48%
1	50	97,78%	93,1%	94,22%	87,45%	69,23%	64,97%
1	100	97,91%	93,1%	94,18%	87,35%	69,25%	64,99%
2	2	93,17%	91,69%	81,96%	75,97%	72,05%	64,29%
2	10	94,07%	98,04%	75,32%	71,91%	94,38%	86,62%
2	16	97,72%	92,9%	94,18%	87,09%	68,54%	64,13%
2	50	97,87%	93,08%	94,25%	87,54%	69,2%	65,17%
2	100	89,6%	89,58%	65,65%	55,69%	64,92%	53,53%
3	2	97,73%	99,28%	95,84%	97,72%	101,58%	100,22%
3	10	91,04%	90,52%	71,06%	61,36%	65,59%	54,93%
3	16	91,09%	90,3%	71,71%	62,42%	66,28%	56,16%
3	50	97,07%	91,72%	92,7%	85,33%	66,38%	61,26%
3	100	97,81%	93,01%	94,16%	87,3%	68,83%	64,6%
4	2	91,95%	96,87%	73,55%	72,66%	98,37%	90,23%
4	10	97,7%	93,1%	94,16%	87,24%	69,22%	64,81%
4	16	86,75%	89%	57,02%	44,33%	63,78%	48,21%
4	50	90,86%	90,5%	71,22%	61,09%	65,26%	54,87%
4	100	96,4%	90,22%	92,44%	83,78%	59,98%	54,38%
6	2	90,06%	90,46%	71,62%	64,56%	70,67%	61,35%
6	10	88,38%	90,24%	63,68%	53,21%	64,22%	52,19%
6	16	89,01%	89,74%	67,03%	56,73%	64,44%	52,78%
6	50	97,68%	92,77%	97,03%	87,24%	68,51%	64,27%
6	100	89,84%	89,81%	69,75%	60,55%	65,19%	54,93%

Table 34: Normalized losses L_{norm} of the probing model on emerged languages of the *attribute generation games* on the 'Dale-2' dataset. The emerged languages are probed with different salience orders where 'C' corresponds to the *color*, 'Sh' to the *shape* and 'Si' to the *size*. The table only includes languages with which the agents could successfully solve the task.

Tables 34 to 36 show the results for the probing of the emerged languages in the *attribute generation games*. The first detail that can be seen is the difference of the results between the 'Dale' datasets and the 'CLEVR color' dataset. On the 'Dale' dataset, the *color* plays no or only a small role in the languages. While most

of the emerged languages align with the salience order 'Si > Sh > C', languages with the lowest loss align with the salience order 'Sh > Si > C'. These indeed achieve the lowest loss across all experiments and tasks in this thesis.

When looking closer on the results for the 'Dale-2' dataset, the influence of n and $|V|$ is less clear. While high alignments with English can be achieved with any n , the normalized loss remains consistently low only with $n \geq 2$. Hereby, a medium vocabulary size of $|V| \in \{10, 16\}$ provides the best results (for instance $Lang_{3,10}$, $Lang_{3,16}$, $Lang_{4,16}$, $Lang_{6,10}$ and $Lang_{6,16}$). However, also large vocabularies of $|V| \in \{50, 100\}$ can give low losses as seen in $Lang_{2,100}$, $Lang_{4,50}$, $Lang_{4,100}$ and $Lang_{6,100}$. This is anyway less consistent. When given a vocabulary with $|V| = 2$, the emerged languages have almost always a relatively low alignment with English.

A similar detail to the emerged languages of the *referring expression games* is as well visible here. Some languages as for instance $Lang_{2,100}$, $Lang_{6,2}$ and $Lang_{6,10}$ achieve similar losses for the salience orders 'Sh > Si > C' and 'Si > Sh > C' which indicates that the *size* and the *shape* are used equally often in the messages. Interestingly, this doesn't have any effect on the final predictions of the receiver. No big difference can be identified for games where the agents make use of these languages or of languages with only one dominant attribute. Indeed, the parsing of the sender's message seems not to be directly connected to the final prediction of the attributes by the receiver. While the *size* is almost always communicated as the most important attribute, it is never predicted correctly by the receiver, as the accuracy of the *size* lies around 52%. The opposite applies to the *color*. This indicates that the sender's message is only used to extract the target object from the image, but the extraction of the attributes for the final prediction is a separate step.

As expected, Table 35 shows that the *color* plays a bigger role for the 'Dale-5' dataset. Still, the dominant salience order is 'Si > Sh > C', in some cases 'Sh > Si > C'. As opposed to the 'Dale-2' dataset, both salience orders have almost always a similarly low loss which indicates that the *size* and *shape* are equally important.

Looking at the influence of the message length n , one can see that languages with $n = 1$ tend to have the worst alignment with English referring expressions. While there are few outliers, languages with $n \geq 2$ perform similarly. The same applies as well to the vocabulary size $|V|$. When the agents are given a very small vocabulary with $|V| = 2$, the resulting languages look very different from English. An increase to $|V| = 10$ lets the agents produce the most similar languages. Increasing it further tends to lower the alignment slightly, but stays mostly still around 65%.

Finally, on the 'CLEVR color' dataset, only very few languages emerge. As expected, the most of them align with salience orders that have the *color* as its most important attribute. The one exception is $Lang_{1,2}$ with the salience order 'Sh > C > Si' that doesn't rely on the *color* at all. However, looking at the results of the receiver's predictions in Table 26, one can see that this configuration doesn't beat the baseline and the communication doesn't seem to help to solve the task.

Looking at the remaining languages, the losses for the salience orders 'C > Sh > Si' and 'C > Si > Sh' are almost equal, which indicates that the *size* and *color* are (not) used equally often. However, that alignment in between 70% to 83% is relatively low compared to the alignments that reach below 50% on the 'Dale' datasets. This can be confirmed by the accuracies of the *color* attribute of the receivers' predictions. Configurations where a language between the agents emerges perform only around 1% higher than the baseline of 90% with no communication. The receiver can solve the task almost on their own and the messages of the sender only help in few cases. The sender seems to be only needed to communicate very specific information instead of always communicating the *color*. For instance, the receiver could struggle with specific *colors* or other underlying structural patterns. This results in a different language and in the lower alignment to English referring expressions.

n	$ V $	C > Sh > Si	C > Si > Sh	Sh > C > Si	Sh > Si > C	Si > C > Sh	Si > Sh > C
1	2	91,81%	96,22%	89,08%	88,2%	95,91%	90,3%
1	10	83,4%	82,11%	79,68%	67,88%	77,12%	66,75%
1	16	86,76%	87,06%	83,08%	75,03%	83,79%	74,72%
1	50	83,12%	82%	78,81%	66,76%	76,95%	65,95%
1	100	93,84%	87,09%	93,01%	83,36%	82,19%	79,14%
2	2	88,86%	86,82%	86,62%	78,45%	82,59%	76,49%
2	10	83,91%	81,57%	79,76%	67,89%	76,47%	66,1%
2	16	75,6%	77,74%	68,78%	55,43%	72,24%	56,24%
2	50	85,1%	83,08%	81,27%	70,13%	77,86%	68,54%
2	100	83,24%	81,87%	79,02%	67,32%	77,06%	66,19%
3	2	97,21%	96,08%	96,43%	95,23%	95,18%	94,24%
3	10	82,66%	81,11%	78,38%	66,21%	75,68%	64,52%
3	16	93,26%	86,09%	92,67%	82,25%	81,17%	77,84%
3	50	82,83%	81,44%	78,57%	66,29%	76,04%	64,84%
3	100	82,74%	81%	78,39%	66,04%	75,44%	64,91%
4	2	92,91%	87,03%	92,16%	84,06%	82,45%	79,57%
4	10	79,3%	79,42%	74,65%	61,71%	74,12%	60,62%
4	16	82,55%	81,31%	78,61%	66,51%	75,61%	65,05%
4	50	88,51%	84,17%	85,77%	75,07%	79%	71,93%
4	100	82,57%	81,61%	78,06%	66,33%	76,32%	65,54%
6	2	92,36%	88,15%	91,49%	84,38%	85,28%	80,85%
6	10	78,11%	79,19%	72,81%	59,86%	73,95%	60,17%
6	16	82,35%	81,09%	78,84%	66,02%	75,9%	64,79%
6	50	82,04%	81,49%	78,34%	66,25%	76,46%	64,91%
6	100	82,09%	80,73%	77,42%	65,3%	75,52%	64,52%

Table 35: Normalized losses L_{norm} of the probing model on emerged languages of the *attribute generation games* on the 'Dale-5' dataset. The emerged languages are probed with different salience orders where 'C' corresponds to the *color*, 'Sh' to the *shape* and 'Si' to the *size*. The table only includes languages with which the agents could successfully solve the task.

The languages with the lowest alignment have a medium-sized vocabulary of $|V| \in \{10, 16\}$ and are relatively short with $n \in \{1, 3\}$. While the language $Lang_{6,2}$ emerges which uses a small vocabulary with long messages, the normalized loss is much higher.

n	$ V $	C > Sh > Si	C > Si > Sh	Sh > C > Si	Sh > Si > C	Si > C > Sh	Si > Sh > C
1	2	99,92%	99,88%	79,83%	82,7%	99,71%	82,14%
1	10	70,52%	70,36%	80,23%	82,36%	74,49%	81,77%
1	16	77,25%	77,16%	84,55%	86,2%	80,72%	85,56%
3	10	71,46%	71,47%	78,81%	81,87%	75,95%	80,93%
6	2	83,25%	83,23%	87,74%	88,95%	85,38%	88,87%

Table 36: Normalized losses L_{norm} of the probing model on emerged languages of the *attribute generation games* on the 'CLEVR color' dataset. The emerged languages are probed with different salience orders where 'C' corresponds to the *color*, 'Sh' to the *shape* and 'Si' to the *size*. The table only includes languages with which the agents could successfully solve the task.

7.3 Reference resolution

n	$ V $	C > Sh > Si	C > Si > Sh	Sh > C > Si	Sh > Si > C	Si > C > Sh	Si > Sh > C
1	2	95,17%	97,23%	87,74%	82,8%	94,4%	88,75%
1	10	96,04%	94,67%	94,06%	88,67%	82,86%	79,71%
1	16	93,82%	95,48%	85,33%	79,96%	90,17%	84,6%
1	50	94,47%	96,65%	86,98%	81,89%	90,93%	86,51%
1	100	95,6%	98,19%	90,41%	86,13%	95,74%	93,76%
2	2	94,75%	96,65%	86,51%	80,84%	92,99%	86,3%
2	10	94,69%	98%	86,92%	82,2%	96,31%	92,55%
2	16	95,04%	96,39%	87,82%	82,54%	90,91%	87,2%
2	50	97,18%	93,99%	96,42%	92,26%	77,97%	75,58%
2	100	93,71%	94,65%	85,56%	78,95%	83,77%	78,69%
3	2	95,24%	97,37%	87,56%	82,49%	94,38%	88,87%
3	10	96,62%	91,61%	94,87%	89%	69,2%	65,45%
3	16	93,45%	97,16%	83,6%	77,06%	94,5%	89%
3	50	90,97%	95,74%	74,49%	68,89%	92,37%	84,98%
3	100	96,74%	92,76%	95,51%	90,35%	71,88%	69,69%
4	2	94,94%	96,45%	89,08%	83,89%	92,29%	85,7%
4	10	91,62%	93,29%	78,53%	70,85%	81,99%	74,83%
4	16	92,86%	96,45%	79,49%	73,49%	94,05%	86,05%
4	50	94%	94,78%	86,17%	79,61%	88,11%	82,65%
4	100	92,15%	96,99%	78,91%	72,51%	94,8%	88,6%
6	16	90,04%	95,83%	69,71%	61,75%	91,77%	81,6%
6	50	91,9%	96,28%	76,04%	69,86%	92,81%	85,2%

Table 37: Normalized losses L_{norm} of the probing model on emerged languages of the *attention prediction games* on the 'Dale-2' dataset. The emerged languages are probed with different salience orders where 'C' corresponds to the *color*, 'Sh' to the *shape* and 'Si' to the *size*. The table only includes languages with which the agents could successfully solve the task.

Finally, Tables 37 to 39 show the similarities between the emerged languages on the *attention prediction games* and English referring expressions. On the 'Dale-2' dataset, one can see that most of the emerged languages align to English in some way. The least aligned language is $Lang_{1,100}$ with 86,13% towards the salience order 'Sh > Si > C'. Hereby, a strong influence of the message length n and vocabulary size $|V|$ can be extracted. Languages with short messages of $n \in \{1, 2\}$ are less connected to English referring expressions. With $n = 2$, larger vocabulary sizes can bring the loss below 80% as seen for the languages $Lang_{2,50}$ and $Lang_{2,100}$. Languages with $n \geq 3$ are aligned more, whereas languages with $n = 3$ perform the best. Looking at the vocabulary size, one can see that again a vocabulary size of $|V| = 2$ render the emerged language more different from English. A vocabulary size of $|V| = 10$ seems to provide the most similar languages ($Lang_{3,10}$, $Lang_{4,10}$) for larger n , but larger vocabularies of $|V| \in \{50, 100\}$ are only few percent points higher. When given languages with $n = 6$, the agents can utilize them only in few cases with medium-sized vocabularies, but if they do, the emerged languages are very similar.

Most of the languages are based on the salience order 'Sh > Si > C', and only the languages $Lang_{2,50}$, $Lang_{3,10}$ and $Lang_{3,100}$ use the salience order 'Si > Sh > C'. The *color* plays almost no role in the communication. In almost all the languages, one attribute is dominant while the remaining two attributes are used much less frequently. This can be seen in the large margin between the losses of the salience orders where the first two attributes are swapped (for instance 'Sh > Si > C' and 'Si > Sh > C').

On the 'Dale-5' dataset, much fewer languages emerge and those that do emerge have a much lower align-

n	$ V $	C > Sh > Si	C > Si > Sh	Sh > C > Si	Sh > Si > C	Si > C > Sh	Si > Sh > C
1	2	95,35%	89,87%	95,09%	87,23%	86,01%	84,14%
1	16	92,95%	87,03%	92,63%	83,91%	82,77%	80,06%
1	50	93,35%	87,23%	93,26%	84,65%	82,46%	80,38%
2	10	88,94%	84,78%	87,5%	77,76%	80,24%	74,95%
2	16	85,71%	84,53%	82,98%	72,85%	79,72%	71,85%
3	16	92,18%	86,23%	91,93%	82,59%	81,69%	78,72%
3	50	92,68%	86,53%	91,9%	83,35%	82,45%	79,99%
6	10	93,4%	86,51%	91,64%	84,03%	82,51%	80,06%

Table 38: Normalized losses L_{norm} of the probing model on emerged languages of the *attention prediction games* on the ‘Dale-5’ dataset. The emerged languages are probed with different salience orders where ‘C’ corresponds to the *color*, ‘Sh’ to the *shape* and ‘Si’ to the *size*. The table only includes languages with which the agents could successfully solve the task.

ment to English referring expressions than languages on the ‘Dale-2’ dataset. The losses for salience orders ‘Sh > Si > C’ and ‘Si > Sh > C’ are much closer, meaning both *size* and *shape* are used similarly often in the messages. The *size* is hereby slightly more important with a lower loss of 1% to 4% points. The *color* plays a larger role than on the ‘Dale-2’ dataset, but it is still the least important attribute.

The emerged languages are making use of shorter messages. The most similar languages use a message length of $n = 2$ followed by $n = 3$. While one language emerges with $n = 6$, it is less similar to English. Looking at the vocabulary size, a medium-sized vocabulary with $|V| \in \{10, 16, 50\}$ provides the most similar languages. However, no conclusive argument about this dependency can be made, as too few languages emerged to compare the effects of the vocabulary thoroughly.

n	$ V $	C > Sh > Si	C > Si > Sh	Sh > C > Si	Sh > Si > C	Si > C > Sh	Si > Sh > C
3	16	98,48%	98,58%	97,87%	96,11%	96,6%	95,97%
4	10	98,88%	98,75%	97,23%	96,67%	97,18%	96,75%

Table 39: Normalized losses L_{norm} of the probing model on emerged languages of the *attention prediction games* on the ‘CLEVR color’ dataset. The emerged languages are probed with different salience orders where ‘C’ corresponds to the *color*, ‘Sh’ to the *shape* and ‘Si’ to the *size*. The table only includes languages with which the agents could successfully solve the task.

Finally, Table 39 shows the similarities of the emerged languages on the ‘CLEVR color’ dataset. Only two languages emerge that help the receiver to increase its predicted probability mass on the target object. While the results are not as high as on the ‘Dale’ dataset, the agents still fare better than the baseline model without any communication. This indicates that the sender is communicating meaningful information to the sender to solve the task. This is however not visible in the results of the probing model. None of the two emerged languages has high similarities with any salience order in English. Interestingly, the lowest (but still very high) normalized losses of 95% to 96% are not based on the only discriminating attribute *color*, but rather on the non-discriminating attributes *shape* and *size*. It suggests that the agents make use of other underlying structural patterns rather than the defined attributes to communicate and solve the task. However, these patterns seem to be difficult to exploit as only two configurations achieve it and both don’t solve the task with high accuracy.

8 Discussion

As outlined in the introduction, two main research questions are to be answered in this thesis. First, what are the limits of the agent’s architectures, the environment, and the input representations on successfully grounding referring expressions in language games? Secondly, to what degree do the emerged languages align with referring expressions in a natural language like English, and what constraints can be imposed on the environment and the agents themselves so that languages align? This section discusses the results of the previous sections in the context of these two questions.

In every experiment, the results are compared to a baseline in which the sender is sending random symbols in the messages. By doing this, it can be determined if a successful communication emerged between the agents. When the agents beat the baseline, the sender needs to have sent at least some information which the receiver could interpret in the context of the task. However, it is more difficult to understand what the agents communicate exactly. More specifically, it can’t easily be seen if the agents exchange referring expressions or other types of messages based on the visual inputs. To resolve this problem, this thesis aims to control what the agents can communicate by introducing a very specific bias to the dataset. The only way for the sender to communicate a target object is by using the attributes *shape*, *size* and *color*, and hence by generating referring expressions. While it can’t be completely guaranteed that the agents don’t make use of any other unseen biases in the dataset, it will be assumed that a successful communication which solves the tasks is based on exchanged referring expressions in the emerged languages. This hypothesis is supported by the analysis of emerged languages that show a certain alignment with English referring expressions for almost all emerged languages.

The central question in this thesis revolves around the limits of the agent’s architectures, the environment, and the input representations in successfully grounding referring expressions in language games. The objective is to understand how these factors influence the emergence of referring expressions in artificial languages.

The most significant impact on successfully grounding referring expression comes from the **environment** the agents are exposed to. This includes both the task the agents need to solve, and the dataset the agents are presented. It is evident that while some tasks can easily be solved, the agents struggle often with more complex datasets and more complex tasks.

The agents are presented with three different **datasets**. Both ‘Dale’ datasets include a similar bias, namely that the target object can be discriminated using the three attributes *shape*, *size* and *color*. However, as the ‘Dale-2’ dataset only contains one distractor object, the minimum length of a discriminating referring expression is relatively short; fewer attributes are necessary to uniquely identify the target object. On the other side, the ‘Dale-5’ dataset includes four distractors and, on average, the referring expressions need to be based on more attributes. Agents therefore need to learn to ground multiple attributes at once in one referring expression which makes the task much harder. This can be seen as well in the results across all experiments. When shown scenes from the ‘Dale-2’ dataset, the agents can consistently beat the baseline, and often achieve almost perfect scores on the object identification and reference resolution tasks. In other words, the agents are able to successfully ground referring expressions to discriminate the target object from the distractor.

When the agents are presented with scenes from the ‘Dale-5’ dataset, a different pattern emerges. First, while the number of successful communications decreases, still many agent configurations are able to solve the tasks to some extent. Again, this shows that the agents are able to ground referring expressions in an emerged language. However, the metrics for most tasks are lower than on the ‘Dale-2’ dataset. This suggests that the emerged referring expressions don’t include all necessary elements to uniquely refer to the target object. Some necessary information to solve the task perfectly is not communicated from the sender to the

receiver. Results from the referring expression generation tasks in Section 6.2 suggest that the reason for this difference are the different attributes. While the *shape* seems to be learned quickly, the agents struggle more with the *size* and especially the *color*. This can be seen for both the 'Dale-2' and 'Dale-5' dataset; the effect is even stronger on the 'Dale-2' dataset. As discussed above, on the 'Dale-2' dataset often only one or two attributes are necessary to discriminate the target object. This results in a focus on the *shape* that is identified always perfectly, and a smaller focus on a secondary attribute, *color*, which is identified correctly oftentimes. As more discriminating attributes are necessary on the 'Dale-5' dataset, predictions of all attributes beat the baseline. Still, the *shape* is the attribute that is most often identified correctly, followed by the *color* and finally the *size*. These results however don't allow conclusions why certain attributes are preferred over others. This would need to be studied in future work.

Finally, the 'CLEVR color' dataset gives insights in how much bias is needed so that agents can ground referring expressions. The objects can only be discriminated using one attribute, the *color*. Instead of 48 possible combinations, the scene can only include a maximum of 8 possible different objects. This apparently increases the difficulty for the agents to generate and comprehend referring expressions. Across all experiments, the agents struggle the most on this dataset. While the object identification and the reference resolution tasks can be solved, the scores are lower compared to the other datasets. On top, much fewer agent configurations are able to successfully communicate and few languages emerge. On the reference resolution task, discussed in Section 6.3, even only one configuration can beat the baseline. This is a surprising result, as one could expect that fewer combinations in the dataset would make it easier for the agents to ground their referring expressions.

However, there could be several reasons explaining this phenomenon. First, the *color* attribute itself is a difficult attribute to ground and the agents struggle to extract the visual features from the scenes. This explanation is also supported by the results on the 'Dale' datasets, where the agents usually prefer the *shape* and *size* over the *color*. Secondly, the number of possible values of each attribute could impact the learning. There are eight different colors, compared to only two sizes and three shapes. This could make it harder for the agents to ground each *color* to a referring expressions than it might be for the *shape* and the *size*. Future work would need to focus on this hypothesis, by comparing for instance additional datasets, where the only discriminating attributes are the *shape* or *size*, or by changing the number of possible colors.

Additionally to the datasets, the **task** itself has a major impact on the agents' capabilities to ground referring expressions in their messages. The object identification task, described in Section 6.1 is the least complex task as agents only need to discriminate between multiple objects. Both sender and receiver are only presented with bounding boxes that include single objects as opposed to whole scenes with all objects. The agents are able to solve this task almost perfectly, compared to a baseline, which implies that the sender must have communicated a grounded referring expression. The complexity increases when more objects are added to the scene, slowing the process of emergence but not preventing it. If only one attribute, such as the *color*, can be used for discrimination, the task becomes harder to solve, and emergence is slower, but referring expressions still emerge, beating the baseline.

The task of referring expression generation is already of higher complexity (Section 6.2). Instead of only comprehending referring expressions, the receiver needs as well to generate referring expression on his own. For this, he needs to learn a complete new vocabulary (English attributes) and arrange them in the correct order. However, opposed to the previous task, the gold label referring expressions inject new bias into the task during training. The agents might use this bias, to align their own emerged referring expressions with given English referring expressions, hence facilitating the grounding of emerged referring expressions. The results of the experiments show that this hypothesis holds only to a certain extent. The agents are able to beat the baseline in certain configurations, showing that referring expressions are communicated. However, in a closer look, it can be seen that the agents only focus on the *shape* and the *color* in their final referring expressions, whereas only the *shape* can be predicted consistently. The agents are therefore not

completely able to make use of the given bias in their own communication, possibly communicating only some attributes. Results of the single models in Section 5.2 suggest that it is not only the added complexity of the agents’ communication, but the task itself that prevents the agents from successfully grounding referring expressions. This is especially eminent for the *masked RE generator*, that achieves similar results with a similar setup and input representations. In future work, this fact would need to be analyzed more deeply to understand why this bias doesn’t help the agents as expected.

In the final task in Section 6.3, the agents need to solve the most complex task. Hereby, the agents need to both resolve referring expressions and ground them in geometric features in the scenes. The main fact that can be concluded from the experiments is that grounding in geometric features works only to a certain extent. As soon as the agents are tasked to predict pixel precise locations in the scenes, they are not able to generate referring expressions. This is especially apparent when compared to the single models in Section 5.3. While the single model already struggles across the datasets, it is able to solve it on the ‘Dale-2’ dataset, showing that the architecture is generally able to combine visual and geometric features. However, when agents are tasked to solve the task together by grounding referring expressions in an emerged language, they fail to do so. In no case, the sender communicates any meaningful information to the receiver. This suggests that the feedback that the receiver gets during training can’t be propagated to the sender as it likely contains too precise geometric information. When reducing the needed geometric precision by predicting regions instead of coordinates, the agents are suddenly able to easily solve the task. As the feedback during training can be linked better to the visual features in each region, the receiver can likely pass this information better on to the sender, and a language can emerge. As expected, a more complex scene with more objects challenges the agents more. However, with every dataset, there is at least one agent configuration that is able to solve the task with successful communication, showing that a less precise task can help to agents to ground referring expressions.

Input representations significantly impact the emergence of referring expressions. More referring expressions seem to emerge when agents are shown bounding boxes, each containing one object, versus complete scenes that include all objects. This might be because agents do not need to separate the objects from one another but can directly extract features. However, this conclusion is limited as the only setup where the receiver sees bounding boxes is the object identification task. Preliminary experiments have shown that when the sender is presented with complete scenes as well, almost no other task can be solved, and no referring expressions emerge. Only when the sender sees bounding boxes, the agents are successful.

The **agent’s architectures** has the least impact on the successful grounding of referring expressions. However, the architecture is inherently tied to the task to solve and is challenging to evaluate independently. For instance, for the referring expression generation, the agents need to generate a sequence of tokens, requiring a much more complex architecture, like LSTMs, than a simpler dot product for the object identification task. However, results show minimal differences when the sizes of specific layers in the agents are adjusted. Changing the hidden and embedding size of the sender LSTM has almost no impact on the emergence of referring expressions, and the same applies to image embedding sizes or dimensions of the output layers.

In conclusion, the environment and input representations have a significant impact on the successful grounding of referring expressions in language games, while the agent’s architecture plays a less critical role. These findings offer valuable insights into the limits and potential of grounding referring expressions in artificial languages, paving the way for further research in this field.

The analysis of the emerged languages gives an insight in when emerged languages align with English. The analysis focuses on two properties. Do the emerged languages make use of the same attributes *shape*, *color* and *size*, and if yes, in which environments? Do the emerged languages follow an incremental approach to specify attributes, or at least give them different importance? To answer the first question, the results show that the agents are relying not only on these attributes by default. While many emerged languages

make use of the attributes, the alignment to English referring expressions is widely lower, and the agents are able to solve the tasks with unaligned languages. The datasets were designed and generated to only contain a domain-specific bias in the visual scenes, namely objects with different combinations of these attributes. The random nature of its generation and the simplicity of its possible combinations aimed to reduce any other patterns and biases that the neural networks could exploit. However, the results show that many emerged languages often seem to utilize biases other than the defined attributes to communicate information. Changes in the tasks and the constraints of communication on the other hand can change the behavior and push the agents to rely more or less on these attributes.

One heavy influence on the usage of these attributes is the given space to transfer information. If the space is very small, the languages tend to rely on other patterns. More specifically that applies to a vocabulary size $|V| = 2$. While still able to solve the tasks to a certain extent, the emerged languages tend to align less with the English referring expressions. This agrees with the fact that only one symbol (and the `<eos>` token) can't represent all possible values of the attributes, even with a sequence length of six symbols. The agents are therefore forced to exploit other biases in the visual scenes that are less diverse to generate referring expressions. What biases these are, needs to be conducted with more experiments.

The message length has a lower impact on the alignment with English referring expressions. Across all message lengths, languages emerge that align better and others that align worse. Hereby, it is especially interesting that the probing approach doesn't highlight almost any interaction between vocabulary size $|V|$ and message length n . One might expect that a smaller vocabulary would require longer messages and vice versa. The results however suggest that there is no connection. A deeper correlation analysis would be required to prove this hypothesis.

A major difference can be seen in the usage of each attribute. While the *shape* and *size* seems to be used relatively consistently across all tasks and datasets, the agents have the biggest problem with the *color* attribute. This attribute is used very few for the 'Dale' datasets. Even on the 'CLEVR color' dataset where it is the only discriminating attribute, the emerged languages seem to use it only in combination with another unseen bias. As discussed in the previous sections, a reason for the preference of certain attributes over other attributes can't be concluded by the conducted experiments. In future work, this aspect would need be studied deeper.

When analyzing if the agents follow an incremental approach, one can see that this is indeed mainly the case. One attribute is used more often than the second which again appears more frequent than the last. While the probing approach doesn't give an answer if the agents exactly follow an incremental policy, it shows that they give each attribute a different salience. Interestingly, one dominant salience order can be identified across almost all tasks when the agents are shown a 'Dale' dataset. The most important attribute in this order is the *size*, followed by the *shape* and finally the *color*. In few cases, a salience order of '*shape* > *size* > *color*' emerges. However, the environment of the agents impacts the emerged salience order. Introducing more ambiguity by adding more distractors to the scene ('Dale-5' vs 'Dale-2' dataset) makes the second attribute more important in the emerged languages, and in some cases even swaps the importance of *size* and *shape*. When the *color* is the only discriminating attribute in the 'CLEVR color' dataset, it becomes the most important attribute. A possible reason for this preferred salience order might be the number of values for each attribute. As there are only two *sizes* and three *shapes*, they might be easier to learn for the agents and to ground in a referring expression. The agents are exposed to more scenes with the same attribute and the learning is reinforced. The opposite applies to the eight *colors*, that correspond to fewer samples for each *color*.

Finally, showing English referring expressions to the receiver during training as in the referring expression generation task pushes the agents to use a different salience order. Here, the *shape* is now the most important attribute, followed by the *size*, and the *color* is only slightly less important. While the emerged languages

don't use the exact same order as the one identified by [Dale & Reiter \(1995\)](#) in English of '*shape > color > size*', it still seems to be heavily influenced. This doesn't come as a surprise, as this type of training introduces a new bias that the agents are able to exploit.

In conclusion, the results show that the emerged languages don't align perfectly with English referring expressions, and especially not with a *Lang*_{3,16} that is used in English. However, when given a big enough vocabulary size, the emerged languages start to align better, focussing on the attributes *shape* and *size*. Presenting the receiver with English referring expressions during training aligns the used salience order of the emerged language even more with the one used in English.

9 Conclusion and future work

This thesis aims to study the generation and comprehension of referring expressions in language games. Hereby, two agents, a sender and a receiver, are tasked to solve tasks together by learning and communicating messages in an emerged language. More specifically, the agents learn to ground referring expressions that describe objects in visual scenes. As the agents will exploit all present biases in the datasets, three new artificial datasets are created where these biases are precisely controlled for. Objects in the visual scene have three attributes, *shape*, *size* and *color*. The target object is uniquely identifiable, while distractors have at least one differing attribute. While the 'Dale-2' dataset contains only one distractor, the 'Dale-5' dataset contains four distractors. In the 'CLEVR color' dataset, the *color* is the only attribute that is different, while all other attributes are shared between the target object and the distractors. The agents are expected to use these specific patterns to refer to a target object and respectively comprehend the generated referring expression. All unwanted bias is reduced by randomizing the creation of the visual scenes, so that the neural models can only use the attributes instead.

To validate that neural models are able to use this controlled bias, several neural models are trained to solve tasks on these datasets. The results on the *object identification* task show that the models are able to comprehend referring expressions and ground them in bounding boxes, as they can consistently point to the correct target object. In the *referring expression generation* tasks, the models can successfully extract visual features and generate referring expressions to discriminate the target object from the distractors. While the task is solved very well when presented with bounding boxes, the models struggle more when presented with the complete scene at once, especially when many objects are present. However, the scores are far above random guesses and show that the introduced bias in the datasets can be exploited. Finally, the models learn to combine geometric information with the extracted visual features in the *reference resolution* task. The models only manage to predict precise coordinates of the target object given a referring expression when two objects are present. On the other side, when tasked to attend to rougher regions around the target object instead, the models are able to solve the task almost perfectly on all datasets. This shows again that the bias in the dataset is enough to ground referring expressions in a spatial context.

In the next step, the two agents are trained on the same tasks. The increased complexity in the architecture of the language games shows in the results. The agents have more difficulties to solve the tasks. However, in almost all tasks, the agents manage to ground some information in referring expressions of the emerged language. The datasets and the tasks have hereby the highest influence on the success of grounding referring expressions. The simpler 'Dale-2' dataset allows the agents to ground referring expressions the best in their messages. While the agents are still able to solve the tasks in many language games on the 'Dale-5' dataset, they have the biggest problems on the 'CLEVR color' dataset. The main reason seems to be the increased number of distractors in combination with extracting features from the whole visual scene as opposed to bounding boxes for each object. Additionally, the results suggest a difference of difficulty to ground each attributes. The *shape* and *size* seem to be grounded easier than the *color*.

Finally, looking closer at the emerged languages, it can be seen that the used referring expressions don't align perfectly with any referring expression that would be common in English. Interestingly, as common in English referring expressions, the emerged languages seem to assign a salience order to the attributes. On the 'Dale' dataset, the *size* seems to be the most salient attribute, followed by the *shape* and lastly the *color*. While the order is different from one used in English, the alignment can be influenced by introducing English referring expressions during training. Then, the *shape* becomes the most salient attribute. For the 'CLEVR color' dataset, unsurprisingly, the most salient attribute is the *color*. However, the agents seem to utilize some other patterns apart from the three attributes.

This thesis lies the basis for several future experiments. As discussed, some attributes seem to be grounded easier than others. Future work should focus on the reasons for this. For instance, the agents can be

trained on new datasets like the 'CLEVR color' dataset where the only differing attributes are *shape* and *size* respectively.

Secondly, the emerged languages can be studied in more depth. While this thesis focuses on an alignment with English referring expression, other linguistic properties like composition could give better insights in how the referring expressions are structured.

Furthermore, at the moment, the sender has the same architecture across all experiments, and the adapted receiver is mainly responsible for the differences in the referring expressions. It would be interesting however, how the referring expressions change if the receiver is kept stable, but the sender is variable. This could give insights about the influence that each agent has on the structure of referring expressions.

Finally, communication only works in one direction, from the sender to the receiver. The emergence of referring expressions is therefore solely based on the final training loss of the receiver. It might support the agents to have a bidirectional communication in which the receiver can respond, and the agents can agree directly on referring expressions.

References

- Ahrens, K., Kerzel, M., Lee, J. H., Weber, C., & Wermter, S. (2022). Knowing earlier what right means to you: A comprehensive vqa dataset for grounding relative directions via multi-task learning. *IJCAI 2022 Workshop on Spatio-Temporal Reasoning and Learning*.
- Antol, S., Agrawal, A., Lu, J., Mitchell, M., Batra, D., Zitnick, C. L., & Parikh, D. (2015). Vqa: Visual question answering. In *International Conference on Computer Vision (ICCV)*.
- Baroni, M. (2020). Rat big, cat eaten! ideas for a useful deep-agent protolanguage. *ArXiv preprint*.
- Baroni, M., Dessi, R., & Lazaridou, A. (2022). Emergent language-based coordination in deep multi-agent systems. In *Proceedings of the 2022 Conference on Empirical Methods in Natural Language Processing: Tutorial Abstracts* (pp. 11–16). Abu Dhabi, UAE: Association for Computational Linguistics.
- Bartlett, M. & Kazakov, D. (2005). The origins of syntax: from navigation to language. *Connection Science*, 17(3-4), 271–288.
- Bay, H., Tuytelaars, T., & Van Gool, L. (2006). Surf: Speeded up robust features. In A. Leonardis, H. Bischof, & A. Pinz (Eds.), *Computer Vision – ECCV 2006* (pp. 404–417). Berlin, Heidelberg: Springer Berlin Heidelberg.
- Bender, E. M., Gebru, T., McMillan-Major, A., & Shmitchell, S. (2021). On the dangers of stochastic parrots: Can language models be too big? In *Proceedings of the 2021 ACM Conference on Fairness, Accountability, and Transparency, FAccT ’21* (pp. 610–623). New York, NY, USA: Association for Computing Machinery.
- Bender, E. M. & Koller, A. (2020). Climbing towards NLU: On meaning, form, and understanding in the age of data. In *Proceedings of the 58th Annual Meeting of the Association for Computational Linguistics* (pp. 5185–5198). Online: Association for Computational Linguistics.
- Bisk, Y., Holtzman, A., Thomason, J., Andreas, J., Bengio, Y., Chai, J., Lapata, M., Lazaridou, A., May, J., Nisnevich, A., Pinto, N., & Turian, J. (2020). Experience grounds language. In *Proceedings of the 2020 Conference on Empirical Methods in Natural Language Processing (EMNLP)* (pp. 8718–8735). Online: Association for Computational Linguistics.
- Brown, T. B., Mann, B., Ryder, N., Subbiah, M., Kaplan, J., Dhariwal, P., Neelakantan, A., Shyam, P., Sastry, G., Askell, A., Agarwal, S., Herbert-Voss, A., Krueger, G., Henighan, T., Child, R., Ramesh, A., Ziegler, D. M., Wu, J., Winter, C., Hesse, C., Chen, M., Sigler, E., Litwin, M., Gray, S., Chess, B., Clark, J., Berner, C., McCandlish, S., Radford, A., Sutskever, I., & Amodei, D. (2020). Language models are few-shot learners. In *Advances in neural information processing systems*, volume 33 (pp. 1877–1901).
- Cao, K., Lazaridou, A., Lanctot, M., Leibo, J. Z., Tuyls, K., & Clark, S. (2018). Emergent communication through negotiation. In *International Conference on Learning Representations*.
- Chaabouni, R., Kharitonov, E., Bouchacourt, D., Dupoux, E., & Baroni, M. (2020). Compositionality and generalization in emergent languages. In D. Jurafsky, J. Chai, N. Schluter, & J. Tetreault (Eds.), *Proceedings of the 58th Annual Meeting of the Association for Computational Linguistics* (pp. 4427–4442). Online: Association for Computational Linguistics.
- Chaabouni, R., Kharitonov, E., Dupoux, E., & Baroni, M. (2019). Anti-efficient encoding in emergent communication. In *Advances in Neural Information Processing Systems*, volume 32: arXiv.

- Chaabouni, R., Kharitonov, E., Dupoux, E., & Baroni, M. (2021). Communicating artificial neural networks develop efficient color-naming systems. *Proceedings of the National Academy of Sciences*, 118(12).
- Chaabouni, R., Strub, F., Altché, F., Tarasov, E., Tallec, C., Davoodi, E., Mathewson, K. W., Tieleman, O., Lazaridou, A., & Piot, B. (2022). Emergent communication at scale. In *International Conference on Learning Representations*.
- Clark, H. H. & Wilkes-Gibbs, D. (1986). Referring as a collaborative process. *Cognition*, 22(1), 1–39.
- Conneau, A., Kruszewski, G., Lample, G., Barrault, L., & Baroni, M. (2018). What you can cram into a single $\$ \& ! \# *$ vector: Probing sentence embeddings for linguistic properties. In I. Gurevych & Y. Miyao (Eds.), *Proceedings of the 56th Annual Meeting of the Association for Computational Linguistics (Volume 1: Long Papers)* (pp. 2126–2136). Melbourne, Australia: Association for Computational Linguistics.
- Coventry, K. R., Cangelosi, A., Rajapakse, R., Bacon, A., Newstead, S., Joyce, D., & Richards, L. V. (2005). Spatial prepositions and vague quantifiers: Implementing the functional geometric framework. In *Spatial Cognition IV. Reasoning, Action, Interaction* (pp. 98–110). Springer Berlin Heidelberg.
- Dale, R. & Reiter, E. (1995). Computational interpretations of the gricean maxims in the generation of referring expressions. *Cognitive science*, 19(2), 233–263.
- Davidoff, J. (2001). Language and perceptual categorisation. *Trends in Cognitive Sciences*, 5(9), 382–387.
- Deng, J., Dong, W., Socher, R., Li, L.-J., Li, K., & Fei-Fei, L. (2009). Imagenet: A large-scale hierarchical image database. In *2009 IEEE Conference on Computer Vision and Pattern Recognition* (pp. 248–255).
- Dessì, R., Kharitonov, E., & Baroni, M. (2021). Interpretable agent communication from scratch (with a generic visual processor emerging on the side). In A. Beygelzimer, Y. Dauphin, P. Liang, & J. W. Vaughan (Eds.), *Advances in Neural Information Processing Systems*.
- Devlin, J., Chang, M.-W., Lee, K., & Toutanova, K. (2019). Bert: Pre-training of deep bidirectional transformers for language understanding. In *Proceedings of the 2019 Conference of the North American Chapter of the Association for Computational Linguistics: Human Language Technologies, Volume 1 (Long and Short Papers)* (pp. 4171–4186). Minneapolis, Minnesota: Association for Computational Linguistics.
- Dobnik, S., Howes, C., & Kelleher, J. D. (2015). Changing perspective: Local alignment of reference frames in dialogue. In C. Howes & S. Larsson (Eds.), *Proceedings of SemDial 2015 (goDIAL): The 19th Workshop on the Semantics and Pragmatics of Dialogue* (pp. 24–32). Gothenburg.
- Dobnik, S. & Kelleher, J. D. (2013). Towards an automatic identification of functional and geometric spatial prepositions. In *Proceedings of PRE-CogSci 2013 Production of referring expressions – bridging the gap between cognitive and computational approaches to reference at CogSci* (pp. 1–6). Berlin, Germany.
- Dobnik, S. & Silfversparre, V. (2021). The red cup on the left: Reference, coreference and attention in visual dialogue. In *Proceedings of the 25th Workshop on the Semantics and Pragmatics of Dialogue - Full Papers* Potsdam, Germany: SEMDIAL.
- Dobnik, S. & Storckenfeldt, A. (2018). Categorisation of conversational games in free dialogue over spatial scenes. In L. Prévot, M. Ochs, & B. Favre (Eds.), *Proceedings of AixDial - Semdial 2018: The 22st Workshop on the Semantics and Pragmatics of Dialogue* Aix-en-Provence: Semdial.

- Dobnik, S. & Åstbom, A. (2017). (perceptual) grounding as interaction. In V. Petukhova & Y. Tian (Eds.), *Proceedings of Saardial: The 21st Workshop on the Semantics and Pragmatics of Dialogue* (pp. 17–26). Saarbrücken: SemDial.
- Field, A., Blodgett, S. L., Waseem, Z., & Tsvetkov, Y. (2021). A survey of race, racism, and anti-racism in NLP. In *Proceedings of the 59th Annual Meeting of the Association for Computational Linguistics and the 11th International Joint Conference on Natural Language Processing (Volume 1: Long Papers)* (pp. 1905–1925). Online: Association for Computational Linguistics.
- Ghanimifard, M. & Dobnik, S. (2017). Learning to compose spatial relations with grounded neural language models. In C. Gardent & C. Retoré (Eds.), *Proceedings of the 12th International Conference on Computational Semantics (IWCS) — Long papers*.
- Ghanimifard, M. & Dobnik, S. (2019). What goes into a word: generating image descriptions with top-down spatial knowledge. In *Proceedings of the 12th International Conference on Natural Language Generation: Association for Computational Linguistics*.
- Gupta, A., Resnick, C., Foerster, J., Dai, A., & Cho, K. (2020). Compositionality and capacity in emergent languages. In *Proceedings of the 5th Workshop on Representation Learning for NLP* (pp. 34–38).: Association for Computational Linguistics.
- Harnad, S. (1990). The symbol grounding problem. *Physica D* 42: 335-346.
- Harris, C. G. & Stephens, M. J. (1988). A combined corner and edge detector. In *Alvey Vision Conference*, volume 15.
- Havrylov, S. & Titov, I. (2017). Emergence of language with multi-agent games: Learning to communicate with sequences of symbols. In I. Guyon, U. von Luxburg, S. Bengio, H. M. Wallach, R. Fergus, S. V. N. Vishwanathan, & R. Garnett (Eds.), *Advances in Neural Information Processing Systems 30: Annual Conference on Neural Information Processing Systems 2017, December 4-9, 2017, Long Beach, CA, USA* (pp. 2149–2159).
- He, K., Zhang, X., Ren, S., & Sun, J. (2016). Deep residual learning for image recognition. In *2016 IEEE Conference on Computer Vision and Pattern Recognition (CVPR)* (pp. 770–778).
- Hendricks, L. A., Burns, K., Saenko, K., Darrell, T., & Rohrbach, A. (2018). Women also snowboard: Overcoming bias in captioning models. In V. Ferrari, M. Hebert, C. Sminchisescu, & Y. Weiss (Eds.), *Computer Vision – ECCV 2018* (pp. 793–811). Cham: Springer International Publishing.
- Hill, F., Tieleman, O., von Glehn, T., Wong, N., Merzic, H., & Clark, S. (2021). Grounded language learning fast and slow. In *International Conference on Learning Representations*.
- Hofstadter, D. & Sander, E. (2013). *Surfaces and Essence: Analogy as the Fuel and Fire of Thinking*. Basic Books.
- Hudson, D. A. & Manning, C. D. (2019). Gqa: A new dataset for real-world visual reasoning and compositional question answering. In *2019 IEEE/CVF Conference on Computer Vision and Pattern Recognition (CVPR)* (pp. 6693–6702).
- Illykh, N., Emampoor, Y., & Dobnik, S. (2022). Look and answer the question: On the role of vision in embodied question answering. In *Proceedings of the 15th International Conference on Natural Language Generation* (pp. 236–245). Waterville, Maine, USA and virtual meeting: Association for Computational Linguistics.
- Jang, E., Gu, S., & Poole, B. (2017). Categorical reparameterization with gumbel-softmax. In *5th International Conference on Learning Representations, ICLR 2017, Toulon, France, April 24-26, 2017, Conference Track Proceedings*.

- Ji, A., Kojima, N., Rush, N., Suhr, A., Vong, W. K., Hawkins, R., & Artzi, Y. (2022). Abstract visual reasoning with tangram shapes. In *Proceedings of the 2022 Conference on Empirical Methods in Natural Language Processing* (pp. 582–601). Abu Dhabi, United Arab Emirates: Association for Computational Linguistics.
- Johnson, J., Hariharan, B., van der Maaten, L., Fei-Fei, L., Zitnick, C. L., & Girshick, R. (2017a). Clevr: A diagnostic dataset for compositional language and elementary visual reasoning. In *Proceedings of the IEEE conference on computer vision and pattern recognition* (pp. 2901–2910).: arXiv.
- Johnson, J., Hariharan, B., van der Maaten, L., Hoffman, J., Fei-Fei, L., Zitnick, C. L., & Girshick, R. (2017b). Inferring and executing programs for visual reasoning. In *Proceedings of the IEEE international conference on computer vision* (pp. 2989–2998).
- Kelleher, J. D. & Dobnik, S. (2017). What is not where: the challenge of integrating spatial representations into deep learning architectures. In S. Dobnik, Simon; Lappin (Ed.), *Proceedings of the Conference on Logic and Machine Learning in Natural Language (LaML 2017)* Gothenburg: University of Gothenburg Centre for Linguistic Theory and Studies in Probability (CLASP).
- Kharitonov, E. & Baroni, M. (2020). Emergent language generalization and acquisition speed are not tied to compositionality. In *Proceedings of the Third BlackboxNLP Workshop on Analyzing and Interpreting Neural Networks for NLP* (pp. 11–15). Online: Association for Computational Linguistics.
- Kharitonov, E., Chaabouni, R., Bouchacourt, D., & Baroni, M. (2019). EGG: a toolkit for research on emergence of lanGuage in games. In *Proceedings of the 2019 Conference on Empirical Methods in Natural Language Processing and the 9th International Joint Conference on Natural Language Processing (EMNLP-IJCNLP): System Demonstrations* (pp. 55–60). Hong Kong, China: Association for Computational Linguistics.
- Kingma, D. P. & Ba, J. (2015). Adam: A method for stochastic optimization. In Y. Bengio & Y. LeCun (Eds.), *3rd International Conference on Learning Representations, ICLR 2015, San Diego, CA, USA, May 7-9, 2015, Conference Track Proceedings*.
- Kirby, S. (2002). Natural language from artificial life. *Artificial Life*, 8(2), 185–215.
- Kirby, S., Cornish, H., & Smith, K. (2008). Cumulative cultural evolution in the laboratory: An experimental approach to the origins of structure in human language. *Proceedings of the National Academy of Sciences*, 105(31), 10681–10686.
- Klymenko, O., Meisenbacher, S., & Matthes, F. (2022). Differential privacy in natural language processing the story so far. In *Proceedings of the Fourth Workshop on Privacy in Natural Language Processing* (pp. 1–11). Seattle, United States: Association for Computational Linguistics.
- Kollar, T., Tellex, S., Roy, D., & Roy, N. (2010). Toward understanding natural language directions. In *2010 5th ACM/IEEE International Conference on Human-Robot Interaction (HRI)* (pp. 259–266).
- Kottur, S., Moura, J., Lee, S., & Batra, D. (2017). Natural language does not emerge ‘naturally’ in multi-agent dialog. In M. Palmer, R. Hwa, & S. Riedel (Eds.), *Proceedings of the 2017 Conference on Empirical Methods in Natural Language Processing* (pp. 2962–2967). Copenhagen, Denmark: Association for Computational Linguistics.
- Krahmer, E. & van Deemter, K. (2012). Computational generation of referring expressions: A survey. *Computational Linguistics*, 38(1), 173–218.
- Lakoff, G. & Johnson, M. (1980). *Metaphors we live by*. Chicago, IL: University of Chicago.
- Landau, B., Smith, L., & Jones, S. (1998). Object perception and object naming in early development. *Trends in Cognitive Sciences*, 2(1), 19–24.

- Larsson, S. (2018). Grounding as a side-effect of grounding. *Topics in Cognitive Science*, 10(2), 389–408.
- Lauria, S., Bugmann, G., Kyriacou, T., Bos, J., & Klein, A. (2001). Training personal robots using natural language instruction. *IEEE Intelligent Systems*, 16(5), 38–45.
- Lazaridou, A., Hermann, K. M., Tuyls, K., & Clark, S. (2018). Emergence of linguistic communication from referential games with symbolic and pixel input. In *International Conference on Learning Representations*.
- Lazaridou, A., Peysakhovich, A., & Baroni, M. (2017). Multi-agent cooperation and the emergence of (natural) language. In *International Conference on Learning Representations*.
- Lee, J. H., Kerzel, M., Ahrens, K., Weber, C., & Wermter, S. (2022). What is right for me is not yet right for you: A dataset for grounding relative directions via multi-task learning. In L. D. Raedt (Ed.), *Proceedings of the Thirty-First International Joint Conference on Artificial Intelligence, IJCAI-22* (pp. 1039–1045).: International Joint Conferences on Artificial Intelligence Organization. Main Track.
- Lewis, D. K. (1969). *Convention: A Philosophical Study*. Cambridge, MA, USA: Wiley-Blackwell.
- Lin, T.-Y., Maire, M., Belongie, S. J., Hays, J., Perona, P., Ramanan, D., Dollár, P., & Zitnick, C. L. (2014). Microsoft coco: Common objects in context. In *European Conference on Computer Vision*.
- Liu, F., Emerson, G., & Collier, N. (2023). Visual spatial reasoning. In *Transactions of the Association for Computational Linguistics*, volume 11 (pp. 635–651). Cambridge, MA: MIT Press.
- Lowe, D. (1999). Object recognition from local scale-invariant features. In *Proceedings of the Seventh IEEE International Conference on Computer Vision: IEEE*.
- Lu, J., Batra, D., Parikh, D., & Lee, S. (2019). Vilbert: Pretraining task-agnostic visiolinguistic representations for vision-and-language tasks. In *Advances in Neural Information Processing Systems* (pp. 13–23).
- Lu, J., Xiong, C., Parikh, D., & Socher, R. (2017). Knowing when to look: Adaptive attention via a visual sentinel for image captioning. In *2017 IEEE Conference on Computer Vision and Pattern Recognition (CVPR)* (pp. 3242–3250).
- Mao, J., Huang, J., Toshev, A., Camburu, O., Yuille, A., & Murphy, K. (2016). Generation and comprehension of unambiguous object descriptions. In *2016 IEEE Conference on Computer Vision and Pattern Recognition (CVPR)* (pp. 11–20).
- Mitchell, M., van Deemter, K., & Reiter, E. (2013). Generating expressions that refer to visible objects. In *Proceedings of the 2013 Conference of the North American Chapter of the Association for Computational Linguistics: Human Language Technologies* (pp. 1174–1184). Atlanta, Georgia: Association for Computational Linguistics.
- Monroe, W., Hawkins, R., Goodman, N., & Potts, C. (2017). Colors in context: A pragmatic neural model for grounded language understanding. *Transactions of the Association for Computational Linguistics*, 5(0), 325–338.
- Noukhovitch, M., LaCroix, T., Lazaridou, A., & Courville, A. (2021). Emergent communication under competition. In *Proceedings of the 20th International Conference on Autonomous Agents and MultiAgent Systems, AAMAS '21* (pp. 974–982). Richland, SC: International Foundation for Autonomous Agents and Multiagent Systems.
- Qiao, Y., Deng, C., & Wu, Q. (2020). Referring expression comprehension: A survey of methods and datasets. In *IEEE Transactions on Multimedia*, volume 23 (pp. 4426–4440).

- Ramisa, A., Wang, J., Lu, Y., Dellandrea, E., Moreno-Noguer, F., & Gaizauskas, R. (2015). Combining geometric, textual and visual features for predicting prepositions in image descriptions. In *Proceedings of the 2015 Conference on Empirical Methods in Natural Language Processing: Association for Computational Linguistics*.
- Regier, T. (1996). *The human semantic potential: spatial language and constrained connectionism*. Cambridge, Massachusetts, London, England: MIT Press.
- Roy, D. K. (2002). Learning visually grounded words and syntax for a scene description task. *Computer Speech, Language*, 16(3-4), 353–385.
- Sánchez, J., Mazuecos, M., Maina, H., & Benotti, L. (2022). What kinds of errors do reference resolution models make and what can we learn from them? In M. Carpuat, M.-C. de Marneffe, & I. V. Meza Ruiz (Eds.), *Findings of the Association for Computational Linguistics: NAACL 2022* (pp. 1971–1986). Seattle, United States: Association for Computational Linguistics.
- Shah, D. S., Schwartz, H. A., & Hovy, D. (2020). Predictive biases in natural language processing models: A conceptual framework and overview. In *Proceedings of the 58th Annual Meeting of the Association for Computational Linguistics* (pp. 5248–5264). Online: Association for Computational Linguistics.
- Simonyan, K. & Zisserman, A. (2015). Very deep convolutional networks for large-scale image recognition. In Y. Bengio & Y. LeCun (Eds.), *3rd International Conference on Learning Representations, ICLR 2015, San Diego, CA, USA, May 7-9, 2015, Conference Track Proceedings*.
- Skocaj, D., Kristan, M., Vrecko, A., Mahnic, M., Janicek, M., Kruijff, G.-J. M., Hanheide, M., Hawes, N., Keller, T., Zillich, M., & Zhou, K. (2011). A system for interactive learning in dialogue with a tutor. In *2011 IEEE/RSJ International Conference on Intelligent Robots and Systems: IEEE*.
- Steels, L. & Belpaeme, T. (2005). Coordinating perceptually grounded categories through language: a case study for colour. *The Behavioral and brain sciences*, 28, 469–89; discussion 489–529.
- Steels, L. & Loetzsch, M. (2009). Perspective alignment in spatial language. In K. R. Coventry, T. Tenbrink, & J. A. Bateman (Eds.), *Spatial Language and Dialogue*, volume 3 of *Explorations in language and space* (pp. 70–88). Oxford University Press.
- Weidinger, L., Uesato, J., Rauh, M., Griffin, C., Huang, P.-S., Mellor, J., Glaese, A., Cheng, M., Balle, B., Kasirzadeh, A., Biles, C., Brown, S., Kenton, Z., Hawkins, W., Stepleton, T., Birhane, A., Hendricks, L. A., Rimell, L., Isaac, W., Haas, J., Legassick, S., Irving, G., & Gabriel, I. (2022). Taxonomy of risks posed by language models. In *Proceedings of the 2022 ACM Conference on Fairness, Accountability, and Transparency, FAccT '22* (pp. 214–229). New York, NY, USA: Association for Computing Machinery.
- Williams, R. J. (1992). Simple statistical gradient-following algorithms for connectionist reinforcement learning. *Machine Learning*, 8(3-4), 229–256.
- Winograd, T. (1972). Understanding natural language. *Cognitive Psychology*, 3(1), 1–191.
- Wittgenstein, L. (1953). *Philosophische Untersuchungen*. Oxford: Basil Blackwell.
- Xu, H. & Saenko, K. (2016). Ask, attend and answer: Exploring question-guided spatial attention for visual question answering. In B. Leibe, J. Matas, N. Sebe, & M. Welling (Eds.), *Computer Vision – ECCV 2016* (pp. 451–466). Cham: Springer International Publishing.
- Yosinski, J., Clune, J., Bengio, Y., & Lipson, H. (2014). How transferable are features in deep neural networks? In *Proceedings of the 27th International Conference on Neural Information Processing Systems - Volume 2, NIPS'14* (pp. 3320–3328). Cambridge, MA, USA: MIT Press.

- Young, P., Lai, A., Hodosh, M., & Hockenmaier, J. (2014). From image descriptions to visual denotations: New similarity metrics for semantic inference over event descriptions. *Transactions of the Association for Computational Linguistics*, 2, 67–78.
- Zarrieß, S. & Schlangen, D. (2019). Know what you don't know: Modeling a pragmatic speaker that refers to objects of unknown categories. In A. Korhonen, D. Traum, & L. Màrquez (Eds.), *Proceedings of the 57th Annual Meeting of the Association for Computational Linguistics* (pp. 654–659). Florence, Italy: Association for Computational Linguistics.
- Zaslavsky, N., Kemp, C., Regier, T., & Tishby, N. (2018). Efficient compression in color naming and its evolution. *Proceedings of the National Academy of Sciences*, 115(31), 7937–7942.
- Zhang, P., Goyal, Y., Summers-Stay, D., Batra, D., & Parikh, D. (2016). Yin and yang: Balancing and answering binary visual questions. In *2016 IEEE Conference on Computer Vision and Pattern Recognition (CVPR)* (pp. 5014–5022).
- Zitnick, C. L., Parikh, D., & Vanderwende, L. (2013). Learning the visual interpretation of sentences. In *2013 IEEE International Conference on Computer Vision* (pp. 1681–1688).